



88020306



PARAHO OIL SHALE DEMONSTRATION

RETORT OPERATIONS

FINAL REPORT VOLUME 3

#15703728

Paraho

10. 88020306

TP
699

P373
1976
v.3

Under a lease approved by the President of the United States in May, 1972, Paraho, under cooperation with the federal government, to develop, design, construct, and operate a demonstration plant for the processing of oil shale. This Final Report to participants of the Paraho Oil Shale Demonstration is a six-volume document that describes the research and development operations, the design and construction, the estimating, and the retort operations carried out from late-1973 to mid-1976.

PARAHO FINAL REPORT

RETORT OPERATIONS

VOLUME 3

THIS VOLUME 3 IS CONSIDERED CONFIDENTIAL UNDER THE

TERMS OF THE AUGUST 31, 1976 AGREEMENT WITH PARAHO

CORPORATION AND DEVELOPMENT ENGINEERING, INC. OVER,

BECAUSE OF THE PREPARED TO THE GOVERNMENT NOT TO

PUBLISH INFORMATION UNLESS AUTHORIZED BY THE GOVERNMENT

BE STRICTLY CONTROLLED ON A NEED-TO-KNOW BASIS UNTIL

AFTER THIS INFORMATION IS RELEASED BY THE GOVERNMENT

OR PARAHO.

DEVELOPMENT ENGINEERING, INC.

for

The field operations were conducted at the Navajo Shale Oil Shale Research and Development Facility, located near Grand Junction, Colorado. The facility was transferred from the Bureau of Mines (BOM) to the Energy Research and Development Administration (ERDA) when the latter agency was formed in 1974.

The Paraho Oil Shale Demonstration was primarily sponsored by the following seventeen participants with a total cost of \$9.4 million:

Solo Petroleum Company
Southern California Edison Company
The Cleveland-Cliffs Iron Company
Gulf Oil Corporation

WESTON BOND

FLUORESCENT

WESTON BOND
FLUORESCENT
P. O. BOX 100
NEW YORK, N. Y. 10001



Arthur G. McKee and FOREWORD

Kerr-McGee Corporation

Under a lease approved by the President of the United States in May, 1972, Paraho undertook, in cooperation with the federal government, to demonstrate the engineering, economic and environmental feasibility and desirability of the Paraho processes and hardware for retorting oil shale. This Final Report to participants of the Paraho Oil Shale Demonstration is a six-volume document that describes the research and development operations, the engineering design and cost estimating, and the commercial evaluation studies carried out from late-1973 to mid-1976.

Chevron Research Company

THIS VOLUME 3 IS CONSIDERED CONFIDENTIAL UNDER THE
TERMS OF THE PARTICIPANTS AGREEMENTS WITH PARAHO
CORPORATION AND DEVELOPMENT ENGINEERING, INC. MORE-
OVER, BECAUSE OF THE COMMITMENT TO THE GOVERNMENT NOT TO
PUBLISH INFORMATION PREMATURELY, DISTRIBUTION SHOULD
BE STRICTLY CONTROLLED ON A NEED-TO-KNOW BASIS UNTIL
AFTER THIS MATERIAL HAS BEEN PUBLISHED BY THE GOVERNMENT
OR PARAHO.

The field operations were conducted at the Anvil Points Oil Shale Research Facilities located on the Naval Oil Shale Reserves near Rifle, Colorado. Administration of these leased facilities was transferred from the Bureau of Mines (BOM) to the Energy Research and Development Administration (ERDA) when the latter agency was formed in 1974.

After the 56-day retort run, 10,000 barrels of Paraho crude

The Paraho Oil Shale Demonstration was privately sponsored by the following seventeen participants at a total cost of \$9.4 million:

for the U.S. Navy's Energy and Natural Resources Research and Development Office. That Office coordinated

the Sohio Petroleum Company, refined product testing program

Southern California Edison Company

The Cleveland-Cliffs Iron Company

Gulf Oil Corporation

FOREWORD

Under a lease approved by the President of the United States in May, 1972, Paraho undertook, in cooperation with the Federal government, to demonstrate the engineering, economic and environmental feasibility and desirability of the Paraho processes and hardware for restoring oil shale. This Final Report to participants of the Paraho Oil Shale Demonstration is a six-volume document that describes the research and development operations, the engineering design and cost estimating, and the commercial evaluation studies carried out from late-1972 to mid-1976.

THIS VOLUME 1 IS CONSIDERED CONFIDENTIAL UNDER THE TERMS OF THE PARTICIPANTS AGREEMENTS WITH PARAH
CORPORATION AND DEVELOPMENT ENGINEERING, INC. MORE-
OVER, BECAUSE OF THE COMMITMENT TO THE GOVERNMENT NOT TO
PUBLISH INFORMATION PREMATURELY, DISTRIBUTION SHOULD
BE STRICTLY CONTROLLED ON A NEED-TO-KNOW BASIS UNTIL
AFTER THIS MATERIAL HAS BEEN PUBLISHED BY THE GOVERNMENT
OR PARAH.

The field operations were conducted at the Anvil Point Oil Shale Research Facilities located on the Naval Oil Shale Reserve near Rifle, Colorado. Administration of these leased facilities was transferred from the Bureau of Mines (BOM) to the Energy Research and Development Administration (ERDA) when the latter agency was formed in 1974.

The Paraho Oil Shale Demonstration was privately sponsored by the following seventeen participants at a total cost of \$2.4 million:

Gulf Oil Corporation
The Cleveland-Cliffs Iron Company
Southern California Edison Company
Sonic Petroleum Company




Arthur G. McKee and Company
Kerr-McGee Corporation
Shell Development Corporation
Standard Oil Company (Indiana)
The Carter Oil Company (Exxon)
Mobil Research and Development Corporation
Webb-Gary-Chambers-McLoraine (Group)
Sun Oil Company
Texaco Inc.
Phillips Petroleum Company
Atlantic Richfield Company
Marathon Oil Company
Chevron Research Company

These participants received the right to license Paraho's oil shale technology on favorable terms for their support and cooperation which are gratefully acknowledged.

The results of Paraho's operations at Anvil Points are encouraging. They demonstrate that the process works, that the equipment is operable and durable, that thermal efficiencies and yields are high, and that the entire system developed is environmentally acceptable. The extended periods of Paraho retort operations and the results obtained demonstrate this. The evidence includes the 77-day Pilot Plant run and the 56-day Semi-Works run, both of which were terminated voluntarily.

After the 56-day retort run, 10,000 barrels of Paraho crude shale oil were shipped to the nearby Gary Western Refinery and converted into military products. This federally funded work was done for the U.S. Navy's Energy and Natural Resources Research and Development Office. That Office coordinated the refining and the nationwide, refined product testing program and publishing a report entitled:



Production and Refining of 10,000 Bbl. Paraho Crude
Shale Oil Into Military Fuels, U. S. Navy Contract
#N0014-75-C-0055

Final Report

A retorted shale management research project jointly funded by the Bureau of Mines and Paraho will be completed in late-1976 at an estimated additional cost of \$0.5 million. At that time, a report entitled, "Retorted Shale Management", will be issued as the concluding volume of this report.

2.	SUMMARY	2-1
3.	DIRECT HEATED MODE OPERATION	3-1
4.	INDIRECT HEATED MODE OPERATION	4-1
5.	PHYSICAL DESCRIPTION OF EQUIPMENT	
5.1	Pilot Plant	5-1
5.2	Semi-Works Plant	5-8
5.3	Materials Handling Equipment	5-13
5.4	Auxiliary Systems	5-35
6.	STARTUP PROCEDURES	
6.1	Direct Heated Mode	6-1
6.2	Indirect Heated Mode	6-5
7.	COMPUTER DATA PROCESSING	
7.1	Introduction	7-1
7.2	Direct Heated Mode	7-5
7.3	Indirect Heated Mode	7-28

Barah

Production and Refining of 10,000 Bbl. Paraho Crude
Shale Oil Into Military Fuels, U. S. Navy Contract
#W0014-75-C-0052

A reformed shale management research project jointly funded
by the Bureau of Mines and Paraho will be completed in late-
1976 at an estimated additional cost of \$0.5 million. At
that time, a report entitled, "Reformed Shale Management",
will be issued as the concluding volume of this report.

RETORT OPERATIONS

Final Report

Table of Contents

<u>SECTION</u>		<u>PAGE</u>
1.	INTRODUCTION	1-1
2.	SUMMARY	2-1
3.	DIRECT HEATED MODE OPERATION	3-1
4.	INDIRECT HEATED MODE OPERATION	4-1
5.	PHYSICAL DESCRIPTION OF EQUIPMENT	
	5.1 Pilot Plant	5-1
	5.2 Semi-Works Plant	5-8
	5.3 Materials Handling Equipment	5-13
	5.4 Auxiliary Systems	5-35
6.	STARTUP PROCEDURES	
	6.1 Direct Heated Mode	6-1
	6.2 Indirect Heated Mode	6-5
7.	COMPUTER DATA PROCESSING	
	7.1 Introduction	7-1
	7.2 Direct Heated Mode	7-5
	7.3 Indirect Heated Mode	7-28

REPORT OPERATIONS

Final Report

Table of Contents

<u>SECTION</u>	<u>PAGE</u>
1. INTRODUCTION	1-1
2. SUMMARY	2-1
3. DIRECT HEATED MODE OPERATION	3-1
4. INDIRECT HEATED MODE OPERATION	4-1
5. PHYSICAL DESCRIPTION OF EQUIPMENT	
5.1 Pilot Plant	5-1
5.2 Semi-Works Plant	5-8
5.3 Materials Handling Equipment	5-13
5.4 Auxiliary Systems	5-23
6. STARTUP PROCEDURES	
6.1 Direct Heated Mode	6-1
6.2 Indirect Heated Mode	6-2
7. COMPUTER DATA PROCESSING	
7.1 Introduction	7-1
7.2 Direct Heated Mode	7-2
7.3 Indirect Heated Mode	7-28

TABLE OF CONTENTS (CONTD)

APPENDIX SECTIONS

APPENDIX A	-	Pilot Plant Operating Summary
APPENDIX B	-	Semi-Works Plant Operating Summary
APPENDIX C	-	Table of Run Evaluations and Equipment Changes
APPENDIX D	-	Test Data
D - 1	-	Test Data Basis
D - 2	-	Pilot Plant Direct Heated Mode
D - 3	-	Semi-Works Direct Heated Mode
D - 4	-	Semi-Works Indirect Heated Mode
APPENDIX E	-	Equipment Summary List
APPENDIX F	-	Drawings
APPENDIX G	-	Glossary of Terms
APPENDIX H	-	List of Abbreviations

TABLE OF CONTENTS (CONT'D)

APPENDIX SECTIONS

APPENDIX A	-	Pilot Plant Operating Summary
APPENDIX B	-	Semi-Works Plant Operating Summary
APPENDIX C	-	Table of Run Evaluations and Equipment Changes
APPENDIX D	-	Test Data
D - 1	-	Test Data Basis
D - 2	-	Pilot Plant Direct Heated Mode
D - 3	-	Semi-Works Direct Heated Mode
D - 4	-	Semi-Works Indirect Heated Mode
APPENDIX E	-	Equipment Summary List
APPENDIX F	-	Drawings
APPENDIX G	-	Glossary of Terms
APPENDIX H	-	List of Abbreviations

1. INTRODUCTION

2. SUMMARY

**3. DIRECT
MODE**

1 INTRODUCTION

The Paraho Oil Shale Demonstration Project was a program to prove the Paraho Process and Hardware for retorting oil shale.

The term "oil shale" is commonly used to cover a wide range of materials of laminated, solidified sediments, and organic material called kerogen. This is a high molecular weight component of indefinite composition. It is insoluble in common solvents, but undergoes a destructive distillation or pyrolysis at temperatures above 600°F. This results in an "oil" and some gas. The thermal decomposition of oil shale has so far proved to be the only practical method of obtaining the oil from oil shale.

Shale oil has been produced from oil shales in a number of foreign countries for several centuries. This production has been on a small scale. Small scale production has also occurred in the United States. Discovery of petroleum ended the United States shale oil industry in the middle 1850's.

Paraho Corporation and Development Engineering, Inc. developed a vertical kiln technology and the hardware for thermal reactions. The companies used the technology and equipment in the limestone industry. Three large capacity Paraho kilns have been operating commercially for several years. Limestone is a geological kin of oil shale marlstone, and a number of analogies may be drawn.

1. INTRODUCTION

The Paraho Oil Shale Demonstration Project was a program to prove the Paraho process and hardware for recovering oil shale.

The term "oil shale" is commonly used to cover a wide range of materials of laminated, solidified sediments, and organic material called kerogen. This is a high molecular weight compound of indolite composition. It is insoluble in common solvents, but undergoes a destructive distillation at pyrolysis at temperatures above 500°F. This results in an "oil" and gas. The thermal decomposition of oil shale has so far proved to be the only practical method of obtaining the oil from oil shale.

Shale oil has been produced from oil shale in a number of foreign countries for several centuries. This production has been on a small scale. Small scale production has also occurred in the United States. Discovery of petroleum ended the United States shale oil industry in the middle 1850's.

Paraho Corporation and Development Engineering, Inc. developed a vertical kiln technology and the hardware for thermal reactions. The companies used the technology and equipment in the limestone industry. These large capacity Paraho kilns have been operating commercially for several years. Limestone is a geological kind of oil shale material, and a number of analogies may be drawn.

This report covers the retort operations of the Paraho Oil Shale Demonstration Program. The project included a 4 1/2 foot O.D. Pilot Plant retort and 10 1/2 foot O.D. Semi-Works unit. Two operating modes were studied, namely a Direct Heated Mode and an Indirect Heated Mode.

The results of the Demonstration Program show that the Paraho process works, that the equipment is durable, and the overall recovery of hydrocarbon material in the forms of oil and gas is very high. The entire operation is environmentally acceptable.

1.1 OBJECTIVES OF THE PROGRAM

The principal objectives of the program were:

- o Demonstrate the operability of the Paraho retorts for processing oil shale.

- o Confirm that improved temperature and gas and shale flow controls will give oil recoveries:

Direct Heated Retort - 90%

Indirect Heated Retort - 100%

- o Minimize the formation of clinkers.
- o Determine scale factors between 30 inch Pilot retort and 8 1/2 foot Semi-works retort.
- o Test performance of retorts on 25-35 gallon per ton shales

This report covers the test operations of the Paraho Oil
Shale Demonstration Program. The project included a 1 1/2 foot
O.D. Pilot Plant reactor and 10 1/2 foot O.D. Semi-Works unit. Two
operating modes were studied, namely a Direct Heated Mode and an
Indirect Heated Mode.

The results of the Demonstration Program show that the
Paraho process works, that the equipment is durable, and the overall
recovery of hydrocarbon material in the form of oil and gas is very
high. The entire operation is environmentally acceptable.

1.1 OBJECTIVES OF THE PROGRAM

The principal objectives of the program were:

- Demonstrate the operability of the Paraho
reactor for processing oil shale.
- Confirm that improved temperature and gas
and shale flow controls will give oil re-
covery:
- Direct heated reactor - 30%
- Indirect heated reactor - 100%
- Minimize the formation of clinkers.
- Determine shale factors between 30 inch
Pilot reactor and 8 1/2 foot semi-works
reactor.
- Test performance of reactor on 25-35 gallon
per ton shales

- o Demonstrate the engineering and environmental feasibility of the Paraho technology.
- o Determine compaction characteristics of Paraho retorted shale.
- o Develop design basis for a commercial evaluation.

1.2 ACCOMPLISHMENTS OF THE PROJECT

The operations of both the Pilot Plant and the Semi-Works Retorts demonstrate that the process works efficiently, that the equipment is durable, and acceptable environmentally.

Extended operation periods of a 77-day Pilot Plant run and a 56-day Semi-Works run evidence the operability of the process and the hardware. Because of the Projects' research nature, both extended runs were voluntarily terminated. Inspection of the equipment and the operation stability, indicate that the runs could have been extended indeterminately.

Both retorts demonstrated good operability. When electric power outages occurred or auxiliary equipment malfunctioned, the retorts could be placed on standby and left full of hot shale. When ready to resume operations, the equipment would be restarted and operations continued without having to empty, refill, and restart the retort. Runs given in Table No. 1-1 are noteworthy since extended operations with high on-stream factors were demonstrated. On-stream factors of less than 100% indicates the retort was placed on standby for correction of malfunctions and operations were continued.

to demonstrate the engineering and scientific
feasibility of the Paraho technology.

to determine comparative characteristics of
Paraho retorted shale.

to develop design basis for a commercial avail-
ability.

1.1. SUMMARY OF THE PROJECT

The operations of both the Pilot Plant and the Semi-Works
Retorts demonstrate that the process works efficiently, that the
equipment is durable, and acceptable environmentally.

Extended operation periods of a 77-day Pilot Plant run
and a 56-day Semi-Works run evidence the operability of the process
and the hardware. Because of the Project's research nature, both
extended runs were voluntarily terminated. Inspection of the equip-
ment and the operation stability, indicate that the runs could have
been extended indefinitely.

Each retort demonstrated good operability. When electric
power outages occurred or auxiliary equipment malfunctioned, the re-
torts could be placed on standby and left full of hot shale. When
ready to resume operations, the equipment would be restarted and op-
erations continued without having to empty, refill, and restart the
retort. Runs given in Table No. 1-1 are noteworthy since extended
operations with high on-stream factors were demonstrated. On-stream
factors of less than 100% indicate the retort was placed on standby
for correction of malfunctions and operations were continued.

Table 1-1

RETORT OPERABILITY

<u>RETORT</u>	<u>RUN NO.</u>	<u>PROCESS</u>	<u>RUN LENGTH (DAYS)</u>	<u>% ON-STREAM TIME</u>
PILOT PLANT	16	DIRECT HEATED	77.0	99.1
PILOT PLANT	18	DIRECT HEATED	27.3	94.6
PILOT PLANT	19	DIRECT HEATED	12.1	99.8
SEMI-WORKS	7	DIRECT HEATED	56.0	88.4
SEMI-WORKS	20	DIRECT HEATED	25.6	99.7
SEMI-WORKS	23	INDIRECT HEATED	31.2	99.6
SEMI-WORKS	28	INDIRECT HEATED	10.6	100.0

The Paraho kiln over all produced up to 92 - 96 Vol.% Fischer assay recovery of the liquid shale oil, and in addition from 8-12 of the kerogen heating value in a product gas.

The Direct Heated Mode proved a liquid oil recovery of 92 Vol.% F.A. and 96 Vol.% when the C₅+ oil is removed from the gas plus 7200 SCF/Ton of low Btu gas. The Indirect Heated Mode, when using an outside source for heater fuel, produced a liquid oil yield of 92 Vol% F.A. and 95 Vol% C₅+ with 500 SCF/Ton of high Btu gas.

The Direct Heated Mode has demonstrated the burning of re-torted shale's residual carbon as a source of fuel. The Indirect Heated Mode heat requirement has been demonstrated at 380,000 Btu

Table I-1

RETORT OPERABILITY

RETORT	RUN NO.	PROCESS	RUN LENGTH (DAYS)	# ON-STREAM TIME
PILOT PLANT	18	DIRECT HEATED	27.0	99.1
PILOT PLANT	18	DIRECT HEATED	27.3	99.6
PILOT PLANT	19	DIRECT HEATED	12.1	99.8
SEMI-WORKS	7	DIRECT HEATED	26.0	88.4
SEMI-WORKS	20	DIRECT HEATED	25.6	99.7
SEMI-WORKS	23	INDIRECT HEATED	31.2	99.8
SEMI-WORKS	28	INDIRECT HEATED	10.8	100.0

The Paraho Kiln over all produced up to 92 - 98 Vol. % Fischer assay recovery of the liquid shale oil, and in addition from 8-12 of the kerosene heating value in a product gas.

The Direct Heated Mode proved a liquid oil recovery of 92 Vol. % F.A. and 98 Vol. % when the C_2+ oil is removed from the gas plus 2500 SCE/Ton of low Btu gas. The Indirect Heated Mode, when using an outside source for heater fuel, produced a liquid oil yield of 92 Vol. % F.A. and 98 Vol. % C_2+ with 500 SCE/Ton of high Btu gas.

The Direct Heated Mode has demonstrated the burning of re- torred shale's residual carbon as a source of fuel. The Indirect Heated Mode heat requirement has been demonstrated at 380,000 Btu

per ton. under the same operating conditions including yields and product properties.

In the Direct Heated Mode, the Semi-Works unit completed a 25-day confirmation run, including operation with variable studies. The pentane and heavier oil produced during this run averaged 96 Vol% of Fischer Assay oil yield. process flows.

In the Indirect Heated Mode, the Semi-Works was operated for a number of exploratory and variable investigation runs. A 30-day operability run was completed, and some variable studies conducted during this run. A 12-day confirmation run was conducted with the best operating conditions producing a liquid oil yield of 95 Vol% when the C₅+ oil is removed from the gas. This yield is before making fuel deductions for the external heater.

Variable studies with high mass rates were conducted in both the Pilot Plant and the Semi-Works. Based on pounds of shale processed per hour per square foot, the Pilot Plant was tested above 700 and the Semi-Works retort tested above 600 in the Direct Heated Mode. A wide range of process variables was studied including shale grade. Neither retort was tested to the limits of the process variables. Auxiliary equipment limitations also prevented extending process variations beyond the tested ranges.

The shale temperatures in both retorts in the Direct Heated Mode were controllable in low ranges to minimize carbonate decomposition and maximize oil recovery and eliminated clinker formation. Both retorts were operated to accommodate fluctuations in shale size, shale grade, and processing over a wide range of conditions. No major differences were shown between the Pilot Plant and Semi-Works

per ton.

In the Direct Heated Mode, the Semi-Works unit completed a 35-day confirmation run, including operation with variable studies. The pentane and heavier oil produced during this run averaged 95 vols of Fischer Assay oil yield.

In the Indirect Heated Mode, the Semi-Works was operated for a number of exploratory and variable investigation runs. A 30-day operability run was completed, and some variable studies conducted during this run. A 12-day confirmation run was conducted with the best operating conditions producing a liquid oil yield of 95 Vols when the C_2+ oil is removed from the gas. This yield is before making fuel deductions for the external heater.

Variable studies with high mass rates were conducted in both the Pilot Plant and the Semi-Works. Based on pounds of shale processed per hour per square foot, the Pilot Plant was tested above 700 and the Semi-Works reactor tested above 600 in the Direct Heated Mode. A wide range of process variables was studied including shale grade. Neither reactor was tested to the limits of the process variables. Auxiliary equipment limitations also prevented extending process variations beyond the tested ranges.

The shale temperatures in both reactors in the Direct Heated Mode were controllable in low ranges to minimize carbonate decomposition and maximize oil recovery and eliminate clinker formation. Both reactors were operated to accommodate fluctuations in shale size, shale grade, and processing over a wide range of conditions. No major differences were shown between the Pilot Plant and Semi-Works

retorts under the same operating conditions including yields and product properties.

Both retorts were capable of long standby periods, permitting repairs to auxiliaries or for power outages, with continued operation upon resumption of process flows.

Operations of the Paraho retort shows that oil mist formation can be controlled by a change of process variables.

Paraho retorted shale does not require the use of water to control dusting after being placed in canyons near the retort.

retorts under the same operating conditions including yields and product properties.

Both retorts were capable of long standby periods, permitting repairs to auxiliaries or for power outages, with continued operation upon resumption of process flows.

Operations of the Paraho retort shows that oil mist formation can be controlled by a change of process variables.

Paraho retorted shale does not require the use of water for control during after being placed in canyons near the retort.

2. SUMMARY

3. DIRECT
MODE

2 SUMMARY

The Paraho retort contains a number of patented features for accurately controlling the flow of solids and gases. The retort is relatively simple, with only two moving parts. It utilizes counter-current flow and a gravity transport of shale through the retort vessel. The process gas may be introduced into three different levels in the shale bed. The Paraho process involves the accurate control of the mixtures of the process gases as well as their bed locations to control bed temperatures. The Paraho patented processes include the Direct Heated Mode and the Indirect Heated Mode.

2.1 BACKGROUND

When heated, the kerogen in oil shale forms hydrocarbon vapors, fixed gases, and carbon which remains in the retorted shale particles. The function of the retort is to economically recover these energy values from the oil shale.

The oil shales of Colorado, Utah and Wyoming are marlstones containing large quantities of dolomite, a mixture of magnesium and calcium carbonates. These carbonates decompose at elevated temperatures to form metal oxides and carbon dioxide. The endothermic decomposition rate is rapid for magnesium carbonate at temperatures above 1000°F and for calcium carbonate above 1500°F. When the temperature in a retort containing oil shale is elevated, it will first stabilize at the magnesium carbonate decomposition temperature. When additional heat is available after decomposition of the

2 SUMMARY

The Paraho retort contains a number of patented features for accurately controlling the flow of solids and gases. The retort is relatively simple, with only two moving parts. It utilizes counter-current flow and a gravity transport of shale through the retort vessel. The process gas may be introduced into three different levels in the shale bed. The Paraho process involves the accurate control of the mixture of the process gases as well as shale bed locations to control bed temperatures. The Paraho patented processes include the Direct Heated Mode and the Indirect Heated Mode.

2.1 BACKGROUND

When heated, the kerogen in oil shale forms hydrocarbon vapors, fixed gases, and carbon which remains in the retorted shale particles. The function of the retort is to economically recover these energy values from the oil shale.

The oil shales of Colorado, Utah and Wyoming are marlstones containing large quantities of dolomite, a mixture of magnesium and calcium carbonates. These carbonates decompose at elevated temperatures to form metal oxides and carbon dioxide. The endothermic decomposition rate is rapid for magnesium carbonate at temperatures above 1000°F and for calcium carbonate above 1500°F . When the temperature in a retort containing oil shale is elevated, it will first stabilize at the magnesium carbonate decomposition temperature. When additional heat is available after decomposition of the

magnesium carbonate, the temperature will rise and stabilize at the calcium carbonate decomposition temperature. After decomposition of all the carbonates, additional heat will raise the temperature and shale particles tend to fuse together.

In oil shale retorting, the endothermic carbonate decomposition wastes heat and the produced carbon dioxide decreases the heating value of the product gases. Low shale retorting temperatures will minimize the carbonate decomposition and maximize the recovery of oil and gas from the kerogen in the oil shale at very high thermal efficiency, and eliminates clinker formation.

2.2 THE RETORT

The Paraho retort is a stationary, vertical, cylindrical, refractory lined kiln, equipped with shale and gas handling devices. The retort contains a number of patented features for control of the process materials streams. The retort with only two moving parts, the grate mechanism and the raw shale feeder, is shown in Figure 2-1. The unit processes lump size solid material.

The crushed and sized fresh shale is fed into the top hopper through a seal. The shale particles are placed in the retort by a rotary distributor, uniformly across the surface of the shale bed without substantial segregation. The shale continuously flows downwardly, by gravity, as a moving bed. A patented grate mechanism, coordinated with the feed mechanism, removes retorted shale, while maintaining a constant

magnesium carbonate, the temperature will rise and stabilize at the calcium carbonate decomposition temperature. After decomposition of all the carbonates, additional heat will raise the temperature and shale particles tend to fuse together.

In oil shale retorting, the endothermic carbonate decomposition wastes heat and the produced carbon dioxide decreases the heating value of the product gases. Low shale retorting temperatures will minimize the carbonate decomposition and maximize the recovery of oil and gas from the kerogen in the oil shale at very high thermal efficiency, and eliminates nitrate formation.

3.2 THE RETORT

The Paraho retort is a stationary, vertical, cylindrical, refractory lined kiln, equipped with shale and gas handling devices. The retort contains a number of patented features for control of the process materials streams. The retort with only two moving parts, the grate mechanism and the raw shale feeder, is shown in Figure 3-1. The unit processes lump size solid materials.

The crushed and sized fresh shale is fed into the top hopper through a seal. The shale particles are placed in the retort by a rotary distributor, uniformly across the surface of the shale bed without substantial segregation. The shale continuously flows downwardly, by gravity, as a moving bed. A patented grate mechanism, coordinated with the feed mechanism, removes retorted shale, while maintaining a constant

depth of bed. The discharged, retorted shale passes into a conical hopper and exits the kiln environment through a seal.

Gas - air mixtures are injected into the shale bed at different levels. By varying the gas flow rates and mixtures, retorting conditions may be controlled.

A gas distributor is located at the top of the shale bed and an intermediate gas distributor is used.

These gas distributors are tubular with a series of holes along each side. The tubes are mounted horizontally.

of the cylindrical retort.

in the Semi-Warts kiln, the Pilot Plant uses a distributor. As the shale particles must flow

around them, refractory "V" shaped channels are built into the retort wall to recover heat from the shale bed thereby increasing the thermal efficiency of the process. The channels are built into the retort wall to recover heat from the shale bed thereby increasing the thermal efficiency of the process.

the shale bed there is a mechanism of the grate where higher temperatures are developed.

where higher temperatures are developed, the mechanism of the grate was developed and used in limestone calcination operations.


where higher temperatures are developed, the mechanism of the grate was developed and used in limestone calcination operations.

where higher temperatures are developed, the mechanism of the grate was developed and used in limestone calcination operations.


where higher temperatures are developed, the mechanism of the grate was developed and used in limestone calcination operations.

where higher temperatures are developed, the mechanism of the grate was developed and used in limestone calcination operations.

where higher temperatures are developed, the mechanism of the grate was developed and used in limestone calcination operations.



Grain



Grain RETORT

FIGURE 2-1

depth of bed. The discharged, retorted shale passes into a conical hopper and exits the kiln environment through a seal.

Gas - air mixtures are injected into the shale bed at different levels. By varying the gas flow rates and mixtures, retorting conditions may be changed.

A gas distributor near the top of the shale bed and an intermediate gas distributor below the top distributor are used to inject process gases into the shale bed. These gas distributors are tubular with a series of orifices along each side. The tubes are mounted horizontally along chords of the cylindrical retort. In the Semi-Works kiln, each level uses two distributors, while the Pilot Plant uses a single tube at each level. As the distributors are mounted in the bed, shale particles must flow around them. The bottom distributors are inverted "V" shaped channels built into the grate for injecting gas to recover heat from the shale bed thereby increasing the thermal efficiency of the process. The channels also direct the shale flow into the moving mechanism of the grate. The design of the distributor was developed and proven in commercial limestone calcination operations, where higher temperatures are required and conditions are more severe.

The produced oil mist and gases are disengaged from the shale and withdrawn from the retort. One type of off-gas collector used is embedded in shale near the top of the bed. Incoming shale must pass over these off-gas collectors. Another type uses peripheral ports in the top cone of the retort above the surface of the shale bed. A major factor in the high retort

depth of bed. The discharged, retorted shale passes into a conical hopper and exits the kiln environment through a seal.

Gas - air mixtures are injected into the shale bed at different levels. By varying the gas flow rates and mixtures, retorting conditions may be changed.

A gas distributor near the top of the shale bed and an intermediate gas distributor below the top distributor are used to inject process gases into the shale bed. These gas distributors are tubular with a series of orifices along each side. The tubes are mounted horizontally along chords of the cylindrical retort. In the Semi-Works kiln, each level has two distributors, while the Pilot Plant uses a single tube at each level. As the distributors are mounted in the bed, shale particles must flow around them. The bottom distributors are inverted "V" shaped channels built into the grate for injecting gas to recover heat from the shale bed thereby increasing the thermal efficiency of the process. The channels also direct the shale flow into the moving mechanism of the grate. The design of the distributor was developed and proven in commercial limestone calcination operations, where higher temperatures are required and conditions are more severe.

The produced oil mist and gases are disengaged from the shale and withdrawn from the retort. One type of off-gas collector used is embedded in shale near the top of the bed. Incoming shale must pass over these off-gas collectors. Another type uses peripheral ports in the top cone of the retort above the surface of the shale bed. A major factor in the high retort

thermal efficiency is the low off-gas temperature.


2.3 DIRECT HEATED MODE PROCESS

The Direct Heated Mode utilizes combustion in the shale bed produced by distributing air directly into the bed as the crushed and sized fresh shale moves downwardly, Figure 2-2. The shale is fed into the top of the retort and removed at the bottom so as to retain a constant bed depth. A top distributor set and an intermediate distributor set inject process gas-air mixtures into the upper portions of the shale bed. By controlling the quantity and the composition of these gases, several zones are created in the shale bed. The upper zone is a mist formation zone, which, also cools the produced hydrocarbon vapors and gas. It is in this zone that the oil vapors are formed into a stable mist. The shale then proceeds into the retorting zone, the area above the top distributor set. In the retorting zone, the organic matter in the shale is decomposed by the heat in the rising hot gases from the lower combustion zone. The decomposition of oil shale kerogen produces oil vapors and gas. A carbon residue from this thermal reaction remains in the retorted shale particles. The retorted shale then proceeds to the combustion zone below the retorting zone. In this combustion zone, the heat required to retort the shale is produced by combustion of the carbon residue and a small quantity of recycle gas returned to the retort. The shale then moves downwardly from this hot zone to a cooling zone below the intermediate distributor set. In the cooling zone, the heat from the retorted shale is transferred to rising stream of cool recycle gas introduced

thermal efficiency is the low off-gas temperature.


2.3 DIRECT HEATED MODE PROCESS

The Direct Heated Mode utilizes combustion in the shale bed produced by distributing air directly into the bed as the crushed and sized fresh shale moves downwardly. Figure 2-2. The shale is fed into the top of the retort and removed at the bottom so as to retain a constant bed depth. A top distributor set and an intermediate distributor set inject process gas-air mixtures into the upper portions of the shale bed. By controlling the quantity and the composition of these gases, several zones are created in the shale bed. The upper zone is a mist formation zone, which, also cools the produced hydrocarbon vapors and gas. It is in this zone that the oil vapors are formed into a stable mist. The shale then proceeds into the retorting zone, the area above the top distributor set. In the retorting zone, the organic matter in the shale is decomposed by the heat in the rising hot gases from the lower combustion zone. The decomposition of oil shale releases oil vapors and gas. A carbon residue from this thermal reaction remains in the retorted shale particles. The retorted shale then proceeds to the combustion zone below the retorting zone. In this combustion zone, the heat required to retort the shale is produced by combustion of the carbon residue and a small quantity of recycle gas returned to the retort. The shale then moves downwardly from this hot zone to a cooling zone below the intermediate distributor set. In the cooling zone, the heat from the retorted shale is transferred to rising streams of cool recycle gas introduced



PARAHO DIRECT MODE PROCESS
FLOW DIAGRAM

FIGURE 2-2



PARAHO DIRECT MODE PROCESS
FLOW DIAGRAM
FIGURE 2-5

into the bottom of the shale bed through distributors above the grate.

The recycle gas rising through the retorted shale acts as a simple and compact counter-current solids-to-gas heat exchanger. The temperature of the combustion zone is controlled by the composition of the air-gas mixture injected through the two upper level gas distributors. The accurate control of the air-gas mixture produces a high residual carbon combustion.

The ability of the Paraho retort to control the bed movement, gas distribution and combustion with the multiple-level injection system, makes it possible to control heat release rate and maximum internal gas temperature. Control of gas temperatures improves the quality of the off-gas stream, lowers the heat requirements for retorting and increases the physical strength of the retorted shale. Lower heat requirements decrease air needs, which decrease nitrogen dilution in the product gas. The ability to keep the maximum temperatures under control, eliminated the tendency of the bed of shale in the retort to fuse into clinkers.

2.4 INDIRECT HEATED MODE PROCESS

In the Indirect Heated Mode, Figure 2-3, recycle gases are heated in external heaters. These heated gases are then injected into the shale bed through one or both of the upper levels of gas distributors. Cool recycle gas is added through the grate distributor to cool the retorted shale. The rising recycle gas is heated by the retorted shale and when mixed with

into the bottom of the shale bed through distributors above the grate.


The recycle gas rising through the retorted shale acts as a simple and compact counter-current solids-to-gas heat exchanger. The temperature of the combustion zone is controlled by the composition of the air-gas mixture injected through the two upper level gas distributors. The accurate control of the air-gas mixture produces a high residual carbon combustion.

The ability of the Paraho retort to control the bed movement, gas distribution and combustion with the multiple-level injection system, makes it possible to control heat release rate and maximum internal gas temperature. Control of gas temperature improves the quality of the off-gas stream, lowers the heat requirements for retorting and increases the physical strength of the retorted shale. Lower heat requirements decrease air needs, which decrease nitrogen dilution in the product gas. The ability to keep the maximum temperatures under control, eliminated the tendency of the bed of shale in the retort to fuse into clinkers.

2.4 INDIRECT HEATED MODE PROCESS

In the Indirect Heated Mode, Figure 2-3, recycle gases are heated in external heaters. These heated gases are then injected into the shale bed through one or both of the upper levels of gas distributors. Cool recycle gas is added through the grate distributor to cool the retorted shale. The rising recycle gas is heated by the retorted shale and when mixed with

the externally heated recycle gas, sufficiency heat is provided for retorting the shale above the top distributor. Oil mist, as in the Direct Mode, is formed near the top of the bed. The incoming fresh shale cools the produced oil vapors, forming a mist which is entrained in the gas. The result is an oil, of somewhat different composition than the shale oil, and a gas and liquid which are of combustion.



PARAHO INDIRECT HEATED MODE PROCESS
FLOW DIAGRAM

FIGURE 2-3





FIGURE 2-2
FLOW DIAGRAM
PARAHO INDIRECT HEATED MODE PROCESS

the externally heated recycle gas, sufficiency heat is provided for retorting the shale above the top distributor. Oil mist, as in the Direct Heated Mode, is formed near the top of the bed. The incoming fresh shale cools the produced oil vapors, forming a mist which is entrained in the gas. The result is an oil, of somewhat different characteristics than Direct Heated Mode oil, and a high BTU gas undiluted with products of combustion.

the externally heated recycle gas, sufficient heat is provided for reforming the shale above the top distributor. Oil mist, as in the Direct Heated Mode, is formed near the top of the bed. The incoming fresh shale cools the produced oil vapors, forming a mist which is entrained in the gas. The result is an oil, of somewhat different characteristics than Direct Heated Mode oil, and a high BTU gas undiluted with products of combustion.



3. DIRECT
MODE

3 DIRECT HEATED MODE OPERATION

3.1 INTRODUCTION

The Direct Heated Mode process, Appendix F, drawing 4, utilized combustion in the shale bed to supply the heat necessary for retorting. The products of this mode of retorting are mixed gases, oil and coke or carbon. The carbon is dispersed within the shale particles, and in this mode of retorting, it is burned in the retort as the principal source of heat for the process.

Air for the combustion diluted with recycle gas is introduced through the two upper distributors. Only sufficient combustion air is injected into the bed to maintain the desired temperature profile while burning the carbon needed to supply the process heat. Recycle gas flows and products of combustion are controlled to provide enough hot gases to retort the shale in the retort zone above the top distributors and above the combustion zone.

3.2 RETORT CONTROL

The Pilot and Semi-Works retorts have proven to be controllable and operable in the Direct Heated Mode of retorting. A prime requirement for good operation of this mode of retorting is a good startup procedure. The procedure must establish the desired temperature profiles and heat inventory in all parts of the retort. This heat or thermal inventory must be developed in a controlled manner so the oil vapors will form

3 DIRECT HEATED MODE OPERATION

3.1 INTRODUCTION

The Direct Heated Mode process, Appendix F, drawing 4, utilized combustion in the shale bed to supply the heat necessary for retorting. The products of this mode of retorting are mixed gases, oil and coke or carbon. The carbon is dispersed within the shale particles, and in this mode of retorting, it is burned in the retort as the principal source of heat for the process.

Air for the combustion diluted with recycle gas is introduced through the two upper distributors. Only sufficient combustion air is injected into the bed to maintain the desired temperature profile while burning the carbon needed to supply the process heat. Recycle gas flows and products of combustion are controlled to provide enough hot gases to retort the shale in the retort zone above the top distributors and above the combustion zone.

3.2 RETORT CONTROL

The Pilot and Semi-Works retorts have proven to be controllable and operable in the Direct Heated Mode of retorting. A prime requirement for good operation of this mode of retorting is a good startup procedure. The procedure must establish the desired temperature profiles and heat inventory in all parts of the retort. This heat or thermal inventory must be developed in a controlled manner so the oil vapors will form

mist in the gas stream and not condense on the shale particles. Such a startup procedure was developed and is described in Section 6.

In the Direct Heated Mode, temperature and gas analysis measurements were used as a guide to retort operational adjustments. The retort temperatures above the top distributor had to be high enough to maintain combustion. When the temperatures at this point are too low, oxygen will pass through the combustion zone and enter the retorting zone where it would consume oil values. If temperatures were lowered further, combustion above the top distributor would stop and oxygen would appear in the recycle gas. Successful re-establishment of combustion at the top distributor has been attained by slowing the shale rate.

The temperature of the combustion zones were also controlled by adjusting the ratio of air and gas flowing to the distributors for a given air rate per ton of oil shale. To monitor the temperatures in the retorts, temperature sensing probes were installed. Combustion reactions were also monitored by measuring the CO_2 , CO , and O_2 in the product gas. A rapid decrease in CO_2 indicates that combustion of oil had started supplying part of the heat needs.

Early retort operations showed the most effective method of retort control for a given set of experiments was to maintain constant air and gas flows with the analog flow controls. The raw shale feed was set at a predetermined rate

mist in the gas stream and not condense on the shale particles. Such a startup procedure was developed and is described in

Section 2:

In the Direct Heated Model, temperature and gas analysis

measurements were used as a guide to retort operational adjustments. The retort temperatures above the top distributor had to be high enough to maintain combustion. When the temperatures at this point are too low, oxygen will pass through the combustion zone and enter the retorting zone where it would consume oil values. If temperatures were lowered further, combustion above the top distributor would stop and oxygen would appear in the recycle gas. Successful re-establishment of combustion at the top distributor has been attained by slowing the shale rate.

The temperature of the combustion zones were also controlled by adjusting the ratio of air and gas flowing to the distributors for a given air rate per ton of oil shale. To monitor the temperatures in the retorts, temperature sensing probes were installed. Combustion reactions were also monitored by measuring the CO_2 , CO , and O_2 in the product gas. A rapid decrease in CO_2 indicates that combustion of oil had started supplying part of the heat needs.

Early retort operations showed the most effective method of retort control for a given set of experiments was to maintain constant air and gas flows with the analog flow controls. The raw shale feed was set at a predetermined rate

with adjustments made to the rate if the measured retort temperatures and product gas analysis were outside a designated range. Varying the shale rate effectively changed the air and gas rates per ton of raw shale, which in turn changes the retort temperatures and the quantity of carbon dioxide produced by carbonate decomposition.

3.3 PILOT PLANT OPERABILITY

The Pilot Plant proved to be operable beginning with the first startup. Continued improvement in the raw shale storage and handling facilities in control techniques resulted in an excellent record of operability (see the Pilot Plant Operating Summary in the Appendix Section A). Although operable, wide fluctuations in the pressure drop across the retort was experienced in the early runs. Investigations showed the equilibrium was changing due to changes in the size of the shale being fed to the retort. These changes in shale size were a result of an accumulation of size segregation problems throughout the shale storage and handling system. Changes in operating procedures and a re-design of the surge bins and hoppers reduced the segregation and an equilibrium operation could be maintained.

The retort operations were stable over a wide range of operating variables, feed characteristics, and ambient conditions. A minimum of control correction was found to be necessary to adjust for variations in shale size, shale gradation, shale fines, and moisture content of the raw shale feed. When

With adjustments made to the rate of the measured retort temperatures and product gas analysis were outside a designated range. Varying the shale rate effectively changed the air and gas rates per ton of raw shale, which in turn changes the retort temperatures and the quantity of carbon dioxide produced by carbonate decomposition.

3.3 PILOT PLANT OPERABILITY

The Pilot Plant proved to be operable beginning with the first startup. Continued improvement in the raw shale storage and handling facilities in control techniques resulted in an excellent record of operability (see the Pilot Plant Operating Summary in the Appendix Section A). Although operable, wide fluctuations in the pressure drop across the retort was experienced in the early runs. Investigations showed the equilibrium was changing due to changes in the size of the shale being fed to the retort. These changes in shale size were a result of an accumulation of size segregation problems throughout the shale storage and handling system. Changes in operating procedures and a re-design of the surge bins and hoppers reduced the segregation and an equilibrium operation could be maintained.

The retort operations were stable over a wide range of operating variables, feed characteristics, and ambient conditions. A minimum of control correction was found to be necessary to adjust for variations in shale size, shale gradation, shale fines, and moisture content of the raw shale feed. When

major variations in the feed material caused upsets, operational recoveries were generally possible permitting retort operations to be continued. When auxiliary equipment malfunction occurred, the retort could be put on standby until it was corrected and the operation would be resumed. A standby was accomplished by stopping all gas and shale flows and allowing the retort to sit full of hot shale. When ready to resume operation all of the equipment is restarted and flows reset and it was not necessary to empty or refire the retort. Recovery from standby outages for major repair to equipment on the retort or auxiliaries was achieved for standby periods of as long as 18 hours. Standbys for short outages did not affect the equilibrium conditions.

Operational stability was maintained for long periods of time and required only a minimum of operator attention. The Pilot Retort was operated in the Direct Heated Mode to supply an emergency source of purge gas for the Semi-Works Retort when the latter was operated in the Indirect Heated Mode. The Pilot Retort gave excellent operational performance and only required about 15 minutes of the operator's attention during each 8-hour shift. There was one Pilot Plant retort run of 77-days that had an on-stream factor of 99%. The retort was on standby for 1% of the time to repair control valves, blowers, and calibrate conveyor scales. The run was terminated voluntarily due to a planned turnaround on the Semi-Works retort. Pilot Plant inspection showed the retort could have operated for a much longer period. The on-stream factor for a four month period was 95%.

major variations in the feed material caused upsets, operational recoveries were generally possible permitting retrofit operations to be continued. When auxiliary equipment malfunction occurred, the retrofit could be put on standby until it was corrected and the operation would be resumed. A standby was accomplished by stopping all gas and ash flow and allowing the retrofit to sit full of hot ash. When ready to resume operation all of the equipment is restarted and flows reset and it was not necessary to empty or refill the retrofit. Recovery from standby outages for major repair to equipment on the retrofit or auxiliaries was achieved for standby periods of as long as 18 hours. Standbys for short outages did not affect the equilibrium conditions.

Operational stability was maintained for long periods of time and required only a minimum of operator attention. The Pilot Retrofit was operated in the Direct Heated Mode to supply an emergency source of purge gas for the Semi-Works Retrofit when the latter was operated in the Indirect Heated Mode. The Pilot Retrofit gave excellent operational performance and only required about 15 minutes of the operator's attention during each 8-hour shift. There was one Pilot Plant retrofit run of 77-days that had an on-stream factor of 99%. The retrofit was on standby for 1% of the time for repair control valves, blowers, and calibrate conveyor scales. The run was terminated voluntarily due to a planned turnaround on the Semi-Works retrofit. Pilot Plant inspection showed the retrofit could have operated for a much longer period. The on-stream factor for a four month period was 95%.

3.4 PILOT PLANT VARIABLE STUDIES

The variables of air and gas flow rates, shale mass rates, and shale size and quality were explored in the Pilot Plant operations. A broad range of operable conditions was achieved with minor effects on yields and product quality. A listing of all test data is given in the Appendix Section D-1. The Table 3-1 illustrates the range of variables studied during this program:

TABLE 3-1

Item	Max	Min
Total Air Input SCF/T	7330	4240
Air of Total to Top Dist. %	100	46
Air of Total to Mid Dist. %	54	0
Gas at Top Dist. %	50	22
Gas at Mid Dist. %	100	48
Bottom Air SCF/T	400	0
Bottom Recycle SCF/T	15010	6620
Total Recycle Gas SCF/T	18520	12810
Mass Rate lbs/hr/ft ²	720	170
Shale Top Size In.	2	1 3/4
Shale Bottom Size In.	7/8	3/8
Shale Quality GPT	32	18

The effects of shale size and grade were not significant, within the range examined, on the dependent variables of oil yield, gas yield, and product qualities. There was a maximum shale size limitation of two inches. The retort internal clearance did not allow the free flow of

3-4 PILOT PLANT VARIABLE STUDIES

The variables of air and gas flow rates, shale mass rates, and shale size and quality were explored in the Pilot Plant operations. A broad range of operable conditions was achieved with minor effects on yields and product quality. A listing of all test data is given in the Appendix Section D-1. The Table 3-1 illustrates the range of variables studied during this program:

TABLE 3-1

Item	Max	Min
Total Air Input SCF/T	7330	4240
Air of Total to Top Dist. #	100	48
Air of Total to Mid Dist. #	24	0
Gas at Top Dist. #	50	22
Gas at Mid Dist. #	100	48
Bottom Air SCF/T	400	0
Bottom Recycle SCF/T	15010	6020
Total Recycle Gas SCF/T	16520	12810
Mass Rate lbs/hr/ft ²	720	170
Shale Top Size In.	2	1 3/4
Shale Bottom Size In.	3/8	3/8
Shale Quality GPT	32	18

The effects of shale size and grade were not significant, within the range examined, on the dependent variables of oil yield, gas yield, and product qualities. There was a maximum shale size limitation of two inches. The reactor internal clearance did not allow the free flow of

shale particles larger than 2-inch, therefore only ranges of particles up to a 2-inch top size were investigated.

No tests were made to determine the effect of shale particle size distribution or shape factor on the retort operation as the equipment in the crushing and storage plant was not capable of producing the retort feed necessary for this type of variable studies.

The mine was not geared or equipped to selectively mine the thin, rich or lean strati. Therefore, shale grade could not be varied in a planned experiment. However, there was wide variation in grade as shown with no significant change in percent Fischer Assay oil yield.

The division of air between the top and middle distributors was set at approximately 2/3 of the total air input to the top for a major portion of the test program. Good operability was established early in the program under these conditions and the vertical distribution was maintained to examine the effect of other process variables. Pilot Plant Run PP-19 explored a broad range of air distribution between the top and middle gas distributors. There were indications of higher product oil fluidity with higher percentage of total air going to the middle distributor.

Changes in percentage recycle gas in the air-gas mixture used at the top and mid distributors affected location, depth of zone, and temperature on the combustion zones as shown by the bed temperature measurements. By decreasing the recycle

shale particles larger than 1/2-inch, therefore only ranges of particles up to a 1/2-inch top size were investigated.

No tests were made to determine the effect of shale particle size distribution or shape factor on the retort operation as the equipment in the crushing and storage plant was not capable of producing the retort feed necessary for this type of variable studies.

The mine was not geared or equipped to selectively mine the thin, rich or lean strata. Therefore, shale grade could not be varied in a planned experiment. However, there was wide variation in grade as shown with no significant change in percent Fischer Assay oil yield.

The division of air between the top and middle distributors was set at approximately 2/3 of the total air input to the top for a major portion of the test program. Good operability was established early in the program under these conditions and the vertical distribution was maintained to examine the effect of other process variables. Pilot Plant Run PT-19 explored a broad range of air distribution between the top and middle gas distributors. There were indications of higher product oil fluidity with higher percentage of total air going to the middle distributor.

Changes in percentage recycle gas in the air-gas mixture used at the top and mid distributors affected location, depth of zone, and temperature on the combustion zones as shown by the bed temperature measurements. By decreasing the recycle

gas, a higher temperature and shorter combustion zone resulted. For this reason, a low recycle gas ratio was preferred at the top distributor, holding combustion close to the distributor. Therefore, gas mixture adjustments did not have to be made for different process conditions to maintain a desired temperature profile in the retort, for example test PP-16 B-3 and C-1, Appendix D-2.

Recycle gas for the mid distributor was held high, usually about 50% of the total mixture, to lower the combustion intensity in this area and to decrease the amount of recycle gas burned to obtain preferential carbon combustion and increase the depth of combustion above the mid distributor.

Bottom recycle rates were generally set to provide adequate retorted shale cooling in the range of 300°F to 450°F. By increasing the bottom recycle rates, a greater heat recovery is obtained from the retorted shale, thus allowing an equivalent reduction in air requirements. However excessive bottom recycle gas rates can affect the heat transfer rates in the shale preheat zone near the top of the retort which gives poor oil mist formation characteristics. A broad range of operable recycle gas rates was explored in the Direct Heated Mode.

High mass rates were considered to be a major item of economic importance. For this reason, many of the early variable studies were directed toward this goal. Good operations were achieved at mass rates of up to 650 lbs/hr/ft². This throughput was calculated on the weight of dry raw shale per hour

gas, a higher temperature and shorter combustion zone resulted. For this reason, a low recycle gas ratio was preferred at the top distributor, holding combustion close to the distributor. Therefore, gas mixture adjustments did not have to be made for different process conditions to maintain a desired temperature profile in the reactor, for example test P-15 B-3 and C-1, Appendix D-2.

Recycle gas for the mid distributor was held high, usually about 50% of the total mixture, to lower the combustion intensity in this area and to decrease the amount of recycle gas burned to obtain preferential carbon combustion and increase the depth of combustion above the mid distributor.

Bottom recycle rates were generally set to provide adequate retorted shale cooling in the range of 300°F to 450°F. By increasing the bottom recycle rates, a greater heat recovery is obtained from the retorted shale, thus allowing an equivalent reduction in air requirements. However excessive bottom recycle gas rates can affect the heat transfer rates in the shale preheat zone near the top of the reactor which gives poor oil mix formation characteristics. A broad range of operable recycle gas rates was explored in the Direct Heated Mode.

High mass rates were considered to be a major item of economic importance. For this reason, many of the early variable studies were directed toward this goal. Good operations were achieved at mass rates of up to 650 lbs/hr/ft². This throughput was calculated on the weight of dry raw shale per hour

per square foot of bed cross section in the unrestricted section of the retort (4.909 ft^2 for the Pilot Plant). A short period of operation was achieved at 720 lbs/hr/ft^2 but problems occurred with auxiliaries, and the test was not repeated. Adjustment of gas and air orifice meters, bed heights, and distributor gas entry velocities would be necessary before problems associated with high mass rates could be clearly defined.

A representative series of Pilot Plant stable operations representing a moderate range of variables is presented in Tables 3-2 and 3-3. Some individual test periods have been combined where operating conditions are comparable. Table 3-2 is a brief summary of the operating conditions and yields. Table 3-3 shows the product properties of these tests and the relationship of total air input to product gas quantity and quality is indicated. The total product gas quantity is a function of air input because the diluent gases present (mainly nitrogen) are proportional to air input. Also, with a greater air input more carbonates are decomposed producing more CO_2 . Retorted shale properties change with the relative air rates (SCF/T) being used. When the SCF/T of air is increased, combustion temperatures are raised, more residual carbon is burned, and more carbonates are decomposed. These changes in retorted shale properties can be seen in the test data from Pilot Plant Direct Heated Mode operations, Appendix Table D-2, Run PP-16, Test A-9 vs. Run PP-19, Test D.

Oil properties show higher API gravity and lower

per square foot of bed cross section in the unrestricted section of the reactor (0.909 ft² for the Pilot Plant). A short period of operation was achieved at 750 lbs/hr/ft² but problems occurred with auxiliaries, and the test was not repeated. Adjustment of gas and air orifice meters, bed heights, and distributor gas entry velocities would be necessary before problems associated with high mass rates could be clearly defined.

A representative series of Pilot Plant stable operations representing a moderate range of variables is presented in Tables 3-2 and 3-3. Some individual test periods have been combined where operating conditions are comparable. Table 3-2 is a brief summary of the operating conditions and yields. Table 3-3 shows the product properties of these tests and the relationship of total air input to product gas quantity and quality as indicated. The total product gas quantity is a function of air input because the diluent gases present (mainly nitrogen) are proportional to air input. Also, with a greater air input more carbonates are decomposed producing more CO₂. Reported shale properties change with the relative air rates (SCP/T) being used. When the SCP/T of air is increased, combustion temperatures are raised, more residual carbon is burned, and more carbonates are decomposed. These changes in reported shale properties can be seen in the test data from Pilot Plant Direct Heated Mode operations, Appendix Table D-2, Run PP-16, Test A-2 vs. Run PP-19, Test D. Oil properties show higher API gravity and lower

TABLE 3-2

PILOT PLANT - DIRECT HEATED MODE OPERATING CONDITIONS AND YIELDS

Run No.	Test No.	Combined Test Length, Hrs.	OPERATING CONDITIONS				PRODUCT YIELDS		
			Mass Rate, Lbs/Hr/Ft ²	Air Input Total SCF/T	% To Top Dist.	Top & Mid Gas, SCF/T	Bottom Gas, SCF/T	Oil Collected Wt% F.A.	Gas (Wet) SCF/T
PP-5	A	16	181	6,730	100	3,900	13,450	89	10,900
PP-5	D, E	32	380	4,330	76	2,980	10,110	91	5,770
PP-9	B	10	633	4,580	68	2,660	12,590	92	5,350
PP-10	B, C, D-2	40	614	4,750	70	2,570	12,820	91	5,250
PP-16	A-3 - A-7	120	399	5,390	81	3,030	13,920	92	8,080
PP-19	J	24	425	5,170	56	2,110	13,600	90	7,740

TABLE 3-3

PILOT PLANT - DIRECT HEATED MODE PRODUCT PROPERTIES

Run No.	Test No.	Combined Test Length, Hrs.	Total Air Input, SCF/T	PRODUCT OIL PROPERTIES			PRODUCT GAS PROPERTIES (Dry)		
				Gravity °API	Visc. SUS @130° F	Ramsbottom Carbon Wt%	N ₂ Vol%	CO ₂ Vol%	Gross Heating Va. BTU/SCF
PP-5	A	16	6,730	19.6	145	N.A.	62.6	28.6	83
PP-5	D, E	32	4,330	21.6	88	1.60	62.6	28.6	117
PP-9	B	10	4,580	21.1	93	1.34	65.1	23.5	116
PP-10	B, C, D-2	40	4,750	21.2	96	1.67	65.3	22.5	121
PP-16	A-3 - A-7	120	5,390	20.4	108	1.65	62.7	29.4	77
PP-19	J	24	5,170	20.2	112	2.24	59.3	25.0	124

BB-70	2	34	2'110	30'3	713	3'34	28'3	32'0	754
BB-70	W-2 - W-1	150	2'300	30'4	708	7'02	03'3	38'4	11
BB-70	B'C'D-S	40	4'120	37'3	00	7'01	02'3	33'2	757
BB-0	B	70	4'280	37'7	03	7'34	02'7	33'2	770
BB-2	D' E	35	4'310	37'0	88	7'00	03'0	38'0	771
BB-2	Y	70	0'130	10'0	742	W'Y'	03'0	38'0	83

NO.	NO.	RENDERING	INSTRUMENT	DATE	TIME	LOCATION	NO.	NO.	TIME
NOV	150	Leaf	Leaf	1951	11	CLAYTON ALEC. 2ND BARRACKS	13	1018	WINDSCL
		Computed				BROOKLYN OIL BROOKLYN			CLAYTON ALEC. 2ND BARRACKS
						BROOKLYN OIL BROOKLYN			BROOKLYN OIL BROOKLYN

EXTRA 1700 - DIRECT REVEAL MODE BROOKLYN BROOKLYN

EXTRA 3-3

Ramsbottom carbon content with the lower air input. Oil yield shows little variation with these changes.

The complete test data for the Direct Heated Mode Operations in the Pilot Plant is shown in Appendix Section D-2.

3.5 SEMI-WORKS OPERABILITY

The demonstration of operability in the Semi-Works retort began with Run SW-7. This operation covered 56 days and achieved an operating factor of 88.4%. A complete summary of all retort operations is given in Appendix Section D-2.

A 26 day conformation demonstration run for the Direct Heated Mode was made after correcting the mechanical and operating problems that were apparent earlier in the program, see Table 3-4. This run, SW-20, shows a 99.7% operating factor and provides the design basis for commercial evaluation. Five power outages accounted for 50% of the total time lost. An additional standby period was necessary for the repair of a retorted shale conveyor belt.

Only a momentary effect of these standbys could be seen in the temperatures, products, or other data, amply demonstrating the stability of the process.

During previous operations, standby periods of up to 21 hours have been sustained in the Semi-Works retort. Operation was continued by restarting the equipment and resetting all flows, without refiring.

Hamabottom carbon content with the lower air input. Oil yield shows little variation with these changes.

The complete test data for the Direct Heated Mode Operations in the Pilot Plant is shown in Appendix Section D-2.

3.5 SEMI-WORKS OPERABILITY

The demonstration of operability in the Semi-Works report began with Run SW-7. This operation covered 56 days and achieved an operating factor of 98.4%. A complete summary of all report operations is given in Appendix Section D-2.

A 56 day confirmation demonstration run for the Direct Heated Mode was made after correcting the mechanical and operating problems that were apparent earlier in the program, see Table 3-4. This run, SW-20, shows a 99.7% operating factor and provides the design basis for commercial evaluation. Five power outages accounted for 20% of the total time lost. An additional standby period was necessary for the repair of a rotted shale conveyor belt.

Only a momentary effect of these standbys could be seen in the temperatures, products, or other data, amply demonstrating the stability of the process.

During previous operations, standby periods of up to 21 hours have been sustained in the Semi-Works report. Operation was continued by restarting the equipment and resetting all flows, without retiring.

MAJOR EQUIPMENT REVISIONS TO THE SEMI-WORKS PLANT

TABLE 3-4

1. Raw and Retorted weigh belt systems were revised to provide greater weighing accuracy and reliability.
2. Gas sampling and analysis was revised including continuous O₂ analysis and on-line gas chromatograph.
3. Replaced and repositioned temperature-pressure probe.
4. Installed a raw shale polishing screen to reduce fines in retort feed.
5. Installed a coalescer and revised the oil handling system to increase the oil recovery efficiency.
6. Installed condensate drains on all recycle gas lines.
7. Double bottom rotary seals of a revised design were installed to reduce gas leakage.
8. Revisions were made to the raw shale rotary distributor for improved shale feed.
9. Revised the hydraulic system to improve control of the discharge grate.

MAJOR EQUIPMENT REVISIONS TO THE SEMI-WORKS PLANT

TABLE 3-4

1. Raw and Retorted weigh belt systems were revised to provide greater weighing accuracy and reliability.
2. Gas sampling and analysis was revised including continuous O₂ analysis and on-line gas chromatograph.
3. Replaced and repositioned temperature-pressure probe.
4. Installed a raw shale polishing screen to reduce fines in retort feed.
5. Installed a coalescer and revised the oil handling system to increase the oil recovery efficiency.
6. Installed condensate drains on all recycle gas lines.
7. Double bottom rotary seals of a revised design were installed to reduce gas leakage.
8. Revisions were made to the raw shale rotary distributor for improved shale feed.
9. Revised the hydraulic system to improve control of the discharge grate.

The off-gas collector systems for the Pilot Plant and Semi-Works retorts are shown in Drawings 8 and 9 in Appendix F. Gases leave the shale bed at a much higher velocity in the Semi-Works retort because of the greater reduction in flow area entering the collector. This change in flow pattern and velocity contributed to a greater amount of sediment carry-over from the Semi-Works retort as shown by oil analysis from Test Data in Appendix D-2 and D-3.

A specific evaluation of the off-gas collection technique was made during Runs SW-12 through 16 by the removal of the submerged off-gas collectors. Other process and equipment changes completed at the same time, made an evaluation of this change difficult. These runs were not successful in sustaining a good operation and a return to the submerged collectors and lower distributor orifice velocity changes were made. The runs testing the elimination of collectors were hampered by several mechanical and operational problems that may have been responsible for the difficulties encountered.

The process function of the air-gas distributor system used for the Semi-Works retort is the same in the Pilot Plant. The principles of air-gas mixtures and the effect of this variable were identical in both retorts. The mechanical configuration for the Semi-Works are shown on Drawing 9 in the Appendix Section F.

The off-gas collector systems for the Pilot Plant

and Semi-Works retorts are shown in Drawings 8 and 9 in Appendix F. Gases leave the shale bed at a much higher velocity in the Semi-Works retort because of the greater reduction in flow area entering the collector. This change in flow pattern and velocity contributed to a greater amount of sediment carry-over from the Semi-Works retort as shown by oil analysis from Test Data in Appendix D-2 and D-3.

A specific evaluation of the off-gas collection

technique was made during Runs SW-12 through 15 by the removal of the submerged off-gas collectors. Other process and equipment changes completed at the same time, made an evaluation of this change difficult. These runs were not successful in sustaining a good operation and a return to the submerged collectors and lower distributor orifice velocity changes were made. The runs testing the elimination of collectors were hampered by several mechanical and operational problems that may have been responsible for the difficulties encountered.

The process function of the air-gas distributor

system used for the Semi-Works retort is the same in the Pilot Plant. The principles of air-gas mixtures and the effect of this variable were identical in both retorts. The mechanical configuration for the Semi-Works are shown on Drawing 9 in the Appendix Section F.

The top distributors were redesigned following Semi-Works Run SW-5. The 10-inch water-cooled stainless pipe distributors were replaced with 6-inch water-cooled steel pipes to provide a 38% reduction in the resistance to shale flow. The objective of this change was an increase in retort operability for a wide range of process conditions. The results obtained in the demonstration Run SW-7 following the change, were a good indication of the success.

Early Semi-Works runs encountered problems similar to those of the Pilot Plant, with fluctuations in pressure drop across the retort because of changes in the size of the raw shale feed. These variations were closely associated with segregation that was occurring in the shale storage bins. Several changes in operating procedures and equipment including the addition of a polishing screen, drawing 1 of Appendix F, significantly improved the retort operation.

3.6 SEMI-WORKS OPERATING CONDITIONS

In Semi-Works operations, one objective was to demonstrate process operability and another to confirm the design basis for the commercial evaluation portion of the Paraho Oil Shale Demonstration. Concurrent with these operations, the effects of a wide range of process variables were investigated in the Pilot Plant. To demonstrate operability and product yields, operating conditions in the Semi-Works retort were selected from the more promising areas of investigation completed on the Pilot Plant. Therefore, many of the operating

The top distributors were redesigned following Semi-Works Run SW-2. The 10-inch water-cooled stainless pipe distributors were replaced with 6-inch water-cooled steel pipes to provide a 38% reduction in the resistance to shale flow. The objective of this change was an increase in retort operability for a wide range of process conditions. The results obtained in the demonstration Run SW-7 following the change, were a good indication of the success.

Early Semi-Works runs encountered problems similar to those of the Pilot Plant, with fluctuations in pressure drop across the retort because of changes in the size of the raw shale feed. These variations were closely associated with segregation that was occurring in the shale storage bins. Several changes in operating procedures and equipment including the addition of a polishing screen, drawing 1 of Appendix F, significantly improved the retort operation.

3.6 SEMI-WORKS OPERATING CONDITIONS

In Semi-Works operation, one objective was to demonstrate process operability and another to confirm the design basis for the commercial evaluation portion of the Paraho Oil Shale Demonstration. Concurrent with these operations, the effects of a wide range of process variables were investigated in the Pilot Plant. To demonstrate operability and product yields, operating conditions in the Semi-Works retort were selected from the more promising areas of investigation completed on the Pilot Plant. Therefore, many of the operating

conditions for the Semi-Works were duplications or near duplications of some of the Pilot Retort operations.

As in Pilot Plant operation, lower total air input reduced the oil viscosity and increased the API gravity. Tables 3-5 and 3-6 show periods of stable operating conditions, product yields, and product properties representative of high operability Semi-Works runs.

A complete listing of Semi-Works test data for the direct Heated Mode is presented in Appendix Section D-3 of this report. The test data tabulation presents the results of 70 test periods. Variable investigations were not as extensive as in the Pilot Plant operations but cover a wide range of operating conditions.

A typical particle size consist for Semi-Works operations achieved through the crushing and screening operation is shown by the screen analysis in Tables 3-7 and 3-8. A specific effect on retorting operations is the fines material carried with the primary coarse and screened raw shale feed to the retort. As shown on Table 3-7, 5.1% of the feed material is finer than the 1/2 inch screen being used in the crushing plant. Good retort operation was maintained during Semi-Works Run SW-20 when as much as 8% of the feed material was finer than the 1/2 inch screen.

Included in Table 3-7 are the calculated values D_a , D_v , and $\frac{D_a}{D_v}$. D_a is the area-oriented average particle diameter, ignoring the -8 mesh material. D_v is the volume-oriented

conditions for the Semi-Works were duplications or near duplications of some of the Pilot Plant operations.

As in Pilot Plant operation, lower total air input reduced the oil viscosity and increased the API gravity. Tables 3-5 and 3-6 show periods of stable operating conditions, product yields, and product properties representative of high operability Semi-Works runs.

A complete listing of Semi-Works test data for the direct heated mode is presented in Appendix Section D-3 of this report. The test data tabulation presents the results of 10 test periods. Variable investigations were not as extensive as in the Pilot Plant operations but cover a wide range of operating conditions.

A typical particle size analysis for Semi-Works operations achieved through the crushing and screening operation is shown by the screen analysis in Tables 3-7 and 3-8. A specific effect on reorting operations is the fines material carried with the primary coarse and screened raw shale feed to the reort. As shown on Table 3-7, 5.1% of the feed material is finer than the 1/2 inch screen being used in the crushing plant. Good reort operation was maintained during Semi-Works Run SW-20 when as much as 8% of the feed material was finer than the 1/2 inch screen.

Included in Table 3-7 are the calculated values D_v , D_v , and D_v . D_v is the area-oriented average particle diameter, ignoring the -8 mesh material. D_v is the volume-oriented

TABLE 3-5

SEMI-WORKS - DIRECT HEATED MODE OPERATING CONDITIONS AND YIELDS

Run No.	Test No.	Combined Test Length, Hrs.	OPERATING CONDITIONS					PRODUCT YIELD	
			Mass Rate Lbs/hr/ft ²	Air Input		Top & Mid Gas SCF/T	Bottom Gas SCF/T	Oil Collected Wt% F.A.	Gas (Wet) SCF/T
				Total SCF/T	% To Top Dis				
SW-5	A-2	32	422	5,180	67	2,930	15,140	92	8,000
SW-7	A,B,B-1	80	359	5,580	100	3,700	13,870	94	9,190
SW-7	PC-1,2,3	40	404	4,700	67	2,910	14,570	94	5,120
SW-19	A,A-1	32	476	4,410	66	3,150	11,670	91	7,240
SW-20	A-1 - A-5	120	462	4,560	82	2,620	11,820	90	7,030
SW-20	A-9 - A-16	183	448	4,740	82	2,620	11,890	92	7,070

2A-30	V-3 - W-7a	103	449	4'140	85	5'830	71'830	85	1'010
2A-30	W-1 - V-2	150	483	4'260	85	5'830	77'850	80	1'020
2A-7a	V-9-V-1	35	416	4'410	88	3'120	77'810	87	1'340
2A-1	BC-1'5'2	40	404	4'100	91	5'910	74'210	84	2'730
2A-1	V-9-V-1	80	383	2'280	100	3'100	73'810	84	2'781
2A-2	W-5	35	435	2'180	41	5'830	72'140	35	8'000

NO- MAN	NO- DEEP	FOUNDER/HTW: DEEP - COMPIRED	TYPE/HT/TF: WAVE HTW	2CL/1.2 DOCV	2A/0.78 1.20	2CL/1.2 JOB 1 HT9	2CL/1.2 BOTTOM	HTF 1.5"	HTF COLLECTED CNS (MCC)	2CL/1.2 CNS (MCC)
------------	-------------	------------------------------------	-------------------------	-----------------	-----------------	----------------------	-------------------	----------	----------------------------	----------------------

OBSERVING CONDITIONS

MOONCL ALIEND

2A-30-2 - DIRECTLY NAMED MOON OBSERVING CONDITIONS AND ALIEND

TABLE 3-2




TABLE 3-6

SEMI-WORKS - DIRECT HEATED MODE PRODUCT PROPERTIES

Run No.	Test No.	Combined Test Length,Hrs.	Total Air Input	PRODUCT OIL PROPERTIES			PRODUCT GAS PROPERTIES (Dry)		
				Gravity °API	Vis.SUS @130°F	Ramsbottom Carbon,Wt%	N ₂ Vol.%	CO ₂ Vol.%	Gross Heating Val BTU/SCF
SW-5	A-2	32	5,180	20.4	120	1.73	62.1	25.7	113
SW-7	A,B,B-1	80	5,580	19.6	146	2.22	61.5	26.1	99
SW-7	PC-1,-2,-3	40	4,700	21.4	95	1.48	64.5	22.6	127
SW-19	A, A-1	32	4,410	21.4	90	2.08	62.7	25.5	129
SW-20	A-1 - A-5	120	4,560	21.3	91	2.22	64.5	24.5	122
SW-20	A-9 - A-16	183	4,740	21.4	88	1.40	66.3	24.0	118

TABLE 3-7

TYPICAL RAW SHALE SCREEN ANALYSIS

Data from Run SW-20

SCREEN ANALYSIS SIZE - INCHES	PASSING - WT%	RETAINED - WT%
	PASSING - WT%	RETAINED - WT%
2.50	97.9	2.1
2.00	84.8	13.1
1.50	52.0	32.8
1.050	30.3	21.7
0.742	15.0	15.3
0.525	5.1	9.9
0.371	3.7	1.4
0.263	2.4	1.3
0.185	1.9	0.5
0.093	1.2	0.7
PAN	0	1.2

$$Da = 1.080$$

$$Dv = 1.464$$

$$Dv/Da = 1.355$$

TABLE 3-7

TYPICAL RAW SHALE SCREEN ANALYSIS

Data from Run SW-20

SCREEN ANALYSIS SIZE - INCHES	PASSING - WT%	RETAINED - WT%
2.50	97.9	2.1
2.00	84.8	15.2
1.50	52.0	48.0
1.050	30.3	69.7
0.743	12.0	88.0
0.525	2.1	97.9
0.371	2.7	97.3
0.303	2.4	97.6
0.182	1.9	98.1
0.093	1.3	98.7
PAH	0	100

$D_{50} = 1.080$
 $D_{40} = 1.464$
 $D_{10}/D_{50} = 1.352$

average particle diameter. Correlations of pressure drop, impaction, and yield data versus **TABLE 3-8** may be used.

TYPICAL RAW SHALE

SCREEN ANALYSIS OF PAN FRACTION

Data from SW-20

<u>SCREEN SIZE</u>	<u>PASSING - WT%</u>	<u>RETAINED - WT%</u>
+8 Mesh	93.95	6.05
+14 Mesh	63.38	30.57
+28 Mesh	44.41	18.97
+48 Mesh	29.16	15.25
+100 Mesh	16.49	12.67
-100 Mesh	0.02	16.47
% Loss		0.02
% of Pan		

Data for **TABLE 3-9** are typical operating conditions and yields representing the Semi-Works Direct Heated Mode of Operation is given in **TABLE 3-9**. These data are the average of 13 test periods run at the same rate. Flows were held within a 1.5% standard deviation and shale rate within 2.4% between each test. A computer heat and material balance for these composite data is shown in Section 7 under Direct Heated Mode Computer Balances. The corresponding raw and retorted shale properties are shown on **TABLE 3-10**.

The product oil recovered and measured in the tanks for the Semi-Works retort were demonstrated as 92 wt% P.A. with a standard deviation of 4.4% between tests during the Semi-Works Pan SW-20. This yield was verified by operations totaling 307 hours. Yield value is based on actual recovered oil

WEST

IN BOARD

FL

WEST

SS

TON FIBER

average particle diameter. Correlations of pressure drop, impaction, and yield data versus these values may be used.

The retorted shale particles are quite friable, and therefore, breakage occurs when a sample is run through screen analysis equipment. This should be taken into consideration in reviewing the typical screen analysis shown in Figure 3-1. This figure shows the effect on handling the retorted shale. One sample was collected at the retorted shale sample hopper. Another sample passed through a 15 foot vertical chute to a 30 foot long, 16" diameter screw conveyor and was collected after a 10 foot vertical drop into a drum container.

Data for specific operating conditions and yields representing the Semi-Works Direct Heated Mode of Operation is given in Table 3-9. These data are the average of 13 test periods run at the same conditions. Gas and air flows were held within a 1.5% standard deviation and shale rate within 2.4% between each test. A computer heat and material balance for these composite data is shown in Section 7 under Direct Heated Mode Computer Balances. The corresponding raw and retorted shale properties are shown on Table 3-10.

The product oil recovered and measured in the tanks for the Semi-Works retort were demonstrated as 92 wt% F.A. with a standard deviation of 4.4% between tests during the Semi-Works Run SW-20. This yield was verified by operations totaling 303 hours. Yield value is based on actual recovered oil

average particle diameter. Correlations of pressure drop, inspection, and yield data versus these values may be used.

The retorted shale particles are quite friable, and therefore, breakage occurs when a sample is run through screen analysis equipment. This should be taken into consideration in reviewing the typical screen analysis shown in Figure 3-1. This figure shows the effect on handling the retorted shale.


One sample was collected at the retorted shale sample hopper. Another sample passed through a 15 foot vertical chute to a 30 foot long, 16" diameter screw conveyor and was collected after a 10 foot vertical drop into a drum container.

Data for specific operating conditions and yields representing the Semi-Works Direct Heated Mode of Operation is given in Table 3-2. These data are the average of 15 test periods run at the same conditions. Gas and air flows were kept within a 1.5% standard deviation and shale rate within 1.5% between each test. A computer heat and material balance for these composite data is shown in Section 7 under Direct Heated Mode Computer Balances. The corresponding raw and retorted shale properties are shown on Table 3-10.


The product oil recovered and measured in the tanks for the Semi-Works retrofit were demonstrated as 92 wt% F.A. with a standard deviation of 4.5% between tests during the Semi-Works Run SW-30. This yield was verified by operations totaling 365 hours. Yield value is based on actual recovered oil

TYPICAL RAW AND RETORTED SHALE SIZE DISTRIBUTION

Figure 3-1



SCREEN SIZE, INCHES



1-51

1-51

TABLE 3-9

PARAHO DIRECT MODE OPERATING CONDITIONS
AVERAGE DATA FROM SEMI-WORKS RUN SW-20 TEST A
EXCEPT A-6 AND A-7

Rates and Quantities:			Temperatures:	
Air to Top Distributor	SCF/T	3810	Product Oil	OF 139
Air to Mid Distributor	SCF/T	850	Retorted Shale	OF 384
Total Air	SCF/T	4660	Raw Shale	OF 36
Recycle to Top Distri.	SCF/T	1360	Off Gas	OF 145
Recycle to Mid Distri.	SCF/T	1320	Distributor Cooling Water ΔT	OF 18
Recycle to Btm Distri.	SCF/T	12110	Top Distributor Inlet	OF 197
Total Recycle Gas	SCF/T	14790	Mid Distributor Inlet	OF 212
Raw Shale Rate	TPH	11.2	Btm Distributor Inlet	OF 241
Throughput	lb/hr/ft	454		
Distributor Cooling Water	GPM	80		
Miscellaneous:			Yields:	
Retort press. drop in H ₂ O/ft		1.0	Oil Collected Gal/T	24.8
Carbonate Decomposition wt%		27	Oil Collected Wt% FA	92
Retort Bed Height Ft. In.		25'6"	Product Gas SCF/T	7200
			Retorted Shale TPH	9.0
			Retorted Shale wt%RS	81
			Liquid Water lbs/T	9.7

TABLE 3-3

PARANO DIRECT MINE OPERATING CONDITIONS
AVERAGE DATA FROM SEMI-WORKS RUN SW-30 TEST A
EXCEPT A-6 AND A-7

Rates and Quantities:		Temperatures:	
Air to Top Distributor	SCF/T 3870	Product Oil	OP 132
Air to Mid Distributor	SCF/T 820	Retrofired Shale	OP 384
Total Air	SCF/T 4690	Raw Shale	OP 36
Recycle to Top Distrib.	SCF/T 1380	Oil Gas	OP 142
Recycle to Mid Distrib.	SCF/T 1120	Distributor Cooling	18
Recycle to Bm Distrib.	SCF/T 1210	Water ΔT	OP
Total Recycle Gas	SCF/T 1470	Top Distributor	OP 197
Raw Shale Rate	TPH 11.2	Inlet	OP
Throughput	lb/hr/ft 424	Mid Distributor	OP 212
Distributor Cooling Water GPM	80	Bm Distributor	OP 241
Miscellaneous:		Yields:	
Water press. drop in Hg/ft	1.0	Oil Collected Gal/T	24.8
Carbonate Decomposition wt%	57	Oil Collected Wt FA	92
Water Bed Height Ft. In.	22'6"	Product Gas SCF/T	7200
		Retrofired Shale TPH	9.0
		Retrofired Shale WtRS	81
		Liquid Water lb/T	2.7

TABLE 3-10

PARAHO DIRECT HEATED MODE PRODUCT PROPERTIES

AVERAGE DATA FROM SEMI-WORKS RUN SW-20

TEST A EXCEPT A-6 AND A-7 (303 Hrs)

<u>Shale Properties</u>		<u>Raw Shale</u>	<u>Retorted Shale</u>
Moisture Content	Wt%	0.96	0.0
Fischer Assay	Gal/T	27.2	0.28
F.A..... Oil	Wt%	10.39	0.10
F.A....Water	Wt%	1.66	0.16
F.A...Gas + Loss	Wt%	2.29	0.29
Mineral CO ₂	Wt%	17.71	15.86
Ignition Loss	Wt%	33.07	17.72
Organic Carbon	Wt%	N.A.	1.97
Carbon	Wt%	17.05	6.30
Hydrogen	Wt%	1.84	0.17
Nitrogen	Wt%	0.51	0.21

TABLE 3-10

PARAMO DIRECT HEATED MOLE PRODUCT PROPERTIES

AVERAGE DATA FROM SEMI-MOLES RUN SW-20

TEST A EXCEPT A-6 AND A-7 (303 Hrs)

Shale Properties	Raw Shale	Recycled Shale
Moisture Content Wt%	0.96	0.0
Flasher Assay Gal/T	27.1	0.28
F.A....Oil Wt%	10.30	0.10
F.A....Water Wt%	1.60	0.16
F.A....Gas + Losses Wt%	3.22	0.20
Mineral CO ₂ Wt%	17.71	13.80
Ignition loss Wt%	33.05	17.73
Organic Carbon Wt%	N.A.	1.97
Carbon Wt%	17.02	6.20
Hydrogen Wt%	1.64	0.17
Nitrogen Wt%	0.21	0.21

and does not reflect the naphtha fractions contained in the gas stream at operating temperatures. By adding the C5+ fractions from the product gas as shown by the Paraho Laboratory in the gas analysis, the liquid yield could increase to 96 wt% F.A.

Product gas production for this series of tests measured 7200 SCF/T (wet basis). The heating value on this gas was 118 BTU/SCF on a dry basis. By removing the C5+ fraction from the gas stream, its heating value would be reduced from 118 BTU/SCF (dry) to 91 BTU/SCF (dry). These C5+ fractions comprise only 25 SCF/T, so the total gas quantity is not appreciably changed.

The C5+ fraction is shown in the gas analysis on Table 3-11. This represents an average of the light and heavy naphtha fractions shown by the Paraho Laboratory. This same value was used for all Direct Heated Mode test data presented in the Appendix. The evolution of these gas analyses techniques continued through the entire retorting program.

The calculation of the C5+ fraction is based on the average quantity of light and heavy naphtha fraction shown by the laboratory analysis for Semi-Works Run SW-20 and Pilot Plant Run PP-18. The naphtha fractions for both the Semi-Works and Pilot Plant operations are equal. The heavy naphtha fraction is obtained using a water cooled condenser at approximately 70 °F which does not remove measureable quantities of hydrocarbons below the C5+ fractions. The light naphthas are

and does not reflect the naphtha fractions contained in the gas stream at operating temperatures. By adding the C₂+ fractions from the product gas as shown by the Paraho Laboratory in the gas analysis, the liquid yield could increase to 95 wt%

F.A.

Product gas production for this series of tests measured 7300 SCF/T (wet basis). The heating value on this gas was 118 BTU/SCF on a dry basis. By removing the C₂+ fraction from the gas stream, its heating value would be reduced from 118 BTU/SCF (dry) to 91 BTU/SCF (dry). These C₂+ fractions comprise only 35 SCF/T, so the total gas quantity is not appreciably changed.

The C₂+ fraction is shown in the gas analysis on Table 3-11. This represents an average of the light and heavy naphtha fractions shown by the Paraho Laboratory. This same value was used for all Direct Heated Mode test data presented in the Appendix. The evolution of these gas analyses techniques continued through the entire retorting program.

The calculation of the C₂+ fraction is based on the average quantity of light and heavy naphtha fraction shown by the laboratory analysis for Semi-Works Run SW-20 and Pilot Plant Run PP-18. The naphtha fractions for both the Semi-Works and Pilot Plant operations are equal. The heavy naphtha fraction is obtained using a water cooled condenser at approximately 70° F which does not remove measurable quantities of hydrocarbons below the C₂+ fractions. The light naphthas are

obtained in a dry ice-acetone condenser which does remove some fractions, which are also analyzed by the Laboratory Gas Chromatograph (G.C.). A composite value of these naphtha fractions shown as C5+ was calculated by reducing the measured light naphtha fraction by 17% average C3's and 40% of the C4's and all of the C5's shown by the G.C. analysis of the gas. The para TEST A EXCEPT A-6 AND A-7 (303 HOURS)

TABLE 3-11
PARAHO DIRECT HEATED MODE PRODUCT PROPERTIES
AVERAGE DATA FROM SEMI-WORKS SW-20

Product Oil Properties:			Product Gas Properties (Dry)		
Gravity	°API	21.4	Gross Heat Value BTU/SCF		118
Viscosity SUS @ 130°F		89.9	Specific Gravity		1.10
Viscosity SUS @ 210°F		46.5	Analysis: H ₂ Vol%		2.50
Ramsbottom Carbon wt%		1.73	N ₂ Vol%		65.45
Water Content	Vol%	4.46	O ₂ Vol%		0.01
Solids, BS	wt%	0.47	CO Vol%		2.51
Carbon	wt%	84.62	CH ₄ Vol%		2.19
Hydrogen	wt%	11.50	CO ₂ Vol%		24.14
Nitrogen	wt%	2.00	C ₂ H ₄ Vol%		0.67
			C ₂ H ₆ Vol%		0.62
			C3's Vol%		0.71
			C4's Vol%		0.36
			C5's+Vol%		0.41
			H ₂ S Vol%		0.22
			NH ₃ Vol%		0.21
			Moisture	Vol%	17.56

Oil properties were uniform for Semi-Works Run SW-20. However, minor variations in viscosity, Ramsbottom Carbon, and gravity (°API) have occurred with changes in retort operating conditions during other Semi-Works and Pilot Plant runs. Moisture and sediment contents vary with the raw shale moisture and fines content, retort configuration, insulation of off-gas piping, and ambient conditions.

TABLE 3-11
PARANO DIRECT HEATER NOSE PRODUCT PROPERTIES
AVERAGE DATA FROM SEMI-WORKS SW-20
TEST A EXCEPT A-6 AND A-7 (303 HOURS)

Product Oil Properties:		Product Gas Properties (Dry)	
Gravity	°API	Gross Heat Value BTU/SCF	118
Viscosity SUS @ 130°F	89.8	Specific Gravity	1.10
Viscosity SUS @ 210°F	46.5	Analysis: H ₂ Vol%	3.20
Residual Carbon wt%	1.75	H ₂ Vol%	65.45
Water Content Vol%	4.46	O ₂ Vol%	0.01
Solids, wt%	0.47	CO Vol%	3.21
Carbon wt%	84.63	CH ₄ Vol%	3.19
Hydrogen wt%	11.50	CO ₂ Vol%	24.14
Nitrogen wt%	2.00	C ₂ H ₆ Vol%	0.67
		C ₂ H ₄ Vol%	0.63
		C ₃ H ₈ Vol%	0.71
		C ₄ H ₁₀ Vol%	0.36
		C ₅ H ₁₂ Vol%	0.41
		H ₂ Vol%	0.35
		N ₂ Vol%	0.31
		Moisture Vol%	17.56

obtained in a dry ice-acetone condenser which does remove some fractions, which are also analyzed by the Laboratory Gas Chromatograph (G.C.). A composite value of these naphtha fractions shown as C5+ was calculated by reducing the measured light naphtha fraction by 17% of the average C3's and 40% of the C4's and all of the C5's shown by the G.C. analysis of the gas. The percentage of light naphtha reduction for the C3's and C4's shown by G.C. analyses was calculated from special analysis of the gas before and after entry to the sub-ambient dry ice-acetone condenser. The adjusted light naphtha value was then ratioed to the heavy naphtha fraction by their respective molecular weights and the combined fraction shown as a C5+ content of the product gas.

Most feed and product properties given in the composite of test data from Semi-Works Run SW-20 are typical of the Direct Heated Mode operations on either retort. Raw shale properties change very little when good blending of mine run shale is maintained. During this run, the raw shale Fischer Assay analysis showed a standard deviation of only 0.27 Gal/Ton.

Oil properties were uniform for Semi-Works Run SW-20. However, minor variations in viscosity, Ramsbottom Carbon, and gravity (°API) have occurred with changes in retort operating conditions during other Semi-Works and Pilot Plant runs. Moisture and sediment contents vary with the raw shale moisture and fines content, retort configuration, insulation of off-gas piping, and ambient conditions.

obtained in a dry ice-acetone condenser which does remove some fractions, which are also analyzed by the Laboratory Gas Chromatograph (G.C.). A composite value of these naphtha fractions shown as C2+ was calculated by reducing the measured light naphtha fraction by 1% of the average C3's and 40% of the C4's and all of the C5's shown by the G.C. analysis of the gas. The percentage of light naphtha reduction for the C3's and C4's shown by G.C. analyses was calculated from special analysis of the gas before and after entry to the sub-ambient dry ice-acetone condenser. The adjusted light naphtha value was then ratioed to the heavy naphtha fraction by their respective molecular weights and the combined fraction shown as a C2+ content of the product gas.

Most feed and product properties given in the composite of test data from Semi-Works Run SW-20 are typical of the Direct Heated Mode operations on either reform. Raw shale properties change very little when good blending of mine run shale is maintained. During this run, the raw shale Fischer Assay analysis showed a standard deviation of only 0.27 Cal/Ton.

Oil properties were uniform for Semi-Works Run SW-20. However, minor variations in viscosity, Ramapbottom Carbon, and gravity (CPI) have occurred with changes in reform operating conditions during other Semi-Works and Pilot Plant runs. Moisture and sediment contents vary with the raw shale moisture and fines content, reform configuration, insulation of off-gas piping, and ambient conditions.

Gas properties are affected by a change in operating conditions. The increase in carbonate decomposition when a higher SCF/T of air is used, increases the CO₂ and N₂ content, Appendix D-3, Run SW-20, Tests A-5 and B. This results in a dilution of the remainder of the gas. Moisture content of the gas will vary with available moisture from the raw shale and the quantity of product gas being produced. Except for cool sections of the recycle gas system, condensation of moisture should not occur.

3.7 SPECIAL DATA

Special data is defined as that data obtained from non-routine tests run on normal samples (recycle gas, crude oil, and raw and retorted shale). These data are usually not used in material balances and many have not been included in the individual run reports. Special data obtained by the Paraho Laboratory during Direct Heated Mode Operations are summarized in Table 3-12.

During Semi-Works Run SW-20, a special test was made for recycle gas analysis. Representatives from the Atlantic Richfield Company obtained two gas samples using a sub-ambient cold trap technique for complete analysis of all components. The results of their test, Table 3-13, show a higher total hydrocarbon content and a higher heating value of the gas than obtained in the Paraho Laboratory. The gross heating value of the dry product gas based on this analysis would be 162 BTU/SCF as compared to the 118 BTU/SCF previously shown by the Paraho Laboratory Data. If calculated on a C5+

Gas properties are affected by a change in operating conditions. The increase in carbonate decomposition when a higher SCV of air is used, increases the CO₂ and N₂ content, Appendix B-3, Run SW-30, Tests A-5 and B. This results in a dilution of the remainder of the gas. Moisture content of the gas will vary with available moisture from the raw shale and the quantity of product gas being produced. Except for cool sections of the recycle gas system, condensation of moisture should not occur.

3.7 SPECIAL DATA

Special data is defined as that data obtained from non-routine tests run on normal samples (recycle gas, crude oil, and raw and retorted shale). These data are usually not used in material balances and many have not been included in the individual run reports. Special data obtained by the Paraho Laboratory during Direct Heated Mode Operations are summarized in Table 3-12.

During Semi-Wet Run SW-30, a special test was made for recycle gas analysis. Representatives from the Atlantic Richfield Company obtained two gas samples using a sub-ambient cold trap technique for complete analysis of all components. The results of their test, Table 3-12, show a higher total hydrocarbon content and a higher heating value of the gas than obtained in the Paraho Laboratory. The gross heating value of the dry product gas based on this analysis would be 155 BTU/SCF as compared to the 118 BTU/SCF previously shown by the Paraho Laboratory Data. If calculated on a C₂+

TABLE 3-12

SPECIAL DATA - SEMI-WORKS
DIRECT HEATED MODE OPERATIONS

Sample	SEMI-WORKS	PILOT PLANT
Recycle Gas		
H ₂ S, Vol%	(18)0.22 ± 0.03	(7)0.27 ± 0.07
NH ₃ , Vol%	(5)0.20 ± 0.08	(3)0.26 ± 0.15
Raw Shale		
Total S, Wt%	(11)0.63 ± 0.11	(2)0.76 ± 0.03
Retorted Shale		
Total S, Wt%	(11)0.90 ± 0.07	(5)0.80 ± 0.12
Oil		
Total S, Wt%	(14)0.59 ± 0.05	(5) 0.60 ± 0.05
Viscosity, SUS, 100 ⁰ F	(18)245 ± 56	----
Mist		
Off-gas		
Lb/MSCF	(4) 5.9	(1) 6.6
Dmmd, /μ	2.8	3.0
cg	1.6	1.9
Coalescer		
Lb/MSCF	(3) 3.2	
Dmmd	~2	
ESP		
Lb/MSCF	(4) 0.005	
Blower Discharge		
Lb/MSCF	(2) 0.000	

NOTE: Data are presented as follows: number of tests
(in parantheses) followed by mean value plus
or minus one standard deviation.

TABLE 3-12

STEEL DATA - SEMI-WORKS
DIRECT HEATING MODE OPERATING

Sample	SEMI-WORKS	PILT PLANT
Recycle Gas		
H ₂ , Vol%	(18) 0.32 ± 0.03	(7) 0.32 ± 0.03
HR ₂ , Vol%	(2) 0.30 ± 0.08	(2) 0.30 ± 0.12
Raw Shale		
Total S, Wt%	(11) 0.63 ± 0.11	(3) 0.70 ± 0.03
Retorted Shale		
Total S, Wt%	(11) 0.90 ± 0.03	(4) 0.80 ± 0.13
Oil		
Total S, Wt%	(14) 0.50 ± 0.02	(2) 0.60 ± 0.02
Viscosity, SUS, 100°F	(18) 242 ± 26	---
Blair		
Oil-gas		
lb/HSCF	(4) 2.8	(1) 2.6
lb/HSCF	2.8	3.0
lb	1.6	1.8
Compressor		
lb/HSCF	(3) 3.2	
lb	3	
ESP		
lb/HSCF	(4) 0.002	
Blower Discharge		
lb/HSCF	(2) 0.000	

NOTE: Data are presented as follows: number of tests
(in parentheses) followed by mean value plus
or minus one standard deviation.

TABLE 3-13

DIRECT MODE PRODUCT GAS ANALYSIS

ANALYSIS BY ATLANTIC RICHFIELD CO. - SEMI-WORKS RUN SW-20

Analysis	Dry Vol%
H ₂	4.36
O ₂ + Ar	0.92
N ₂	64.15
CH ₄	2.30
CO	1.98
CO ₂	21.75
C ₂ H ₄	0.92
C ₂ H ₆	0.94
C ₃ H ₆	0.45
C ₃ H ₈	0.47
C ₄ 's	0.40
C ₅ 's	0.16
C ₆ 's+	0.77
H ₂ S	0.22
NH ₃	0.21
Moisture Content	17.56
Heating Value (Dry) BTU/SCF	162

TABLE 3-13

DIRECT MOIST PRODUCT GAS ANALYSIS

ANALYSIS BY ATLANTIC RICHFIELD CO. - SEMI-WORKS RUN SW-20

Analysis	Dry Vol%
H ₂	4.35
O ₂ + Ar	0.93
N ₂	64.15
CO ₂	2.30
CO	1.88
CO ₂	21.75
C ₂ H ₄	0.93
C ₂ H ₆	0.94
C ₂ H ₂	0.45
C ₂ H ₄	0.47
C ₂ H ₆	0.40
C ₂ H ₂	0.16
C ₂ H ₄	0.77
H ₂	0.33
H ₂	0.31
Moisture Content	17.56
Heating Value (Dry) BTU/SCF	163

basis, it's effect on the potential liquid yield would show a calculated 100 Wt% F.A. recovery.

Contaminants of recycle gas (hydrogen sulfide and ammonia) are listed for both Semi-Works and Pilot Plant. Although the means for ammonia and hydrogen sulfide concentrations are about equal with no significant differences between the Semi-Works and Pilot Plant, the deviations of the individual means are fairly large. This indicates that better data could be obtained by continuous monitoring.

Total sulfur was determined on raw and retorted shale and oil samples retained from five Direct Heated Mode runs. Although no rigorous sulfur balances were made with these data, an approximate overall sulfur balance (including the hydrogen sulfide in the recycle gas) ranges from about 100 to 120%.

Viscosities of Direct Heated Mode crude shale oil were measured at 100°F, primarily for comparison with the Indirect Heated Mode shale oil. The mean Saybolt viscosity at this temperature (245 SUS) is much higher than at 130°F. Significant curvature occurs in the viscosity temperature relationships between temperatures from 100°F to 210°F. This indicates non-Newtonian behavior in this temperature range, probably because the cloud-point has been reached (wax crystallization) at the 100°F.

Mist determinations on Table 3-12 show that there is not significant difference in the loading (#/MSCF), mean

basis, it's effect on the potential lipid yield would show a calculated 100 Wt % A. recovery.

Concentrations of recycle gas (hydrogen sulfide and

ammonia) are listed for both Semi-Works and Pilot Plant.

Although the means for ammonia and hydrogen sulfide concentrations

are about equal with no significant differences between the

Semi-Works and Pilot Plant, the deviations of the individual

means are fairly large. This indicates that better data

could be obtained by continuous monitoring.

Total sulfur was determined on raw and reformed

shale and oil samples retained from five Direct Heated Mode

runs. Although no rigorous sulfur balances were made with

these data, an approximate overall sulfur balance (including

the hydrogen sulfide in the recycle gas) ranges from about 100

to 120%.

Viscosities of Direct Heated Mode crude shale oil

were measured at 100°F, primarily for comparison with the

Indirect Heated Mode shale oil. The mean Saybolt viscosity

at this temperature (345 SUS) is much higher than at 150°F.

Significant curvature occurs in the viscosity-temperature

relationship between temperatures from 100°F to 210°F. This

indicates non-Newtonian behavior in this temperature range,

probably because the cloud-point has been reached (was

crystallized) at the 100°F.

Most determinations on Table 1-12 show that there

is not significant difference in the loading (%MSE), mean

particle size (D_{mmd}), or geometric deviation (G) between Semi-Works and Pilot Plants. Mist determinations require isokinetic sampling with minimum flow disturbance lines, therefore, the mist data obtained at the site may not be valid as the flow at the off-gas collector is turbulent. These data show that the Paraho oil separation equipment is effective.

52% COTTON FIBER
ECONOMY
MELON BOND

4. INDIRECT
MODE

4 INDIRECT HEATED MODE OPERATION

4.1 INTRODUCTION

It has been recognized that the dilution of pyrolysis gas with the products of combustion could be avoided if retort heat requirements were supplied as sensible heat in a recycle gas stream. Gas heating equipment was added to the Pilot Plant and the Semi-Works Retort designs to obtain data using this Indirect Heating. The flow sheet of the Paraho Indirect Heated Mode is illustrated in Appendix Section F (Drawing 3).

4.2 INDIRECT HEATED MODE PROCESS DESCRIPTION

The shale movement and its control through the retort for the Indirect Heated Mode process are the same as for the Direct Heated Mode process previously explained. Gas removal from the bed and the product oil recovery equipment also remain the same.

The primary differences between the Direct and Indirect Heated Modes of operation involve the heating of recycle gas, and those items associated with the high heating value product gas. The quantity of product gas is approximately 1/10th that of the Direct Mode.

A special startup procedure was developed for Indirect Heated Mode operations and is presented in Section 6.2. An inert gas (Pilot Plant Direct Heated Mode gas) is circulated through the external heater and retort

4.1 INTRODUCTION

It has been recognized that the dilution of pyrolysis gas with the products of combustion could be avoided if reform heat requirements were supplied as sensible heat in a recycle gas stream. Gas heating equipment was added to the Pilot Plant and the Semi-Works Reform design to obtain data using this Indirect Heating. The flow sheet of the Paraho Indirect Heated Mode is illustrated in Appendix Section F (Drawing 3).

4.1 INDIRECT HEATED MODE PROCESS DESCRIPTION

The shale movement and its control through the reform for the Indirect Heated Mode process are the same as for the Direct Heated Mode process previously explained. Gas removal from the bed and the product oil recovery equipment also remain the same.

The primary differences between the Direct and Indirect Heated Modes of operation involve the heating of recycle gas, and those items associated with the high heating value product gas. The quantity of product gas is approximately 1/10th that of the Direct Mode.

A special startup procedure was developed for Indirect Heated Mode operations and is presented in Section 4.2. An inert gas (Pilot Plant Direct Heated Mode gas) is circulated through the external heater and reform

until a suitable heat inventory and temperature profile is established in a moving bed of non-kerogen bearing rock. Then the rock feed is replaced with oil shale and the specified processing conditions are established.

Similar to the Direct Heated Mode, the recycle gas blower compresses the clean gas from the electrostatic precipitator and recycles approximately half to the bottom of the retort and the other half through the external hot gas heaters. Approximately 3% of the gas handled is the product gas which for this program was burned in the thermal oxidizer. Hot gas piping and distributor systems must use alloy steels or other suitable high temperature resistant materials for this operation.

The external heaters that could be timely obtained were not designed for the particular operation and they were proved not to be suitable for heating this high sulfur containing recycle gas. A description of the heaters and associated problems is given in Physical Description, Sec. 5.3.2.

4.3 PILOT PLANT INDIRECT MODE OPERATION

The Pilot Plant preliminary operations in the Indirect Heated Mode defined the characteristics of the gas and the temperatures needed to minimize gas cracking. Due to heater limitations only operator training and process familiarization runs were conducted in the Pilot Plant. The Pilot Plant Operating Summary, Section A of the Appendix, identifies those runs.

until a suitable heat inventory and temperature profile is established in a moving bed of non-kerosen bearing rock. Then the rock feed is replaced with oil shale and the specified processing conditions are established.

Similar to the Direct Heated Mode, the recycle gas

blower compresses the clean gas from the electrostatic precipitator and recycles approximately half to the bottom of the reactor and the other half through the external hot gas heaters. Approximately 1% of the gas handled is the product gas which for this program was burned in the thermal oxidizer. Hot gas piping and distributor systems must use alloy steels or other suitable high temperature resistant materials for this operation.

The external heaters that could be timely obtained

were not designed for the particular operation and they were proved not to be suitable for heating this high sulfur containing recycle gas. A description of the heaters and associated problems is given in Physical Description, Sec. 2.3.1.

4.3 PILOT PLANT INDIRECT MODE OPERATION

The Pilot Plant preliminary operations in the Indirect Heated Mode defined the characteristics of the gas and the temperatures needed to minimize gas cracking. Due to heater limitations only operator training and process familiarization runs were conducted in the Pilot Plant. The Pilot Plant Operating Summary, Section A of the Appendix, identifies these runs.

The external heaters were made of concentric pipes with the flow of process gas in the annulus. Fins in the annulus were made of Inconel and deteriorated rapidly in the hot gas containing about 3% hydrogen sulfide. Rather than redesigning and refabricating the Pilot Plant external heaters, operations proceeded to the Semi-Works Plant where preliminary heater operations were satisfactory.

4.4 SEMI-WORKS INDIRECT MODE OPERATIONS

The Semi-Works Operating Summary in the Appendix Section B, identifies the Indirect Heated runs. Operability of the Indirect Heated Mode was demonstrated during Semi-Works Run SW-23 with a 31 day operation having a 96.6% on-stream factor. A total of 29 outages were recorded on the heaters accounting for 82% of the time lost. Most of these required less than a 15 minute duration to perform heater re-ignition procedures. In most cases, gas circulation was continued. An additional 18% of the lost time was attributed to two scheduled outages, one for the installation of the bottom recycle gas cooler and another for a raw shale weighbelt check.

The difficulties with the external gas heaters during Semi-Works Run SW-23 were primarily related to the fuel oil burner system and its controls. These problems were corrected, greatly reducing the short-term outages on the heaters.

The external heaters were made of concentric pipes with the flow of process gas in the annulus. Fins in the annulus were made of Inconel and deteriorated rapidly in the hot gas containing about 35 hydrogen sulfide. Rather than redesigning and refabricating the Pilot Plant external heaters, operations proceeded to the Semi-Works Plant where preliminary heater operations were satisfactory.

4.4 SEMI-WORKS INDIRECT MODE OPERATIONS

The Semi-Works Operating Summary in the Appendix Section B, identifies the Indirect Heated runs. Operability of the Indirect Heated Mode was demonstrated during Semi-Works Run SW-13 with a 31 day operation having a 96.6% on-stream factor. A total of 32 outages were recorded on the heaters accounting for 8% of the time lost. Most of these required less than a 15 minute duration to perform heater re-ignition procedures. In most cases, gas circulation was continued. An additional 18% of the lost time was attributed to two scheduled outages, one for the installation of the bottom recycle gas cooler and another for a raw shale weight check.

The difficulties with the external gas heaters during Semi-Works Run SW-13 were primarily related to the fuel oil burner system and its controls. These problems were corrected, greatly reducing the short-term outages on the heaters.

Metal deterioration problems in the heaters gradually increased throughout the Indirect Heated Mode program. Heater problems indirectly produced process upsets, which in turn limited the operational time on the retort.

The general design problems and limitations of the external heaters are discussed in the Section 5.3.2. The design requirements of gas heaters are well-known and for this reason are not expected to present a serious problem for future installations.

Two unusual operating conditions were noted in the Indirect Heated Mode; a tendency to form a partial blockage of shale flow through the bed and a tendency towards high off-gas temperatures. The latter was not a serious operational problem since the temperature within the collecting system was controlled by the coalescer system.

The problems of partial bed blockage are attributed to the larger diameter distributors required for the Indirect Heated Mode and numerous upsets in process conditions because of heater failure. It was necessary to change the top distributors in the Semi-Works retort back to the original 10-inch pipe size because they were the only distributors available that were suitable for the high temperature service. This increased the bed restriction between the straight side walls and the distributor and increased the gas and shale velocities. This restriction increased the chances of partial blockage to solids flow in this

Metal deterioration problems in the heaters gradually increased throughout the Indirect Heated Mode program. Heater problems indirectly produced process upsets, which in turn limited the operational time on the reactor.

The general design problems and limitations of the external heaters are discussed in the Section 5.3.3. The design requirements of gas heaters are well-known and for this reason are not expected to present a serious problem for future installations.

Two unusual operating conditions were noted in the Indirect Heated Mode: a tendency to form a partial blockage of shale flow through the bed and a tendency towards high off-gas temperatures. The latter was not a serious operational problem since the temperature within the collecting system was controlled by the condenser system.

The problems of partial bed blockage are attributed to the larger diameter distributors required for the Indirect Heated Mode and numerous upsets in process conditions because of heater failure. It was necessary to change the top distributor in the Semi-Works reactor back to the original 10-inch pipe size because they were the only distributors available that were suitable for the high temperature service. This increased the bed restriction between the straight side walls and the distributor and increased the gas and shale velocities. This restriction increased the chances of partial blockage to solids flow in this

section of the retort. Generally, partial blockage did not result in a run termination. One effect of a blockage noted was an imbalance between the temperatures of the off-gas ports. Another was the increase in combined off-gas temperature resulting from a decreased bed volume for solids-gas contact.

Operational control for the Indirect Heated Mode differs in many respects from that used for the Direct Heated Mode. Major differences are:

1. Internal temperature changes and their response to process adjustments are much slower in the Indirect Heated Mode because rapid changes in heat inventory are more difficult to make.
2. The position of the hot gas entry is fixed within the bed. In the Direct Heated Mode, however, heat release will move with variations of the combustion zone.
3. Control and operation of the external heater has been added to the plant complexity.
4. Control of temperature of the recycle gas stream is necessary for collection efficiency in the oil collection system and moisture control.
5. Hydrocarbon cracking within the heater is a function of the moisture content of the gas and the temperature of the metal exposed to the gas, and residence time.

Control of the internal process relies primarily on bed temperature measurements and gas analysis. These values

section of the report. Generally, partial blockage did not result in a run termination. One effect of a blockage noted was an imbalance between the temperatures of the off-gas ports. Another was the increase in combined off-gas temperature resulting from a decreased bed volume for solids-gas contact.

Operational control for the Indirect Heated Mode

differs in many respects from that used for the Direct Heated Mode. Major differences are:

1. Internal temperature changes and their response to process adjustments are much slower in the Indirect Heated Mode because rapid changes in heat inventory are more difficult to make.
2. The position of the hot gas entry is fixed within the bed. In the Direct Heated Mode, however, heat release will move with variations of the combustion zone.
3. Control and operation of the external heater has been added to the plant complexity.
4. Control of temperature of the recycle gas stream is necessary for collection efficiency in the oil collection system and moisture control.
5. Hydrocarbon cracking within the heater is a function of the moisture content of the gas and the temperature of the metal exposed to the gas, and residence time.

Control of the internal process relies primarily on bed temperature measurements and gas analysis. These values

must be used as a guide to adjust prescribed operating conditions of hot gas rate and temperatures.

Control of the external heaters was achieved through an analog instrument system controlling heater outlet temperature; by regulation of the fuel to the heater burner. This system was used with a minimum of difficulty during this program.

The volume of product gas made is less in the Indirect Heated Mode. This affects the moisture control of the recycle gas. Moisture content above 50% would result unless water was condensed somewhere within the recycle gas system. With a product gas quantity of approximately 700 SCF/T, or 1/10 that of the Direct Mode, excessively high moisture contents would be required to remove the water as a vapor in the product gas stream.

A special moisture control method was devised for this mode of operation involving a gas cooler and water condenser in the bottom gas recycle stream. By controlling the gas temperature, any desired moisture level could be obtained in that stream. The moisture content in the recycle gas stream could be controlled as desired and was relatively uniform throughout the gas system.

Complete temperature control in the recovery system was also accomplished through coolers on the recirculating oil system for the coalescer. As a result, a highly efficient and stabilized operation of the oil-gas recovery

must be used as a guide to adjust prescribed operating conditions of hot gas rate and temperature.

Control of the external heaters was achieved through an analog instrument system controlling heater outlet temperature by regulation of the fuel to the heater burner. This system was used with a minimum of difficulty during this program.

The volume of product gas made is less in the Indirect Heated Mode. This affects the moisture control of the recycle gas. Moisture content above 50% would result unless water was condensed somewhere within the recycle gas system. With a product gas quantity of approximately 700 SCF/T, or 1/10 that of the Direct Mode, excessively high moisture contents would be required to remove the water as a vapor in the product gas stream.

A special moisture control method was devised for this mode of operation involving a gas cooler and water condenser in the bottom gas recycle stream. By controlling the gas temperature, any desired moisture level could be obtained in that stream. The moisture content in the recycle gas stream could be controlled as desired and was relatively uniform throughout the gas system.

Complete temperature control in the recovery system was also accomplished through coolers on the recirculating oil system for the condenser. As a result, a highly efficient and stabilized operation of the oil-gas recovery

equipment was attained. As in the Direct Heated Mode, a properly insulated system should reduce the water in the product oil to a negligible quantity.

The control of these gas and oil cooling systems was achieved with a simple instrument regulating the flow of cooling water through the heat exchangers. The closed circuit cooling water system was employed as the cooling medium.

The upper temperature limit for hot gas entry was limited by the degree of cracking occurring in the recycle gas stream. It was desirable to maintain a maximum temperature to reduce the quantity of gas required for heat transfer while limiting the degree of cracking. Hydrocarbon cracking must be limited to prevent carbon deposition within the system and to prevent heat loss from its endothermic reactions.

4.5 SEMI-WORKS OPERATING CONDITIONS

While demonstrating the operability of the Indirect Heated Mode, variable studies were also made. A total of 16 test periods were obtained during Run SW-23 under several different operating conditions. The results of these variable studies were used to establish the operating conditions designed to improve retort thermal efficiency for later runs.

The heat input from hot gas affects the product properties and yields in the Indirect Heated Mode in the same manner as heat input in the Direct Heated Mode. When

equipment was attained. As in the Direct Heated Mode, a properly insulated system should reduce the water in the product oil to a negligible quantity.

The control of these gas and oil cooling systems was achieved with a single instrument regulating the flow of cooling water through the heat exchangers. The closed circuit cooling water system was employed as the cooling medium.

The upper temperature limit for hot gas entry was limited by the degree of cracking occurring in the recycle gas stream. It was desirable to maintain a maximum temperature to reduce the quantity of gas required for heat transfer while limiting the degree of cracking. Hydrocarbon cracking must be limited to prevent carbon deposition within the system and to prevent heat loss from its endothermic reactions.

4.5. SEMI-WORKS OPERATING CONDITIONS

While demonstrating the operability of the Indirect Heated Mode, variable studies were also made. A total of 16 test periods were obtained during Run 2W-23 under several different operating conditions. The results of these variable studies were used to establish the operating conditions designed to improve reactor thermal efficiency for later runs.

The heat input from hot gas affects the product properties and yields in the Indirect Heated Mode in the same manner as heat input in the Direct Heated Mode. When

the heat input is low, the volume of product gas is low, but its unit heating value is higher. At lower heat input, a more fluid oil is produced. Test periods A-4.1 and A-4.2 of Semi-Works Run SW-28 are shown individually on Table 4-1 to illustrate data reproducibility in the Indirect Heated Mode.

With the exception of the external gas heaters, the reliability of all equipment had been previously demonstrated in the Direct Heated Mode operations and was again confirmed in the Indirect Heated Mode operations.

Six operating conditions have been selected from the Semi-Works Indirect Heated Mode to highlight the variations in thermal efficiency and operations demonstrated. The more significant operating conditions are shown in Table 4-1 with the corresponding product properties shown on Table 4-2. Each of the six conditions shown produced a retorted shale having less than 1 gal/ton residual oil by Fischer Assay.

the heat input is low, the volume of product gas is low, but its unit heating value is higher. At lower heat input, a more fluid oil is produced. Test periods A-4.1 and A-4.2 of Semi-Works Run SW-28 are shown individually on Table 4-1 to illustrate data reproducibility in the Indirect Heated Mode.

With the exception of the external gas heaters, the reliability of all equipment had been previously demonstrated in the Direct Heated Mode operations and was again confirmed in the Indirect Heated Mode operations.

Six operating conditions have been selected from the Semi-Works Indirect Heated Mode to highlight the variations in thermal efficiency and operations demonstrated. The more significant operating conditions are shown in Table 4-1 with the corresponding product properties shown on Table 4-2. Each of the six conditions shown produced a retorted shale having less than 1 gal/lon residual oil by Fischer Assay.

TABLE 4-1

SEMI-WORKS - INDIRECT HEATED MODE OPERATING CONDITIONS AND YIELDS

Run No.	Test No.	Combined Test Length, Hr.	OPERATING CONDITIONS					PRODUCT YIELD	
			Mass Rate Lbs/Hr/Ft ²	Hot Gas Input** MBTU/T	Top Dist. Gas SCF/T	Top Dist. Inlet T, °F	Bottom Gas, SCF/T	Oil, C5 plus Wt. % F.A.	Gas(wet) C4 minus SCF/T
SW-23	A-1 thru A-7	152	331	584	18,500	1146	5160	90	1,480
SW-23	C-2.1, -2.2 -2.3	47	504	447	12,370	1176	8460	91	935
SW-23	C-5	16	529	442	11,750	1206	8430	88	1,175
SW-28	C-1, C-2	46	446	440	11,840	1197	7860	90	980
SW-28	A-4.1	12	401	415	11,060	1298	12,570	95	570*
SW-28	A-4.2	24	421	393	10,270	1299	11,650	94	520*

* Gas production may be low because of unmeasured gas leakage through the heater.

** Hot gas heat input at the top distributor inlet temperature, above the 77°F datum.

TABLE 4-2

SEMI-WORKS RETORT - INDIRECT HEATED MODE PRODUCT PROPERTIES

Run No.	Test No.	Combined Test Length, Hrs.	Hot Gas Input MBTU/T	PRODUCT OIL PROPERTIES			PRODUCT GAS PROPERTIES (DRY)		
				Gravity °API	Visc. SUS @ 130°F	Ramsbottom Carbon, Wt%	H ₂ Vol%	CO ₂ Vol%	Gross Heating Value BTU/SCF
SW-23	A-1 thru A-7	152	584	20.2	108	2.10	26.5	29.2	636
SW-23	C-2.1, -2.2, -2.3	47	447	20.3	90	1.68	26.2	17.2	870
SW-23	C-5	16	442	20.5	90	1.34	25.6	17.1	870
SW-28	C-1, C-2	46	440	21.8	68	1.31	24.9	15.9	886
SW-28	A-4.1	12	415	20.6	83	1.60	25.5	15.5	803
SW-28	A-4.2	24	393	20.0	86	2.10	24.9	15.1	811

4.6 DEMONSTRATION TESTS

Representative operating conditions for the Indirect Heated Mode are shown in Table 4-3. They are average conditions demonstrated in tests A-4.1 and A-4.2 of Semi-Works Run SW-28. These values show a condition of high thermal efficiency as well as good operability.

The scope of process variation in the Indirect Heated Mode as opposed to the Direct Heated Mode, is greatly reduced because of the requirements for high thermal efficiency. Minor variations in the hot recycle gas temperature can be made with the following considerations:

1. The upper temperature limit is determined by the degree of hydrocarbon cracking that occurs. Cracking is also influenced by the moisture content of the recycle gas stream. A control of 30% moisture was maintained during these studies using the bottom recycle gas cooler to remove water from the system.
2. The increase in gas flow required to maintain the desired heat input into the system defines the lower input temperature. The closer this inlet temperature approaches the minimum bed temperature for complete retorting, the greater the gas flow required and the lower the temperature differential between the gas and solids. Total gas flow through the bed is also increased, which is detrimental to the mist formation and causes increased off-gas temperature.

Representative operating conditions for the Indirect

Heated Mode are shown in Table 4-3. They are average conditions demonstrated in tests A-4.1 and A-4.2 of Semi-Works Run SW-28. These values show a condition of high thermal efficiency as well as good operability.

The scope of process variation in the Indirect

Heated Mode as opposed to the Direct Heated Mode, is greatly

reduced because of the requirements for high thermal

efficiency. Minor variations in the hot recycle gas

temperature can be made with the following considerations:

1. The upper temperature limit is determined by the degree of hydrocarbon cracking that occurs. Cracking is also influenced by the moisture content of the recycle gas stream. A control of 30% moisture was maintained during these studies using the bottom recycle gas cooler to remove water from the system.
2. The increase in gas flow required to maintain the desired heat input into the system defines the lower input temperature. The closer this input temperature approaches the minimum bed temperature for complete retorting, the greater the gas flow required and the lower the temperature differential between the gas and solids. Total gas flow through the bed is also increased, which is detrimental to the mix formation and causes increased off-gas temperature.

TABLE 4-3

PARAHO INDIRECT HEATED MODE OPERATING CONDITIONS

DATE FROM SEMI-WORKS RUN SW-28

Rates and Quantities:

Temperature:

Recycle to Top Dist. SCF/T	10530	Product Oil °F	147
Recycle to Mid Dist. SCF/T	0	Retorted Shale °F	336
Recycle to Btm. Dist. SCF/T	11950	Raw Shale °F	40
Total Recycle Gas SCF/T	22480	Off-Gas °F	326
Raw Shale Rate TPH	10.2	Top Dist. Inlet °F	1299
Throughput lb/hr/ft	414	Btm Dist. Inlet °F	150

Miscellaneous:

Yields:

Retort Press drop in. H ₂ O/ft.	1.4	Oil Collected Gal/T	24.2
Carbonate Decomposition Wt%	2.5	Total Oil Yield C5+ Wt% F.A.	95
Retort Bed Height Ft. In.	24"6'	Product Gas SCF/T	535
		Retorted Shale TPH	9.1
		Retorted Shale Wt% RS	89
		Liquid Water Lbs/T	29.9

TABLE 4-3

TABLE 4-3
DATE FROM SEMI-WORKS RUN 2W-32

Rates and Quantities:		Temperatures:	
Recycle to top dist. SCP/T 10230	Product Oil °F	147	
Recycle to mid dist. SCP/T 0	Reformed Shale °F	336	
Recycle to bot. dist. SCP/T 11250	Raw Shale °F	40	
Total Recycle Gas SCP/T 23480	Off-Gas °F	336	
Raw Shale Rate TFR	Top Dist. Inlet °F	1399	
Throughput lb/hr	Bot. Dist. Inlet °F	150	
Miscellaneous:		Yields:	
Reform Press drop in. H ₂ O/Et. 1.4	Oil Collected Gal/T	24.1	
Carbonate Decomposition Wt% 1.2	Total Oil Yield CS+ Wt% F.A.	92	
Reform Bed Height F.T. In. 16.5	Product Gas SCP/T	235	
	Reformed Shale TFR	9.1	
	Reformed Shale Wt% H ₂	89	
	Reformed Water Lbs/T	28.9	

The yields of oil and product gas in Run SW-28 for the operating conditions are shown in Table 4-3. The 95 Wt% F.A. oil yield, as shown, represents the oil measured in the tank plus the calculated liquid obtained by adding all of the C5's and heavier naphtha fractions in the product gas stream going to the thermal oxidizer. The recovered oil without this naphtha addition was 93.5 wt% of F.A.

The product gas production for these two test periods (Run SW-28, A-4.1 and A-4.2) measured 535 SCF/T on a wet basis. Possible internal process gas leaks may have occurred in the heater during this period thus reducing the measured product gas yield. This loss is indicated by comparing these results to those of other Indirect Heated Mode tests.

The shale properties for the preceding tests are shown in Table 4-4 and product properties in Table 4-5.

The computer program balances shown in Section 7.2 Table 7-20 are based on raw shale weights and ash contents. Included as part of the computer program is the heat balance for the retort. This shows a hot gas input of 402 MBTU/T at the top distributor based on the 77°F datum temperature. The corresponding heat requirement based on gas blower discharge temperature of 214°F to the gas distributor inlet temperature of 1299°F is 378 MBTU/T.

The yields of oil and product gas in Run SW-18 for the operating conditions are shown in Table 4-3. The 92 wt% F.A. oil yield, as shown, represents the oil measured in the tank plus the calculated liquid obtained by adding all of the C₂'s and heavier naphtha fractions in the product gas stream going to the thermal oxidizer. The recovered oil without this naphtha addition was 93.5 wt% of F.A.

The product gas production for these two test periods (Run SW-18, A-4.1 and A-4.2) measured 535 BCF/T on a wet basis. Possible internal process gas leaks may have occurred in the heater during this period thus reducing the measured product gas yield. This loss is indicated by comparing these results to those of other indirect heated Mode tests.

The shale properties for the preceding tests are shown in Table 4-4 and product properties in Table 4-5.

The computer program balances shown in Section 7.2 Table 7-10 are based on raw shale weights and ash contents. Included as part of the computer program is the heat balance for the reactor. This shows a hot gas input of 402 MBTU/T at the top distributor based on the 77°F ambient temperature. The corresponding heat requirement based on gas blower discharge temperature of 214°F to the gas distributor inlet temperature of 1390°F is 378 MBTU/T.

TABLE 4-4

PARAHO INDIRECT HEATED MODE SHALE PROPERTIES

DATA FROM SEMI-WORKS RUN SW-28

<u>Shale Properties</u>		<u>Raw Shale</u>	<u>Retorted Shale</u>
Moisture Content	Wt%	1.23	0.0
Fischer Assay	Gal/T	26.3	0.50
F.A. ...Oil	Wt%	10.02	0.19
F.A. ...Water	Wt%	1.68	0.74
F.A. ...Gas + Loss	Wt%	2.03	0.62
Mineral CO ₂	Wt%	17.70	19.47
Ignition Loss	Wt%	32.02	23.32
Organic Carbon	Wt%	11.77	3.06
Carbon	Wt%	16.16	8.37
Hydrogen	Wt%	1.70	0.33
Nitrogen	Wt%	0.45	0.34

TABLE 4-4

BARANO INDIRECT HEATED MOON SHALE PROPERTIES

DATA FROM SEMI-WORKS RUN SW-28

<u>Retorted Shale</u>	<u>Raw Shale</u>	<u>Shale Properties</u>	
0.0	1.23	Wt%	Moisture Content
0.20	10.3	Gal/T	Fischer Assay
0.19	10.02	Wt%	F.A. ... Oil
0.24	1.88	Wt%	F.A. ... Water
0.82	2.02	Wt%	F.A. ... Gas + Loss Wt%
19.47	17.70	Wt%	Mineral CO ₂
23.32	32.02	Wt%	Ignition Loss
3.06	11.77	Wt%	Organic Carbon
8.77	16.16	Wt%	Carbon
0.32	1.70	Wt%	Hydrogen
0.24	0.42	Wt%	Nitrogen

4.7 PRODUCT PROPERTIES

TABLE 4-5

PARAHO INDIRECT HEATED MODE PRODUCT PROPERTIES

DATA FROM SEMI-WORKS RUN SW-28

<u>Product Oil Properties:</u>		<u>Product Gas Properties: (Dry)</u>	
Gravity, Deg API	20.2	Gross Heat Value BTU/SCF	808
Viscosity SUS @ 130°F	85.0	Specific Gravity	0.721
Viscosity SUS @ 210°F	45.7	Analysis: H ₂ Vol%	25.12
Ramsbottom Carbon Wt%	1.93	N ₂ Vol%	0.56
Water Content Vol%	1.07	O ₂ Vol%	0.0
Solids, B.S. Wt%	1.56	CO Vol%	2.73
Carbon Wt%	84.89	CH ₄ Vol%	32.15
Hydrogen Wt%	11.44	CO ₂ Vol%	15.24
Nitrogen Wt%	2.03	C ₂ H ₄ Vol%	12.74
		C ₂ H ₆ Vol%	4.52
		C ₃ 's Vol%	2.28
		C ₄ 's Vol%	0.61
		H ₂ S Vol%	2.82
		NH ₃ Vol%	1.23
		Moisture Vol%	28.82

4.8 SPECIAL DATA

During Semi-Works Run SW-28 test period A-4.1, a special large size gas sample stream was processed for complete analysis of recycle gas. Representatives from the Atlantic Richfield Company obtained two gas samples using the

TABLE 4-2

BARAN INDIRECT HEATED MOIST PRODUCT PROPERTIES

DATA FROM SEMI-WORKS RUN SW-18

Product Oil Properties:		Propane Gas Properties: (Dry)	
Gravity, Deg API	20.2	Gross Heat Value BTU/SCF	808
Viscosity SUS @ 110°F	62.6	Specific Gravity	0.721
Viscosity SUS @ 210°F	45.7	Analysis: H ₂ Vol%	22.12
Maximum Carbon Wt%	1.31	H ₂ Vol%	0.26
Water Content Vol%	1.07	CO ₂ Vol%	0.0
Solids, S.S. Wt%	1.26	CO Vol%	2.73
Carbon wt%	84.82	CH ₄ Vol%	32.12
Hydrogen Wt%	11.44	CO ₂ Vol%	12.24
Nitrogen Wt%	2.02	C ₂ H ₄ Vol%	12.74
		C ₂ H ₆ Vol%	4.22
		C ₃ H ₈ Vol%	2.28
		C ₄ H ₁₀ Vol%	0.61
		H ₂ S Vol%	2.82
		NH ₃ Vol%	1.22
		Moisture Vol%	28.82

4.7 PRODUCT PROPERTIES

Product properties show only minor changes with operating conditions. The changes in gas composition are the most significant, occurring from both carbonate decomposition and hydrocarbon cracking from increased distributor inlet temperatures. This can be seen in the complete tabulation of Indirect Heated Mode data in the Appendix D-3.

The Indirect Heated Mode product oil quality has shown lower viscosities than the Direct Heated Mode operations. Viscosities decrease with reductions in retort bed temperatures and increased efficiency of operation. Other associated oil properties such as pour point and API gravity also improve with lower viscosities as previously shown in Tables 4-1 and 4-2.

Retorted shale has a relatively high residual carbon and shows little change unless a condition of incomplete retorting occurs due to inadequate heat input or insufficient temperature. Some test periods shown for the Indirect Heated Mode reflect this condition, see Appendix Section D-3, Tests; SW-22 A-2; SW-28 Step 3, A-3, A-4 and A-4.4.

4.8 SPECIAL DATA

During Semi-Works Run SW-28 test period A-4.1, a special large size gas sample stream was processed for complete analysis of recycle gas. Representatives from the Atlantic Richfield Company obtained two gas samples using the

4.7 PRODUCT PROPERTIES

Product properties show only minor changes with operating conditions. The changes in gas composition are the most significant, occurring from both carbonate decomposition and hydrocarbon cracking from increased distributor inlet temperatures. This can be seen in the complete tabulation of Indirect Heated Mode data in the Appendix B-3.

The Indirect Heated Mode product oil quality has shown lower viscosities than the Direct Heated Mode operations. Viscosities decrease with reductions in reactor bed temperatures and increased efficiency of operation. Other associated oil properties such as pour point and API gravity also improve with lower viscosities as previously shown in Tables 4-1 and 4-2.

Reactor shale has a relatively high residual carbon and shows little change unless a condition of incomplete retorting occurs due to inadequate heat input or inefficient temperature. Some test periods shown for the Indirect Heated Mode reflect this condition, see Appendix Section B-3. Tests: SW-22 A-3; SW-28 Step 3, A-3, A-4 and A-4.4.

4.8 SPECIAL DATA

During Semi-Works Run SW-28 test period A-4.1, a special large size gas sample stream was processed for complete analysis of recycle gas. Representatives from the Atlantic Richfield Company obtained two gas samples using the

same techniques they employed during Direct Heated Semi-Works Run SW-20. The amounts of cold trap condensates were significantly greater than shown by the Paraho control laboratory. The values are shown in Table 4-6 are an average of the two tests and include the H_2S and NH_3 values obtained by the Paraho Laboratory. The increase in the C5+ naphtha fractions represent an increase of 226 BTU/SCF in the gross heating value of the product gas on a dry basis. The effect on the liquid yield is most significant, raising the C5+ yield from the 95% shown to 98 wt% F.A. Therefore, all of the C5+ yields given in the Appendix, Section D-3, may be 3 wt% low as the data reported are based on the Paraho control laboratory analyses. This change will also affect the hydrocarbon balances.

Special Paraho Laboratory data obtained during Semi-Works Indirect Heated Mode operations are shown in Table 4-7. Included are recycle gas contaminants (H_2S and NH_3), total sulfur, and Saybolt viscosities at 100°F.

As in the case of Direct Heated Mode operation, the levels of hydrogen sulfide and ammonia are approximately equal. Both modes of operation have large deviations including wide fluctuations in the levels from time to time.

Total sulfur data was obtained for crude oil and raw and retorted shale from two Indirect Heated Mode runs. These data do not differ significantly from Direct Heated Mode data.

Page 11

same techniques they employed during Direct Heated Semi-Works Run SW-20. The amount of cold trap condensates were significantly greater than shown by the Paraho control laboratory. The values are shown in Table 4-6 as an average of the two tests and include the H₂S and NH₃ values obtained by the Paraho laboratory. The increase in the C₂+ naphtha fractions represent an increase of 125 BTU/SCF in the gross heating value of the product gas on a dry basis. The effect on the liquid yield is most significant, raising the C₂+ yield from the 95% shown to 98 wt% F.A. Therefore, all of the C₂+ yields given in the Appendix, Section D-3, may be as low as the data reported are based on the Paraho control laboratory analyses. This change will also affect the hydrocarbon balances.

Special Paraho Laboratory data obtained during

Semi-Works Indirect Heated Mode operations are shown in Table 4-7. Included are recycle gas contaminants (H₂S and NH₃), total sulfur, and Saybolt viscosities at 100°F.

As in the case of Direct Heated Mode operation, the levels of hydrogen sulfide and ammonia are approximately equal. Both modes of operation have large deviations including wide fluctuations in the levels from time to time.

Total sulfur data was obtained for crude oil and raw and reformed shale from two Indirect Heated Mode runs. These data do not differ significantly from Direct Heated Mode data.

TABLE 4-6

INDIRECT HEATED MODE PRODUCT GAS ANALYSIS
ANALYSIS BY ATLANTIC RICHFIELD COMPANY
SEMI-WORKS RUN SW-28 TEST A-4.1

Product Gas Properties (Dry Basis)

Gross Heating Value	1036
Specific Gravity	.866
Analysis:	
H ₂ Vol%	22.95
N ₂ Vol%	0.38
O ₂ Vol%	0.01
CO Vol%	2.71
CH ₄ Vol%	30.20
CO ₂ Vol%	14.79
C ₂ H ₄ Vol%	11.34
C ₂ H ₆ Vol%	5.58
C ₃ 's Vol%	3.03
C ₄ 's Vol%	0.77
C ₅ 's Vol%	0.16
C ₆ 's+ Vol%	4.20
H ₂ S Vol%	2.71
NH ₃ Vol%	1.16

TABLE 4-2

INDIRECT HEATED MODE PRODUCT GAS ANALYSIS

ANALYSIS BY ATLANTIC RICHFIELD COMPANY

SEMI-WORKS RUN SW-28 TEST A-4.1

Product Gas Properties (Dry Basis)

Gross Heating Value 1036

Specific Gravity 0.866

Analysis:

H ₂ Vol%	23.92
H ₂ Vol%	0.38
O ₂ Vol%	0.01
CO Vol%	2.71
CH ₄ Vol%	30.30
CO ₂ Vol%	14.72
C ₂ H ₄ Vol%	11.34
C ₂ H ₆ Vol%	2.28
C ₃ 's Vol%	3.83
C ₄ 's Vol%	0.77
C ₅ 's Vol%	0.16
C ₆ + Vol%	4.30
N ₂ Vol%	2.71
Arg Vol%	1.16

TABLE 4-7

SPECIAL DATA SEMI-WORKS INDIRECT HEATED MODE OPERATIONS

Recycle Gas

H₂S, Vol% (9) 2.07 \pm 0.33

NH₃, Vol% (5) 2.02 \pm 1.31

Raw Shale

S, Wt% (3) 0.79 \pm 0.03

Ret Shale

S, Wt% (3) 0.74 \pm 0.15

Oil

S, Wt% (13) 0.62 \pm 0.05

SUS, 100°F (18) 192 \pm 55

NOTE: Data are presented as follows: number of tests (in parentheses) followed by mean values plus or minus one standard deviation.

TABLE 4-3
SPECIAL DATA SEMI-WORKS INDIRECT HEATED MODE OPERATIONS

Recycle Gas		
Wt%	Vol%	(3) 2.07 ± 0.11
Wt%	Vol%	(2) 2.02 ± 1.11
Raw Shale		
Wt%		(3) 0.73 ± 0.03
Ref Shale		
Wt%		(3) 0.74 ± 0.12
Oil		
Wt%		(13) 0.82 ± 0.02
Wt%		(18) 1.01 ± .25

NOTE: Data are presented as follows: number of tests (in parentheses) followed by mean value plus or minus one standard deviation.

Saybolt viscosities were determined at 100°F on the Indirect Heated Mode crude shale oil. The mean data (192 SUS) are not significantly reduced from the Direct Heated Mode data and some curvature still exists in the viscosity - temperature relationship from 100°F to 210°F.

An attempt was made to determine mist characteristics during Indirect Heated Mode operations. Probes fitted with packing glands and gate valves were installed during a retort outage because of potential hazards, due to the flammability and toxicity of indirect recycle gas. However, the small opening in the probe tips plugged and no valid samples were obtained.

5. EQUIPMENT
DESCRIPTION

5. PHYSICAL DESCRIPTION

5.1 DESCRIPTION OF PILOT PLANT

The Pilot Plant was constructed to explore the broad process parameters for the retorting process. The results of these studies provided the basis for the confirmation and demonstration runs in the Semi-Works retort.

The Pilot retort has a 1/4-inch mild steel plate shell of 4 1/2-foot outside diameter with an insulating lining, detailed in Appendix E. The inside diameter is 2 1/2-feet and the cross-sectional area inside the lining is 4.909 square feet.

The height of the retort vessel (from the retarder plate in the grate mechanism to the bottom of the raw shale level hopper) is 33.1 feet. The working bed height is adjustable. The overall height (from ground level to the upper rotary seal) is about 58 feet.

A cross-sectional diagram showing the retort dimensions and the position of the rotary seals, off-gas collector, distributors, and grate mechanism is shown on Drawing 8.

The solids handling system (Drawing 2) shows the flow of material for both Pilot and Semi-Works plant starting with the conveying system from the shale storage area. Crushed shale may be supplied from any one, or any combination, of four storage bins to a primary feed conveyor. As the crushed shale

2. PHYSICAL DESCRIPTION

2.1 DESCRIPTION OF PILOT PLANT

The Pilot Plant was constructed to explore the broad process parameters for the retorting process. The results of these studies provided the basis for the confirmation and demonstration runs in the Semi-Works retort.

The Pilot retort has a 1/4-inch mild steel plate shell of 1 1/2-foot outside diameter with an insulating lining. The inside diameter is 2 1/2-feet and the cross-sectional area inside the lining is 4.902 square feet.

The height of the retort vessel (from the retarding plate in the grate mechanism to the bottom of the raw shale level hopper) is 35.1 feet. The working bed height is adjustable. The overall height (from ground level to the upper rotary seal) is about 55 feet.

A cross-sectional diagram showing the retort dimensions and the position of the rotary seals, off-gas collector, distributors, and grate mechanism is shown on Drawing 8.

The solids handling system (Drawing 2) shows the flow of material for both Pilot and Semi-Works plant starting with the conveying system from the shale storage area. Crushed shale may be supplied from any one, or any combination, of four storage bins to a primary feed conveyor. As the crushed shale

leaves the primary belt conveyor, it passes over a motorized diversion gate used for sampling the raw shale for either Pilot or Semi-Works plants. Descriptions of the sampling systems are in the Laboratory Report. The crushed shale flows through the sampler gate to a short reversible belt conveyor that is used to divert the shale supply to either retort surge hopper. The shale is withdrawn continuously from each surge hopper by a vibrating feeder - weigh conveyor system and fed to the top of the retort.

The raw shale level control hopper on the top of the retort is used as a surge between the weighbelt conveyor and the retort. Shale feed rates are adjusted to maintain a constant level in the raw shale feed hopper. The hopper has a surge capacity of approximately one ton of material. The retort mass rate is controlled by the hydraulically operated grate at the bottom of the retort. Correlations of grate strokes and raw shale feed rates serve as a guide to establish a steady processing rate with only occasional adjustments.

The raw shale descends from the level control hopper, through a telescoping chute arrangement that is used for bed height adjustment within the retort vessel and into the retort. As the shale moves through the various zones, it passes around the top and mid distributors within the retort and continues to the discharge grate at the bottom of the retort.

The details of construction for the level control

leaves the primary belt conveyor, it passes over a motorized diversion gate used for sampling the raw shale for either Pilot or Semi-Works plants. Descriptions of the sampling systems are in the Laboratory Report. The crushed shale flows through the sampler gate to a short reversible belt conveyor that is used to divert the shale supply to either retort surge hopper. The shale is withdrawn continuously from each surge hopper by a vibrating feeder - weigh conveyor system and fed to the top of the retort.

The raw shale level control hopper on the top of the retort is used as a surge between the weighbelt conveyor and the retort. Shale feed rates are adjusted to maintain a constant level in the raw shale feed hopper. The hopper has a surge capacity of approximately one ton of material. The retort mass rate is controlled by the hydraulically operated grate at the bottom of the retort. Correlations of grate strokes and raw shale feed rates serve as a guide to establish a steady processing rate with only occasional adjustments.

The raw shale descends from the level control hopper, through a telescoping chute arrangement that is used for bed height adjustment within the retort vessel and into the retort. As the shale moves through the various zones, it passes around the top and mid distributors within the retort and continues to the discharge grate at the bottom of the retort.

The details of construction for the level control

hopper and telescoping adjustment system are on the retort cross-sectional drawing (Drawing 8).

The discharge grate mechanism consists of two side baffles used for bottom recycle gas entry and one pusher bar mechanism set on the single retarder plate. The retarder plate prevents free flow of material out of the retort. Shale discharge will only occur with reciprocal movement of the pusher bar. Sloping plates guide the shale bed toward the pusher bar which is alternately pulled by a hydraulic cylinder from each side of the retort. The pusher profile is carefully contoured to cause a laterally uniform descent of the shale throughout the retort cross-section. As the material is discharged from the retarder plate, it drops into a collection cone at the bottom of the retort. From there, the retorted shale passes through a double rotary seal system and drops onto the retorted shale conveyors. The rotary seals at the bottom of the retort act to retain internal gas pressure while discharging retorted shale. A purge gas is installed between the two rotors to assist in preventing leakage of gases through the seals.

As the retorted shale leaves the double rotary seals, it drops onto an inclined weighbelt conveyor, past a diversion gate for sampling, and to the disposal conveying system. This retorted shale weighbelt is similar to the raw shale feed weighbelt. Retorted shale from both the Pilot and Semi-Works retorts join to a common disposal conveying system as shown in Drawing 2. An alternate bypass chute arrangement was installed to provide an alternate method of

hopper and telescoping adjustment system are on the retort cross-sectional drawing (Drawing 2).

The discharge grate mechanism consists of two side

ballies used for bottom recycle gas entry and one pusher bar mechanism set on the single retarder plate. The retarder plate prevents free flow of material out of the retort. Shale discharge will only occur with reciprocal movement of the pusher bar. Sloping plates guide the shale bed toward the pusher bar which is alternately pulled by a hydraulic cylinder from each side of the retort. The pusher profile is carefully contoured to cause a laterally uniform descent of the shale throughout the retort cross-section. As the material is discharged from the retarder plate, it drops into a collection cone at the bottom of the retort. From there, the retorted shale passes through a double rotary seal system and drops onto the retorted shale conveyor. The rotary seals at the bottom of the retort act to retain internal gas pressure while discharging retorted shale. A purge gas is installed between the two rotors to assist in preventing leakage of gases through the seals.

As the retorted shale leaves the double rotary seals, it drops onto an inclined weighbelt conveyor, past a diversion gate for sampling, and to the disposal conveying system. This retorted shale weighbelt is similar to the raw shale feed weighbelt. Retorted shale from both the Pilot and Semi-Works rotors join to a common disposal conveying system as shown in Drawing 2. An alternate bypass chute arrangement was installed to provide an alternate method of

retorted shale disposal through the sampling system and out to a screw conveyor to the retorted shale disposal pile. During the use of this bypass arrangement (required for separating the retorted shale from both retorts during a simultaneous operation), sampling of the retorted shale can be accomplished only by grab samples rather than the usual continuous and automatic sampling operations.

The gas handling system for the Pilot Plant is shown on Drawing 3. Off gases from the shale bed leave the shale interface between the telescoping feed chute and the retort wall and are removed at a single collection point through a six-inch off gas line at the top of the retort. Using a pressure tap in the off gas line, a pressure controller adjusts the product gas valve position to maintain a slight positive pressure in the top of the retort. The off-gas containing oil mist passes through the six-inch line to the coalescer and then to the electrostatic precipitator for oil separation from the gas.

Clean recycle gas is piped to the suction of the seven stage Hoffman recycle blower and pressurized. The discharge of the recycle gas blower is diverted to four different lines for measurement and control; the bottom recycle gas line, the mid and top distributor gas lines, and the product gas vent line going to the thermal oxidizer. A common upstream pressure tap and temperature measurement is taken for these orifice runs. Each control loop consists of a controller, a throttle butterfly valve, and an orifice.

retorted shale disposal through the sampling system and out to a screw conveyor to the retorted shale disposal pile. During the use of this bypass arrangement (provided for separating the retorted shale from both retorts during a simultaneous operation), sampling of the retorted shale can be accomplished only by grab samples rather than the usual continuous and automatic sampling operations.

The gas handling system for the Pilot Plant is shown on

Drawing 3. Off gases from the shale bed leave the shale interface between the telescoping lead chute and the retort wall and are removed at a single collection point through a six-inch off gas line at the top of the retort. Using a pressure tap in the off gas line, a pressure controller adjusts the product gas valve position to maintain a slight positive pressure in the top of the retort. The off-gas containing oil mist passes through the six-inch line to the condenser and then to the electrostatic precipitator for oil separation from the gas.

Clean recycle gas is piped to the suction of the seven stage Hoffman recycle blower and pressurized. The discharge of the recycle gas blower is diverted to four different lines for measurement and control: the bottom recycle gas line, the mid and top distributor gas lines, and the product gas vent line going to the thermal oxidizer. A common upstream pressure tap and temperature measurement is taken for these orifice runs. Each control loop consists of a controller, a chiotic butterfly valve, and an orifice.

A seven stage Spencer blower using a suction filter supplies air for combustion purposes at all three distributors levels. Similar to the recycle system, the discharge of this blower is diverted to three lines of the bottom, mid, and top distributors for air supply. A common upstream pressure tap and thermocouple are used for all orifice runs and a butterfly control valve maintains positive flow control for each air entry point. Air is injected into the recycle gas lines for mixing prior to its entry into the distributors. A high velocity injection nozzle is used for this purpose.

For Indirect Heated Mode operations, the gas lines to the mid and top distributors are diverted through two vertical external gas heaters before entering each distributor. Arrangements for the Indirect Heated Mode operations are made using a system of blinds to divert the gas stream through the heater system. All materials of construction downstream of the heaters are of 304 stainless steel to provide temperature and corrosion resistance for hot gas operation.

The distributor system in the Pilot Plant consists of a single 4-inch stainless steel pipe using a row of injection orifices on each side of the pipe for proper gas distribution. A common circulating cooling water system is used to maintain temperature control of these distributors for Direct Heated Mode operation. During Indirect Heated operations, the distributor water cooling system is drained and vented to prevent cooling of the hot gases being supplied

A seven stage Spencer blower using a suction filter supplies air for combustion purposes at all three distributor levels. Similar to the recycle system, the discharge of this blower is diverted to three lines of the bottom, mid, and top distributors for air supply. A common upstream pressure tap and thermocouple are used for all orifice runs and a butterfly control valve maintains positive flow control for each air entry point. Air is injected into the recycle gas lines for mixing prior to its entry into the distributors. A high velocity injection nozzle is used for this purpose.

For Indirect Heated Mode operations, the gas lines to the mid and top distributors are diverted through two vertical external gas heaters before entering each distributor. Arrangements for the Indirect Heated Mode operations are made using a system of blinds to divert the gas stream through the heater system. All materials of construction downstream of the heaters are of 304 stainless steel to provide temperature and corrosion resistance for hot gas operation.

The distributor system in the Pilot Plant consists of a single 4-inch stainless steel pipe using a row of injection orifices on each side of the pipe for proper gas distribution. A common circulating cooling water system is used to maintain temperature control of these distributors for Direct Heated Mode operation. During Indirect Heated operations, the distributor water cooling system is drained and vented to prevent cooling of the hot gases being supplied

from the external heater.

The mist separation and oil recovery for the Pilot Plant include a coalescer and electrostatic precipitator. The coalescer system is designed to remove about half of the mist prior to the final cleanup in the electrostatic precipitator. The coalescer, consisting of a system of sprays followed by a knockout chamber, removes mist from the gas stream with negligible pressure loss (Drawing 11). The electrostatic precipitator is a wet type unit originally purchased by the U.S. Bureau of Mines in the 1950's. It was installed to remove oil mist for the Pilot Plant operation. During proper operation, oil recovery, determined from mist analysis, exceeded 99%. An accumulation of oil within the coalescer recirculating tank overflows by gravity and joins the electrostatic precipitator product stream going to storage. A gravity oil drain and sealing system equipped with heat tracing and insulation to two rundown tanks is used for both the electrostatic precipitator and the coalescer. Two rundown tanks are employed for the Pilot Plant, each having a cone bottom and a capacity of approximately 35 barrels (about one day's operation at high shale rates).

Instrumentation for the Pilot Plant, shown on Drawing 3, includes a temperature-pressure probe device within the retort bed for measurement for bed temperature and pressures. This temperature-pressure probe consists of a two-inch stainless pipe equipped with 14 thermocouples spaced at two-foot intervals and five pressure points as shown on the retort cross-sectional

from the external heater.

The mist separation and oil recovery for the

Pilot Plant include a coalescer and electrostatic precipitator.

The coalescer system is designed to remove about half of

the mist prior to the final cleanup in the electrostatic

precipitator. The coalescer, consisting of a system of sprays

followed by a knockout chamber, removes mist from the gas stream

with negligible pressure loss (Drawing II). The electrostatic

precipitator is a wet type unit originally purchased by the U.S.

Bureau of Mines in the 1950's. It was installed to remove oil

mist for the Pilot Plant operation. During proper operation,

oil recovery, determined from mist analysis, exceeded 99%.

An accumulation of oil within the coalescer recirculating tank

overflows by gravity and joins the electrostatic precipitator

product stream going to storage. A gravity oil drain and

sealing system equipped with heat tracing and insulation to two

run-down tanks is used for both the electrostatic precipitator

and the coalescer. Two run-down tanks are employed for the

Pilot Plant, each having a cone bottom and a capacity of

approximately 35 barrels (about one day's operation at high

shale rates).

Instrumentation for the Pilot Plant, shown on Drawing

3, includes a temperature-pressure probe device within the

retort bed for measurement for bed temperature and pressure.

This temperature-pressure probe consists of a two-inch stainless

pipe equipped with 14 thermocouples spaced at two-foot intervals

and five pressure points as shown on the retort cross-sectional

diagram (Drawing 8). These bed temperatures and other gas and oil temperatures throughout the Pilot Plant are recorded on multi-point strip chart recorders. Bed pressures and orifice differential pressure leads are connected to manometers on the control panel. All gas and air flows are recorded on miniature circular charts in the analog controllers on the control panel. The manometer readings, weight counter readings, and many temperatures are recorded hourly in the control room by the retort operators. Cooling water rates are measured and temperatures in and out of the distributors recorded for calculation of heat loss to the cooling water.

The hydraulic circuitry includes an electrical alarm on a delay relay to indicate grate stoppage. Electrical interlocking is used to turn off the air blower when the recycle gas blower fails. A secondary override for the air blower is tied to the startup propane valve to prevent propane injection during startup periods in case of air blower failure.

An on-line gas chromatograph, a continuous oxygen analyzer and an Orsat apparatus are used to monitor components of the recycle gas. A switchover system permits monitoring Pilot or Semi-Works operations. An on-line gas chromatograph continuously monitors these gases: oxygen, nitrogen, carbon monoxide, carbon dioxide, methane, ethylene, and ethane in the recycle gas stream. Attenuator switches permit monitoring of the gas in either the Direct or Indirect Heated Mode of operation.

Diagram (Drawing 8) shows these bed temperatures and other gas and oil temperatures throughout the Pilot Plant are recorded on multi-point strip chart recorders. Bed pressures and orifice differential pressure leads are connected to manometers on the control panel. All gas and air flows are recorded on miniature circular charts in the analog controllers on the control panel. The manometer readings, weight counter readings, and many temperatures are recorded hourly in the control room by the record operators. Cooling water rates are measured and temperatures in and out of the distributors recorded for calculation of heat loss to the cooling water.

The hydraulic circuitry includes an electrical alarm on a delay relay to indicate grate stoppage. Electrical interlocking is used to turn off the air blower when the recycle gas blower fails. A secondary override for the air blower is tied to the startup propane valve to prevent propane injection during startup periods in case of air blower failure.

An on-line gas chromatograph, a continuous oxygen analyzer and an Orsat apparatus are used to monitor components of the recycle gas. A switchover system permits monitoring Pilot or Semi-Works operations. An on-line gas chromatograph continuously monitors these gases: oxygen, nitrogen, carbon monoxide, carbon dioxide, methane, ethylene, and ethane in the recycle gas stream. Attenuator switches permit monitoring of the gas in either the Direct or Indirect Heated Mode of operation.

5.2 DESCRIPTION OF SEMI-WORKS PLANT

The Semi-Works Plant was used to provide data for commercial evaluation and design basis. Selected operating conditions on the retort was used to demonstrate and confirm the design criteria used for the commercial evaluation.

The retort is shown in Drawing 9, and detailed in Appendix E. It is a 10 1/2-foot O.D. cylindrical vessel having an outer shell of 1/4-inch steel plate. The 1-foot thick retort lining has been altered from a circular cross-section to provide flat walls parallel to the air-gas distributors. The circular section has an internal diameter of 8 1/2-feet and the flat walls are 6 1/2-feet apart giving an unrestricted cross-sectional area of 49.25 square feet.

The retort construction, auxiliary equipment and instrumentation are similar to that of the Pilot Plant and unless otherwise stated the equipment function and description will be the same.

The increased retort diameter requires two air-gas distributors at each level and two parallel pusher bars for the grate discharge mechanism. The height of the retort vessel (from retarder plate in the grate mechanism to the bottom of the raw shale level hopper) is 41 1/2-feet and the overall height is about 72 feet.

5.2 DESCRIPTION OF SEMI-WORKS PLANT

The Semi-Works Plant was used to provide data for commercial evaluation and design basis. Selected operating conditions on the reactor was used to demonstrate and confirm the design criteria used for the commercial Evaluation.

The reactor is shown in Drawing 9, and detailed in Appendix E. It is a 10 1/2-foot O.D. cylindrical vessel having an outer shell of 1/4-inch steel plate. The 1-foot thick reactor lining has been altered from a circular cross-section to provide flat walls parallel to the air-gas distributors. The circular section has an internal diameter of 8 1/2-feet and the flat walls are 6 1/2-feet apart giving an unrestricted cross-sectional area of 49.25 square feet.

The reactor construction, auxiliary equipment and instrumentation are similar to that of the Pilot Plant and unless otherwise stated the equipment function and description will be the same.

The increased reactor diameter requires two air-gas distributors at each level and two parallel pusher bars for the grate discharge mechanism. The height of the reactor vessel (from retainer plate in the grate mechanism to the bottom of the raw shale level hopper) is 41 1/2-feet and the overall height is about 72 feet.

The retorts use a common raw shale supply system from the storage bins through the raw shale sampler to the surge hoppers (see Drawing 2). The raw shale surge hopper for the Semi-Works retort contains approximately a two-hour shale supply for normal operations. Shale level is controlled with a high level shutoff switch to the feed conveying system and a low level alarm system.

Shale leaving the surge hopper passes over the vibrating feeder to a bucket elevator which feeds a second small surge bin. The small surge bin (only a few minutes capacity) for the elevator discharge is used to supply the vibrating feeder which feeds the raw shale weighbelt. A high and low level control is used to maintain a shale level in this small surge bin. The weighbelt-feeder system for the Semi-Works unit operates similarly, but its capacity is approximately ten times greater than the Pilot Plant.

A diversion chute from the Semi-Works weighbelt conveyor provides a method of weight calibration and check by routing the shale to a truck for weighing. Under normal operations, the discharge from the weighbelt conveyor passes directly to the top rotary seal and into the level control hopper at the top of the retort.

The level control hopper for the Semi-Works retort discharges into a rotating solids distributor which spreads shale across the full diameter of the retort to control particle size segregation as the shale enters the retort.

The report has a common raw shale supply system from the storage bins through the raw shale sampler to the surge hoppers (see Drawing 3). The raw shale surge hopper for the Semi-Works report contains approximately a two-hour shale supply for normal operations. Shale level is controlled with a high level shutoff switch to the feed conveying system and a low level alarm system.

Shale leaving the surge hopper passes over the vibrating feeder to a bucket elevator which feeds a second small surge bin. The small surge bin (only a few minutes capacity) for the elevator discharge is used to supply the vibrating feeder which feeds the raw shale weighbelt. A high and low level control is used to maintain a shale level in this small surge bin. The weighbelt-feeder system for the Semi-Works unit operates similarly, but its capacity is approximately ten times greater than the Pilot Plant.

A diversion chute from the Semi-Works weighbelt conveyor provides a method of weight calibration and check by routing the shale to a truck for weighing. Under normal operations, the discharge from the weighbelt conveyor passes directly to the top rotary seal and into the level control hopper at the top of the report.

The level control hopper for the Semi-Works report discharges into a rotating solids distributor which spreads shale across the full diameter of the report to control particle size segregation as the shale enters the report.

Solids flow around submerged off-gas collectors and descend through the Semi-Works retort as previously explained in the Pilot Plant description. The Semi-Works retort differs from the Pilot retort in that it uses submerged off-gas collectors and has two distributors for the top and middle air-gas entries and two parallel pusher bars and retarder plates for the discharge grate mechanism. In the bottom of the retort, there is a single retorted shale collecting cone and a double rotary seal assembly. The retorted shale discharges from the retort onto a retorted shale weighbelt, and from there to the retorted shale sampling and disposal system.

Two parallel off-gas collectors are installed across the retort bed normal to the straight sidewalls. They are half-pipes with vertical skirts extending downward to effectively cause the gases to exit the shale lump surface and enter off-gas ports. The ports are manifolded and are joined in a Y to a single pipe leading to the oil recovery equipment. Temperatures are recorded from each of the four discharge ports. The single pipe contains a thermocouple which represents a composite of the individual port temperatures. After leaving the oil separation equipment, the recycle gas is compressed in a seven-stage blower for distribution to the recycle system as shown in Drawing 4. For the Direct Heated Mode, another seven-stage blower is used to supply air for injection into the gas lines.

Solids flow around submerged off-gas collectors and descend through the Semi-Works retort as previously explained in the Pilot Plant description. The Semi-Works retort differs from the Pilot retort in that it uses submerged off-gas collectors and has two distributors for the top and middle air-gas entries and two parallel pusher bars and retainer plates for the discharge grate mechanism. In the bottom of the retort, there is a single retorted shale collecting cone and a double rotary seal assembly. The retorted shale discharges from the retort onto a retorted shale conveyor, and from there to the retorted shale sampling and disposal system.

Two parallel off-gas collectors are installed across the retort bed normal to the straight sidewalls. They are half-pipes with vertical exits extending downward to effectively cause the gases to exit the shale lump surface and enter off-gas ports. The ports are manifolded and are joined in a Y to a single pipe leading to the oil recovery equipment. Temperatures are recorded from each of the four discharge ports. The single pipe contains a thermocouple which represents a composite of the individual port temperatures. After leaving the oil separation equipment, the recycle gas is compressed in a seven-stage blower for distribution to the recycle system as shown in Drawing 4. For the Direct Heated Model, another seven-stage blower is used to supply air for injection into the gas lines.

The gas heating equipment for supplying hot gas for the Indirect Heated Mode operations is similar in function but of different design than that employed for the Pilot Plant. The Semi-Works external heaters are fired with No. 2 fuel oil and have six horizontal tube banks, designed to heat the gas to 1400°F. An additional change for Indirect Heated Mode operations in the Semi-Works unit was the installation of the gas cooler - knockout pot arrangement for the bottom recycle gas. The function of this is to control the water vapor in the gas going to the heater by condensing and removing water from the system. A temperature controller is used to measure downstream gas temperature and to control the flow of cooling water to the water jacket of the cooler.

The product gas is burned in the thermal oxidizer. During the Indirect Heated Mode operation, the volume of product gas was much less than the Direct Heated Mode and therefore a small control valve was used on the product gas line.

The oil recovery system for the Semi-Works retort is of similar design, construction, and operation as that in the Pilot retort. A number of minor differences in the piping were made to remove oil from both the electrostatic precipitator and coalescer. These differences are shown on Drawings 4 and 5. Rundown tanks for the Semi-Works retort each provide capacity for about eight hours of operation. For details of the shale oil rundown and storage system, see Section 5.4 Auxiliary Systems.

The gas heating equipment for supplying hot gas

for the Indirect Heated Mode operation is similar in function but of different design than that employed for the Pilot Plant. The Semi-Works external heaters are fired with No. 2 fuel oil and have six horizontal tube banks, designed to heat the gas to 1400°F. An additional change for Indirect Heated Mode operation in the Semi-Works unit was the

installation of the gas cooler - knockout pot arrangement for the bottom recycle gas. The function of this is to control the water vapor in the gas going to the heater by condensing and removing water from the system. A temperature controller is used to measure downstream gas temperature and to control the flow of cooling water to the water jacket of the cooler.

The product gas is burned in the thermal oxidizer.

During the Indirect Heated Mode operation, the volume of product gas was much less than the Direct Heated Mode and therefore a small control valve was used on the product gas line.

The oil recovery system for the Semi-Works reactor

is of similar design, construction, and operation as that in the Pilot reactor. A number of minor differences in the piping were made to remove oil from both the electrostatic precipitator and condenser. These differences are shown on Drawings 4 and 5. Run-down tanks for the Semi-Works reactor each provide capacity for about eight hours of operation. For details of the shale oil run-down and storage system, see Section 2.4 Auxiliary Systems.

5.3 MATERIALS HANDLING EQUIPMENT

The temperature - pressure probe used in the Semi-Works retort is located as shown on Drawing 9 and the gas analysis equipment is manifolded so that the gas can be analyzed from either plant.

5.3.1 SOLIDS

New shale preparation includes the stockpiles and primary crushing and screening through the storage and distribution system as shown on Drawing 1. This complex was installed in 1946 and because deliveries of desired materials were so long, it was necessary to use the equipment that was available, most of which was old and in poor condition. The system selected for this project was a combination of size or size distribution. Primary crushing is accomplished in a Blake jaw crusher, built in 1919, which reduces material to approximately 3 inch maximum long size. From there, the crushed shale is conveyed to a double deck primary screen. The oversize material is crushed in a secondary double roll tooth crusher. Products from the secondary crusher are recycled back over the screen to acquire the size product specified for retort operations. By varying screen size and crusher settings, feed material from a top size of 1 1/2 to 4-inch is produced in this crushing and screening operation. The undersize material is removed as desired by the lower deck screen and discarded to a final pile.

The sized shale from the screen is transported by a system of belt conveyors to four storage bins consisting

5.3 MATERIALS HANDLING EQUIPMENT

This section describes the equipment as well as limitations of the solids, gas and oil handling systems of the Pilot and Semi-Works plants.

5.3.1 SOLIDS

Raw shale preparation includes the stockpiles and primary crushing and screening through the storage and distribution system as shown on Drawing 1. This complex was installed in 1946 and because deliveries of desired equipment were so long, it was necessary to use the equipment that was available, most of which was old and in poor condition. The system cannot adequately control particle shape factor or size distribution. Primary crushing is accomplished in a Blake jaw crusher, built in 1919, which reduces material to approximately 5 inch maximum lump size. From there, the crushed shale is conveyed to a double deck primary screen. The oversized material is crushed in a secondary double roll tooth crusher. Products from the secondary crusher are recycled back over the screen to acquire the size product specified for retort operations. By varying screen size and crusher settings, feed material from a top size of 1 1/2 to 4-inches is produced in this crushing and screening operation. The undersize material is removed as desired by the lower deck screen and discarded to a fines pile.

The sized shale from the screen is transported by a system of belt conveyors to four storage bins consisting

2.1 MATERIALS HANDLING EQUIPMENT

This section describes the equipment as well as limitations of the solids, gas and oil handling systems of the prior and Semi-Works plants.

2.1.1 SOLIDS

Raw shale preparation includes the stockpiles and primary crushing and screening through the storage and distribution system as shown on Drawing I. This complex was installed in 1946 and because deliveries of desired equipment were so long, it was necessary to use the equipment that was available, most of which was old and in poor condition. The system cannot adequately control particle shape factor or size distribution. Primary crushing is accomplished in a Blake jaw crusher, built in 1919, which reduces material to approximately 5 inch maximum lump size. From there, the crushed shale is conveyed to a double deck primary screen. The oversized material is crushed in a secondary double roll tooth crusher. Products from the secondary crusher are recycled back over the screen to acquire the size product specified for test operations. By varying screen size and crusher settings, feed material from a top size of 1 1/2 to 4-inches is produced in this crushing and screening operation. The undersize material is removed as desired by the lower deck screen and discarded to a fines pile. The sized shale from the screen is transported by a system of belt conveyors to four storage bins consisting

of three 80-ton bins with cone bottoms and one 1,000-ton bin. Shale removal from the 80-ton storage bins is accomplished with vibrating feeders equipped with perforated decks for fines removal and the 1000-ton bin equipped with a vibrating feeder without fines removal equipment.

The shale is transported from the feeders by belt conveyors to a polishing screen where fines are removed prior to being conveyed to the retort surge hoppers. The fines waste belt conveyor from the bin discharge feeders is also used for emptying or recirculating the bins. All bin discharge and conveying equipment is controlled from the retort control room, thus providing complete flexibility in blending or switching bins.

The variation in screen analysis of the retort feed is used to evaluate the crushing operation performance and to control crusher maintenance and adjustment.

A primary requirement of retorting operations involving crushed and screened material is the proper control of particle size distribution. Even though crushing and screening facilities may provide a properly sized raw shale product, this size distribution must be maintained through storage and handling facilities to achieve a minimum of variation in the actual feed to the retort. To meet the tonnage requirements for retorting, it was necessary to make maximum use of available shale storage facilities even though problems of particle size

of three 80-ton bins with cone bottoms and one 1,000-ton bin. Shale removal from the 80-ton storage bins is accomplished with vibrating feeders equipped with perforated decks for fines removal and the 1000-ton bin equipped with a vibrating feeder without fines removal equipment.

The shale is transported from the feeders by belt conveyors to a polishing screen where fines are removed prior to being conveyed to the retort surge hoppers. The fines waste belt conveyor from the bin discharge feeders is also used for emptying or recirculating the bins. All bin discharge and conveying equipment is controlled from the retort control room, thus providing complete flexibility in blending or switching bins.

The variation in screen analysis of the retort feed is used to evaluate the crushing operation performance and to control crusher maintenance and adjustment.

A primary requirement of retorting operations involving crushed and screened material is the proper control of particle size distribution. Even though crushing and screening facilities may provide a properly sized raw shale product, this size distribution must be maintained through storage and handling facilities to achieve a minimum of variation in the actual feed to the retort. To meet the tonnage requirements for retorting, it was necessary to make maximum use of available shale storage facilities even though problems of particle size

segregation existed in the bins. Particle size segregation occurred while filling and emptying the four storage bins. A system of baffles installed in the bottom of the 80-ton storage bins aggravated this problem and retained fines which could be removed only after a complete emptying of the bins. Particle size segregation problems were also detected in the surge bins at the Pilot and Semi-Works retorts and within the level control bins at the top of the retorts. The surge bins feed arrangement was changed and the level control mechanism within the retort feed bins was repositioned, which alleviated some of the segregation problems.

An associated problem with particle size segregation involves shale with high surface moisture. Due to lack of enclosed storage, the mine run shale is trucked to a large open area stockpile before feeding the crusher. This open storage pile is exposed to all weather conditions, the worst of which can cause serious problems. The natural adhesion character of the wetted fines cause them to stick to the larger particles and be carried through the system and into the retort. This in turn causes high retort pressure drop together with restricting the gas piping flow and contaminating the product oil.

The following additional problems were experienced in the old plant:

1. Excessive maintenance on old equipment
2. Inadequate storage capacity

SECTION 1124

ENDORSEMENT

ARRESTION BOND

3. Inadequate crushing capacity
4. Screen inefficiency
5. Design restriction for additional equipment

Under item 5, the surge bins for the Pilot and Semi-Works plants were designed into the existing retort structure used for former operations. These restrictions resulted in a poor design that contributed to segregation of particles.

Fines, surface moisture and particle size segregation were shown to affect retort operations. However, the retort tolerance of these effects was proved in a 56 day run in the Semi-Works retort through the severe winter weather conditions.

Particle size segregation always occurs when a mixture of different sizes of particles is allowed to seek its angle of repose. Segregation also occurs during a gravitational flow in passing from a smaller to a larger cross-sectional area. This principle is present in the Pilot retort telescoping chute feeding device but caused only minor particle segregation due to a small change in diameter between the telescoping chute and the retort. The effects are not evident in the data or operation.

The Semi-Works rotary solids distributor assembly consists of four feeder legs. One pair of legs places the shale in a ring near the retort wall and the other pair places the shale in a ring near the center of the retort. This minimizes segregation in the flow of shale from the

3. Inadequate crushing capacity
4. Screen inefficiency
5. Design restriction for additional equipment

Under item 5, the surge bin for the Pilot and Semi-Works plants were designed into the existing retort structure used for former operations. These restrictions resulted in a poor design that contributed to segregation of particles.

Finer, surface moisture and particle size segregation were shown to affect retort operations. However, the retort tolerance of these effects was proved in a 56 day run in the Semi-Works retort through the severe winter weather conditions.

Particle size segregation always occurs when a mixture of different sizes of particles is allowed to seek its angle of repose. Segregation also occurs during gravitational flow in passing from a smaller to a larger cross-sectional area. This principle is present in the Pilot retort telescoping chute feeding device but caused only minor particle segregation due to a small change in diameter between the telescoping chute and the retort. The effects are not evident in the data on operation.

The Semi-Works rotary solids distributor assembly consists of four feeder legs. One pair of legs places the shale in a ring near the retort wall and the other pair places the shale in a ring near the center of the retort. This minimizes segregation in the flow of shale from the

smaller hopper into the larger retort cross-section, but will not correct for particle size variation in the feed to the retort.

The linear grate mechanism installed in both Pilot and Semi-Works retorts controls the solids flow throughout the retort cross-section.

The results of cold flow tests made with typical retort feed in both retorts confirmed the uniform movement of solids. The initial tests in the Pilot retort confirmed the residence time of particles moving through the bed is independent of particle size or position within the retort. In the first Semi-Works cold flow test, the standard deviation of all particle residence times was 7.6%. A portion of this variance was caused by the slower movement of the shale adjacent to the straight sidewalls of the retort. The pusher bar contour was modified and a subsequent cold flow test showed a standard deviation of all particle size residence times at 4.2%, an overall improvement over the first test. This standard deviation compares favorably with the Pilot Plant value of 4.3% for all particle size residence times.

Operational experience of the grate mechanism on both retorts uncovered some problems that required adjustment and alterations during the program. Problems with early unstable control of the discharge mechanism were traced to initial design of the hydraulic system. Pressure loss in the hydraulic line from the hydraulic supply system to the retort was being affected by variation in the ambient

smaller hopper into the larger retort cross-section, but will not correct for particle size variation in the feed to the retort.

The linear grate mechanism installed in both Pilot and Semi-Works retorts controls the solids flow throughout the retort cross-section.

The results of cold flow tests were with typical retort feed in both retorts confirmed the uniform movement of solids. The initial tests in the Pilot retort confirmed the residence time of particles moving through the bed is independent of particle size or position within the retort.

In the first Semi-Works cold flow test, the standard deviation of all particle residence times was 7.6%. A portion of this variance was caused by the slower movement of the shale adjacent to the straight sidewalls of the retort. The washer bar contour was modified and a subsequent cold flow test showed a standard deviation of all particle size residence times at 4.3%, an overall improvement over the first test. This standard deviation compares favorably with the Pilot Plant value of 4.3% for all particle size residence times.

Operational experience of the grate mechanism on both retorts uncovered some problems that required adjustment and alterations during the program. Problems with early unstable control of the discharge mechanism were traced to initial design of the hydraulic system. Pressure loss in the hydraulic line from the hydraulic supply system to the retort was being affected by variation in the ambient

temperature and uninsulated lines. This was corrected by proper tracing and insulating of the system. A problem of flow restriction was caused by undersized lines. Larger hydraulic lines were installed which corrected this problem.

During the early runs on both the Semi-Works and Pilot Plants, frequent failures of hydraulic cylinder seals and packing occurred. This problem was traced to a buildup of material on the piston rods that was not removed by the rod seal/wipers. A laboratory analysis of the material indicated the presence of magnetic iron dust as one of the contributing components of this buildup material. An extension box was mounted between the hydraulic cylinders and the retort discharge cone. A new sealing arrangement to prevent gas leakage was constructed around this connecting rod assembly. The failures of hydraulic cylinder seals caused three runs in the retort to terminate.

After revisions, the Semi-Works plant completed 122 days of actual retort operations with only two outages due to hydraulic cylinder problems.

The rotary seals limited the size of material that could be fed to the retorts as they will pass only minus 3-inch raw shale. During Semi-Works Runs SW-14 through SW-18, 3 1/2-inch raw shale was processed by removing the rotor in the top rotary seal. The retort was filled with 2 3/4-inch shale to protect the lower rotary seals during start-up. The 3 1/2-inch shale was then added. Once retorted, 3 1/2-inch material passes through the bottom rotary seals

temperatures and uninsulated lines. This was corrected by proper tracing and insulating of the system. A problem of flow restriction was caused by undersized lines. Larger hydraulic lines were installed which corrected this problem.

During the early runs on both the Semi-Works and Pilot Plants, frequent failures of hydraulic cylinder seals and packing occurred. This problem was traced to a buildup of material on the piston rods that was not removed by the rod seal/wipers. A laboratory analysis of the material indicated the presence of magnetic iron dust as one of the contributing components of this buildup material. An extension box was mounted between the hydraulic cylinders and the retort discharge cone. A new sealing arrangement to prevent gas leakage was constructed around this connecting rod assembly. The failures of hydraulic cylinder seals caused three runs in the retort to terminate.

After revisions, the Semi-Works plant completed 122 days of actual retort operations with only two outages due to hydraulic cylinder problems.

The rotary seals limited the size of material that could be fed to the retorts as they will pass only minus 3-inch raw shale. During Semi-Works Runs SW-14 through SW-18, 3 1/2-inch raw shale was processed by removing the rotor in the top rotary seal. The retort was filled with 3 3/4-inch shale to protect the lower rotary seals during start-up. The 3 1/2-inch shale was then added. Once retorted, 3 1/2-inch material passes through the bottom rotary seals

with no problems.

In early operations, occasional overload due to shale particles locking in the top rotary seals caused drive shear pins to fail. A delay in feeding operations resulted until a new pin could be manually installed. To decrease these interruptions, the seals were equipped with momentary torque limiting electrical overload protection having automatic reset, manual reversing switches, and coupled with an alarm. Through this improvement, the operator could remotely operate the seal and relieve the blockage without leaving the control room.

High wear rates were experienced with the original rotary seals in the Semi-Works retort prior to Run SW-12. The original rotary seals in the retorted shale service were replaced with newly designed double rotary seals having a low rate air purge to the endbells. There were no further problems with the seals.

The handling of retorted shale from the rotary seal discharge to disposal was by a system of conveyors and chutes. Much of the retorted shale was loaded into trucks and transported to the retorted shale management research area. The remainder was placed in the disposal canyon. A stacker conveyor was added during the changes proceeding Semi-Works SW-12. The conveyor is equipped with a motorized swivel movement system that greatly reduced the direct handling requirements for retorted shale disposal.

with no problems.

In early operations, occasional overload due to shale particles locking in the top rotary seals caused drive shear pins to fail. A delay in feeding operations resulted until a new pin could be manually installed. To decrease these interruptions, the seals were equipped with momentary torque limiting electrical overload protection having automatic reset, manual reversing switches, and coupled with an alarm. Through this improvement, the operator could remotely operate the seal and relieve the blockage without leaving the control room.

High wear rates were experienced with the original rotary seals in the Semi-Works retrofit prior to Run SW-12. The original rotary seals in the retrofitted shale service were replaced with newly designed double rotary seals having a low rate air purge to the endbell. There were no further problems with the seals.

The handling of retrofitted shale from the rotary seal discharge to disposal was by a system of conveyors and chutes. Much of the retrofitted shale was loaded into trucks and transported to the retrofitted shale management research area. The remainder was placed in the disposal canyon. A stacker conveyor was added during the changes proceeding Semi-Works SW-12. The conveyor is equipped with a motorized swivel movement system that greatly reduced the direct handling requirements for retrofitted shale disposal.

Dry type dust collection that is properly designed and installed works quite successfully controlling retorted shale dust. Retorted shale dust can be adequately controlled by either confinement or dry type dust collection in all areas. Fugitive dust from the disposal pile is not a specific problem. A minor problem of dust picked up by a thermal draft did exist on the disposal pile caused by a stream of warm retorted shale moving down the angle of repose on the pile. This can also be controlled with dry type dust collection except during periods of excessive wind conditions.

The retorted shale weighbelt presented many difficulties throughout the program. Intermittent high temperatures caused by upset operating conditions resulted in belt expansion and deterioration which affected the accuracy of the weight measurements. Test data presented in this report uses the raw shale weights and the ash measurements in the raw and retorted shales to calculate the retorted shale weights whenever the measured weight causes the ash balance to be outside the range of 99-101 weight percent.

5.3.2 GAS

The Pilot and Semi-Works retorts are equipped with rotary seals to allow shale into and out of the retort and minimize leakage of air into or gas out. During Semi-Works Runs SW-14 through SW-18, the rotor was removed from

Dry type dust collection that is properly designed and installed works quite successfully controlling returned ash dust. Returned ash dust can be adequately controlled by either confinement or dry type dust collection in all areas. Fugitive dust from the disposal pile is not a specific problem. A minor problem of dust picked up by a thermal draft did exist on the disposal pile caused by a stream of warm returned ash moving down the angle of repose on the pile. This can also be controlled with dry type dust collection except during periods of excessive wind conditions.

The returned ash weight presented many difficulties throughout the program. Intermittent high temperatures caused by upset operating conditions resulted in belt expansion and deterioration which affected the accuracy of the weight measurements. Test data presented in this report uses the raw ash weights and the ash measurements in the raw and returned ashes to calculate the returned ash weights whenever the measured weight causes the ash balance to be outside the range of 99-101 weight percent.

5.3.2 GAS

The Pilot and Semi-Works rotors are equipped with rotary seals to allow ash into and out of the rotor and minimize leakage of air into or gas out. During Semi-Works Runs SW-14 through SW-18, the rotor was removed from

the top seal to accommodate larger size shale feed. Control of air in-leakage and product gas loss was attempted using top pressure control. Because of the gas valve actions, this control was not adequate and the rotor was again installed in the seal.

Gas loss through the rotary seals varies with wear to the seals and operating conditions. A method was developed to measure these gas losses from both the top and bottom rotary seals. In this report, the gas loss through the rotary seal has been added to the product gas quantities for Indirect Heated Mode data. The data does not account for the proportionately small seal loss in the Direct Heated Mode.

Bed height adjustment in the Semi-Works retort is made by the addition of extension skirts to the off-gas collectors. In the Pilot retort, an adjustment of the telescoping shale feed chute is used for this purpose.

After leaving the retort, the recycle gas passes through the oil mist recovery equipment to the recycle gas blower. All major piping and vessels between the retort and suction of the recycle blower was insulated to prevent exposure to extreme weather conditions. A foam type insulation was used to prevent condensation of moisture thus reducing the moisture content of the product oil. A substantial decrease in water content of the product oil was shown following insulation of the pipes.

the top seal to accommodate larger size shale feed. Control of air in-leakage and product gas loss was attempted using top pressure control. Because of the gas valve actions, this control was not adequate and the rotor was again installed in the seal.

Gas loss through the rotary seals varies with wear to the seals and operating conditions. A method was developed to measure these gas losses from both the top and bottom rotary seals. In this report, the gas loss through the rotary seal has been added to the product gas quantities for Indirect Heated Mode data. The data does not account for the proportionately small loss in the Direct Heated Mode.

Bed height adjustment in the Semi-Works retort is made by the addition of extension skirts to the off-gas collectors. In the Pilot retort, an adjustment of the telescoping shale feed chute is used for this purpose. After leaving the retort, the recycle gas passes through the oil mist recovery equipment to the recycle gas blower. All major piping and vessels between the retort and suction of the recycle blower was insulated to prevent exposure to extreme weather conditions. A foam type insulation was used to prevent condensation of moisture thus reducing the moisture content of the product oil. A substantial decrease in water content of the product oil was shown following insulation of the pipes.

TABLE 5-1

The recycle blowers are multi-staged and capable of developing 150 inches of water discharge pressure. All blowers are generally operated below design capacity and often below their cyclic surge line. To prevent surging within the blower at low capacity, a bypass system is used to recycle a portion of the gas from the discharge back to the suction stage. Both Pilot and Semi-Works blowers are operated without their suction stage impellers to reduce excess pressure and compression temperature rise.

A liquid removal system is required on each blower stage to keep the blower free of collected water and oil. To alleviate this problem, a line skimmer removes the liquid flowing along the pipe surface immediately before its entry into the blower. Both the skimmer and the individual blower stage drains are then piped to the rundown tanks for measurement and sampling.

The Semi-Works recycle blower was dismantled for inspection only once during the program and accumulated sludge and polymerized oil were removed. This was done prior to Run SW-12.

The pressure requirements for the recycle system generally are small compared to the pressure available from the blower. The individual pressure drops under typical Direct or Indirect Heated operations on the Semi-Works retort are shown in the following table 5-1.

The recycle blowers are multi-staged and capable of developing 150 inches of water discharge pressure. All blowers are generally operated below design capacity and often below their cyclic surge line. To prevent surging within the blower at low capacity, a bypass system is used to recycle a portion of the gas from the discharge back to the suction stage. Both Pilot and Semi-Works blowers are operated without their suction stage impellers to reduce excess pressure and compression temperature rise. A liquid removal system is required on each blower stage to keep the blower free of collected water and oil. To alleviate this problem, a line skimmer removes the liquid flowing along the pipe surface immediately before its entry into the blower. Both the skimmer and the individual blower stage drains are then piped to the rundown tanks for measurement and sampling.

The Semi-Works recycle blower was dismantled for inspection only once during the program and accumulated sludges and polymerized oil were removed. This was done prior to Run SW-12.

The pressure requirements for the recycle system generally are small compared to the pressure available from the blower. The individual pressure drops under typical direct or indirect heated operations on the Semi-Works report are shown in the following table 5-1.

TABLE 5-1
PRESSURE DROP THROUGH THE RECYCLE GAS SYSTEM

	<u>Direct</u>	<u>Indirect</u>
	In. of H ₂ O	In. of H ₂ O
Retort Shale Bed	26"	26"
Top of Shale Bed to Recycle Blower Suction	1 to 2"	6 to 8"
Permanent Loss caused by Orifice Differential	2 to 12"	2 to 12"
Control Valve	Variable	Variable
Gas Heater	---	8"
Distributor Piping and Entry	2 to 10"	2 to 10"
TOTAL - Maximum Total Less Control Valve	50"	64"

The heating of recycle gas in the Indirect Heated Mode is achieved in the multi-tube, six pass, horizontal heaters for the Semi-Works retort. For the Pilot retort, a vertical single pass, alloy steel, finned - tube heater was used. Many problems occurred with their operation which greatly limited operational time in the Indirect Heated Mode for both retorts. The ability to maintain continuous heater operations for the Semi-Works Indirect Heated Mode was shown by the ability to operate without coke deposition in the heater, hot gas system, or on the inlet tube header. The ability to remove all of the oil mist was responsible for the clean inlet tube header and moisture control of the gas stream controlled the coke deposition.

The Pilot and Semi-Works external heaters were not the best design for this service. They were obtained

TABLE 2-1

PRESSURE DROP THROUGH THE RECYCLE GAS SYSTEM

Indirect	Direct
In. of H ₂ O	In. of H ₂ O
25"	25"
6 to 8"	1 to 2"
2 to 12"	2 to 12"
Variable	Variable
8"	---
2 to 10"	2 to 10"
64"	50"
	TOTAL - Maximum Total
	Less Control Valve
	Gas Heater
	Control Valve
	Permanent Loss caused by
	Recycle Blower Section
	Top of Shale Bed to
	Reactor Shale Bed

The heating of recycle gas in the Indirect Heated Mode is achieved in the multi-tube, six pass, horizontal heaters for the Semi-Works reactor. For the Pilot reactor, a vertical single pass, alloy steel, finned - tube heater was used. Many problems occurred with this operation which greatly limited operational time in the Indirect Heated Mode for both reactors. The ability to maintain continuous heater operations for the Semi-Works Indirect Heated Mode was shown by the ability to operate without coke deposition in the heater, hot gas system, or on the inlet tube header. The ability to remove all of the oil mist was responsible for the clean inlet tube header and moisture control of the gas stream controlled the coke deposition.

The Pilot and Semi-Works external heaters were not the best design for this service. They were obtained

as a compromise as heaters designed for this type of service could not be delivered in time for use in the program as scheduled. The Pilot Plant Indirect Heated Mode never reached an operable condition before failure of these heaters occurred. The Semi-Works heaters accounted for a major amount of lost time during these operations.

The maximum temperatures for processing were limited by the heater capability on both the Pilot and Semi-Works plants. The Pilot retort was not able to operate above 1300°F. The Semi-Works heaters achieved a 1300°F gas inlet temperature at the distributor and approximately 1400°F at the heater discharge. The Semi-Works heaters were limited by maximum firebox temperatures and recycle flue gas temperatures based on the manufacturer's recommendations.

Problems with the Semi-Works external heaters involved breaks in the tubes, tube sheets, and expansion bellows which allowed process gas to escape into the firebox section. Heater problems also limited the operations in the Indirect Heated Mode to a single heater operation. The proposed two level hot gas entry as performed for Direct Heated Mode operations was not achieved in the Indirect Heated Mode.

The Pilot Plant external heaters failed when the Inconel fins deteriorated and prevented gas flow through the heater. The fins appeared to have carbonized and melted during the operation.

as a compromise as heaters designed for this type of service could not be delivered in time for use in the program as scheduled. The Pilot Plant Indirect Heated Mode never reached an operable condition before failure of these heaters occurred. The Semi-Works heaters accounted for a major amount of lost time during these operations.

The maximum temperatures for processing were limited by the heater capability on both the Pilot and Semi-Works plants. The Pilot reactor was not able to operate above 1300°F. The Semi-Works heaters achieved a 1300°F gas inlet temperature at the distributor and approximately 1400°F at the heater discharge. The Semi-Works heaters were limited by maximum firebox temperatures and recycle line gas temperatures based on the manufacturer's recommendations.

Problems with the Semi-Works external heaters involved breaks in the tubes, tube sheets, and expansion bellows which allowed process gas to escape into the firebox section. Heater problems also limited the operations in the Indirect Heated Mode to a single heater operation. The proposed two level hot gas entry as performed for Direct Heated Mode operations was not achieved in the Indirect Heated Mode.

The Pilot Plant external heaters failed when the Inconel fins deteriorated and prevented gas flow through the heater. The fins appeared to have carbonized and melted during the operation.

Very few operational problems occurred with the air-gas distributors, except during periods of oil mist carry-over from the recovery system. During early Semi-Works runs, when some oil mist may have been recycled, a problem of coke buildup on the orifice openings restricted the gas flow. Later Semi-Works operations, such as the 25-day Direct Heated Mode demonstration run, showed no evidence of a distributor coking problem.

The process air supply for each retort is a multi-stage centrifugal blower similar to the recycle blower. The discharge of the Semi-Works air blower is partially vented to atmosphere to prevent pressure surging. To limit excessive capacity and prevent pressure surging, a restricting orifice is used on the suction of the Pilot Plant air blower. Both machines are equipped with dry suction filters to remove dust. There were no operational problems with either process air system.

Gas and air measurement is made using a sharp edge orifice plate meeting the design standards of the American Gas Association. Orifice plates cause a permanent pressure loss but are highly reliable, easy to maintain, and known to have an accuracy of $\pm 2\%$ when properly installed.

Gas and air flows are recorded continuously on miniature circular charts. The differential pressure leads are connected to manometers for better readability. Flow rates were calculated using the procedures in "Principles

Flow rates were calculated using the procedures in "Principles on miniature circular charts. The differential pressure leads are connected to manometers for better readability.

Gas and air flows are recorded continuously on miniature circular charts. The differential pressure leads are connected to manometers for better readability. and known to have an accuracy of $\pm 3\%$ when properly installed. pressure loss but are highly reliable, easy to maintain, American Gas Association. Orifice plates cause a permanent edge orifice plate meeting the design standards of the Gas and air measurement is made using a sharp

either process air system. There were no operational problems with to remove dust. Both machines are equipped with dry suction filters

blower. Both machines are equipped with dry suction filters orifice is used on the suction of the Pilot Plant air excessive capacity and prevent pressure surging, a restricting vented to atmosphere to prevent pressure surging. To limit The discharge of the Semi-Works air blower is partially stage centrifugal blower similar to the recycle blower.

The process air supply for each reactor is a multi-

a distributor coking problem.

Direct Heated Mode demonstration run, showed no evidence of

flow. Later Semi-Works operations, such as the 12-day

of coke buildup on the orifice openings restricted the gas

turns, when some oil mist may have been recycled, a problem

carry-over from the recovery system. During early Semi-Works

air-gas distributors, except during periods of oil mist

Very few operational problems occurred with the

and Practice of Flow Meter Engineering" by Spink (Foxboro Co.). The computer program listing is Table 7-1 in Section 7.1.

A low rate air purge is used through all gas differential pressure and static pressure lines to free them of oil. This air purge or bubbler increases the reliability of the measurements.

All gas and air orifice taps are equipped with line drains to remove trapped liquid. Periodic checking or draining of these drain lines is done during operations. The drain valves are maintained in a closed position except during periods of liquid drainage. All accumulated oil or water is then piped to the rundown tanks for inclusion in product oil for measurement.

Some locations of product gas loss have been previously described (top and bottom rotary seals); other minor losses were identified. These losses occurred sometimes at the blower seals, the hydraulic cylinder seal boxes, the distributor packing glands, during liquid drainage, and through other minor leaks within the system. In the Indirect Heated Mode, internal leakage into the heaters was known to be a major loss during some operations. The largest unmeasured gas loss was the recycle blower shaft seal. This was essentially corrected prior to Semi-Works Run No. SW-27 when an enclosure and a return line to the suction of the blower was installed. None of the minor gas losses have been measured or accounted for in the reported data except

and Practice of Flow Meter Engineering" by Spink (Foxboro Co.).
The computer program listing is Table 7-1 in Section 7.1.

A low rate air purge is used through all gas differential pressure and static pressure lines to free them of oil. This air purge or bubbler increases the reliability of the measurements.

All gas and air orifice taps are equipped with line drains to remove trapped liquid. Periodic checking or draining of these drain lines is done during operations. The drain valves are maintained in a closed position except during periods of liquid drainage. All accumulated oil or water is then piped to the known tanks for incineration in product oil for measurement.

Some locations of product gas loss have been previously described (top and bottom rotary seals; other minor losses were identified. These losses occurred sometimes at the blower seals, the hydraulic cylinder seal boxes, the distributor packing glands, during liquid drainage, and through other minor leaks within the system. In the indirect heated mode, internal leakage into the heaters was known to be a major loss during some operations. The largest unmeasured gas loss was the recycle blower shaft seal. This was essentially corrected prior to Semi-Works Run No. SW-17 when an enclosure and a return line to the suction of the blower was installed. None of the minor gas losses have been measured or accounted for in the reported data except

for heater gas loss when identified.

The pressure at the top of the retort is regulated by a pressure controller which positions the product gas control valve. This procedure provides very small pressure fluctuations. During Indirect Heated Mode operations, a line containing a small control valve was used because of the reduction in product gas quantity of approximately 10 to 1 compared to the Direct Heated Mode. Only during periods of extreme upset or excessive gas loss did problems occur in this control technique.

5.3.3 LIQUIDS

The oil mist particles produced in oil shale retorting processes are very small. Average particle diameter is only 3 microns. It is carried through the shale bed in the gas stream without appreciable impingement upon the shale particles. Because of the small particle size, specialized collection equipment is required. The equipment used for the collection of such minute particles in a gas stream should also meet many other requirements which are as follows:

1. The collection must be continuous.
2. The equipment must be capable of handling the liquid oil product.
3. The collector must have a very low pressure drop.
4. It must withstand the temperatures and physical and chemical conditions of the gas and oil.

for heater gas loss when identified.

The pressure at the top of the retort is regulated by a pressure controller which positions the product gas control valve. This procedure provides very small pressure fluctuations. During Indirect Heated Mode operations, a line containing a small control valve was used because of the reduction in product gas quantity of approximately 10 to 1 compared to the Direct Heated Mode. Only during periods of extreme upset or excessive gas loss did problems occur in this control technique.

2.1.3 LIQUIDS

The oil mist particles produced in oil shale retorting processes are very small. Average particle diameter is only 3 microns. It is carried through the shale bed in the gas stream without appreciable impingement upon the shale particles. Because of the small particle size, specialized collection equipment is required. The equipment used for the collection of such minute particles in a gas stream should also meet many other requirements which are as follows:

1. The collection must be continuous.
2. The equipment must be capable of handling the liquid oil product.
3. The collector must have a very low pressure drop.
4. It must withstand the temperatures and physical and chemical conditions of the gas and oil.

5. The collector should be inexpensive and easy to construct.
6. The collection efficiency should be high.
7. The unit should be self-cleaning and suited for long continuous service with a minimum of operator and maintenance attention.
8. It should have low power requirements.
9. The collector should minimize contamination or dilution of product oil.

Numerous collection devices have been tried during the experimental work on other similar retorting processes. Results of previous work showed the electrostatic precipitator to be the most suitable single piece of apparatus for this service.

The initial oil recovery system for the Paraho retort was made using an electrostatic precipitator as the single collection device. During the testing of the Indirect Heated Mode in the Pilot Plant Run PP-11 and the testing of high mass rates on the Semi-Works Runs SW-8 and 9, the ESP collection system efficiency decreased. Coalescers (Drawings 10 and 11) were designed and installed, to improve oil recovery. Their collection principle is to coalesce the oil mist particles with a cool oil spray system and then to remove the larger particles by impingement. By controlling the degree of cooling and the quantity of oil spray used, a control of gas temperature is also achieved. Mist removal in the coalescer is approximately 50% under most

5. The collector should be inexpensive and easy to construct.
 6. The collection efficiency should be high.
 7. The unit should be self-cleaning and suited for long continuous service with a minimum of operator and maintenance attention.
 8. It should have low power requirements.
 9. The collector should minimize contamination or dilution of product oil.
- Numerous collection devices have been tried during the experimental work on other similar retorting processes. Results of previous work showed the electrostatic precipitator to be the most suitable single piece of apparatus for this service.
- The initial oil recovery system for the Paraho retort was made using an electrostatic precipitator as the single collection device. During the testing of the Indirect Heated Mode in the Pilot Plant Run PP-11 and the testing of high mass rates on the Semi-Works Runs SW-8 and 9, the ESP collection system efficiency decreased. Coalescers (Drawings I and II) were designed and installed, to improve oil recovery. Their collection principle is to coalesce the oil mist particles with a cool oil spray system and then to remove the larger particles by impingement. By controlling the degree of cooling and the quantity of oil spray used, a control of gas temperature is also achieved. Mist removal in the coalescer is approximately 50% under most

operating conditions, thus lowering the input loading of the electrostatic precipitator by 50%. The system has minimal pressure drop. A correction in the gas entry to the Semi-Works electrostatic precipitator during the installation of the coalescer also helped overall recoveries.

The installation of the coalescer system also stabilized the electrostatic precipitator operation at all times on both the Pilot and Semi-Works retorts, resulting in fewer problems of mist recovery. The total system achieves the nine requirements previously listed, and in addition, provides a method of temperature control for the gas stream.

An additional change was made to the coalescer prior to the final Indirect Heated Mode operation on the Semi-Works retort starting with Semi-Works Run SW-21. The baffled section of the coalescer was converted to an oil-gas contactor using 2-inch Pall rings. This was done to provide better gas contact with cool oil. This addition was made within the gas passage area of the impingement section.

Experiences during the Indirect Heated Mode operations, show no increase in collection efficiency from the packing section addition. However, cooling of the gas stream was easily accomplished. Temperature control was always maintained. Periods of sediment carryover existed but no problem in plugging of the coalescer impingement or packing sections was noted. Additional pressure drop resulted.

operating conditions, thus lowering the input loading of the electrostatic precipitator by 50%. The system has minimal pressure drop. A correction in the gas entry to the Semi-Works electrostatic precipitator during the installation of the condenser also helped overall recoveries.

The installation of the condenser system also stabilized the electrostatic precipitator operation at all times on both the Pilot and Semi-Works reports, resulting in fewer problems of mist recovery. The total system achieves the nine requirements previously listed, and in addition, provides a method of temperature control for the gas stream.

An additional change was made to the condenser prior to the final Indirect Heated Mode operation on the Semi-Works report starting with Semi-Works Run SW-21. The baffled section of the condenser was converted to an oil-gas contactor using 3-inch Pall rings. This was done to provide better gas contact with cool oil. This addition was made within the gas passage area of the impingement section.

Experiences during the Indirect Heated Mode operations show no increase in collection efficiency from the packing section addition. However, cooling of the gas stream was easily accomplished. Temperature control was always maintained. Periods of sediment carryover existed but no problem in plugging of the condenser impingement or packing sections was noted. Additional pressure drop resulted.

3.3.4 The oil, after collection, is piped directly to rundown tanks for measurement and sampling. Initially the oil drained by gravity. The Pilot Plant operated satisfactorily with the gravity drain system. Minor problems occurred in some earlier runs in the Semi-Works retort with sludge blocking the drain lines in the gravity overflow system. During Run SW-12, a change in the system allowed the oil to discharge to tankage through a bleed line from the pump supplying spray oil. After the installation of the coalescer, sediment is removed with the coalescer oil, reducing problems in the electrostatic precipitator and recycle gas pipes.

All oil handling systems require heat tracing and insulation in order to maintain temperatures above the pour point of the oil. During shutdown conditions, this is also required to prevent freezing during cold weather.

The oil rundown and storage tanks systems are shown in Drawing 6. Steam-heated, insulated tanks are used. The only precautions taken to retain the volatile fractions within the oil is to maintain a minimum temperature on the oil during storage.

Both sediment and water separate readily in storage tanks. The water condensed in the bottom gas cooler used in the Indirect heated Mode operations is separately gaged and sampled.

The oil, after collection, is piped directly to rundown tanks for measurement and sampling. Initially the oil drained by gravity. The Pilot Plant operated satisfactorily with the gravity drain system. Minor problems occurred in some earlier runs in the Semi-Works resort with sludge blocking the drain lines in the gravity overflow system. During Run SW-12, a change in the system allowed the oil to discharge to tanks through a bleed line from the pump supplying spray oil. After the installation of the coalescer, sediment is removed with the coalescer oil, reducing problems in the electrostatic precipitator and recycle gas pipes.

All oil handling systems require heat tracing and insulation in order to maintain temperatures above the pour point of the oil. During shutdown conditions, this is also required to prevent freezing during cold weather. The oil rundown and storage tanks systems are shown in Drawing 6. Steam-heated, insulated tanks are used. The only precautions taken to retain the volatile fractions within the oil is to maintain a minimum temperature on the oil during storage.

Both sediment and water separate readily in storage tanks. The water condensed in the bottom gas cooler used in the indirect heated Mode operations is separately aged and sampled.

5.3.4 RETORT WEAR RATES

An inspection of the Pilot and Semi-Works retorts and associated equipment was made to determine the extent of wear during the operating period from mid - 1974 to April 1976. The following is an outline of the equipment examined and explanatory remarks.

Pilot and Semi-Works Retort

Solids

Raw Shale Screen Feeder

Raw Shale Weighbelt

Raw Shale Rotary Seals

Raw Shale Level Control

Raw Shale Distributor

Retort Lining

Discharge Mechanism

Moving mechanism including pusher,

spacer bars, clevis etc.

Fixed components including inverted V's,

retarder plates, etc.

Hydraulic cylinders

Hydraulic circuitry

Volume controls

Retorted Shale Discharge Cone

Retorted Shale Rotary Seals

Retorted Shale Weighbelt

An inspection of the Pilot and Semi-Works retorts and associated equipment was made to determine the extent of wear during the operating period from mid - 1974 to April 1975. The following is an outline of the equipment examined and explanatory remarks.

Pilot and Semi-Works Retort

Solids

Raw Shale Screen Feeder

Raw Shale Weighbelt

Raw Shale Rotary Seals

Raw Shale Level Control

Raw Shale Distributor

Retort Lining

Discharge Mechanism

Moving mechanism including pusher.

Spacer bars, clevis etc.

Fixed components including inverted V's.

Retarder plates, etc.

Hydraulic cylinders

Hydraulic circuitry

Volume controls

Retorted Shale Discharge Cone

Retorted Shale Rotary Seals

Retorted Shale Weighbelt

Gases

Off-gas Collectors (Semi-Works)

Top Distributors Made in the Semi-Works retort

Middle Distributors

Bottom Distributors

Instruments

Retort Thermocouples (can be dropped up to 3/4 inch)

Retort Pressure Taps ~~dogs required appreciable~~

SOLIDS

There has been no measurable wear to the shale handling equipment with minor exceptions as follows:

1. The screen on the Semi-Works screen feeder developed holes where the shale entered the screen from the surge bin. Both the Semi-Works and Pilot Plant screens developed fatigue cracks from vibrating motion. A plate was installed to relieve the wear on the screen inlet and the cracks were welded. A stronger screen is recommended.
2. The retorted shale weighbelt on the Semi-Works retort was unable to withstand the retorted shale discharge temperatures of the preliminary operations in the Indirect Heated Mode. Improved operating conditions and better thermal efficiency in later operations resulted in lower discharge temperatures of the retorted shale. The belt wear was reduced to minimal.

2. The retorted shale weighbelt on the Semi-Works retort was unable to withstand the retorted shale discharge temperatures of the preliminary operations in the Indirect Heated Mode. Improved operating conditions and better thermal efficiency in later operations resulted in lower discharge temperatures of the retorted shale. The belt wear was reduced to minimal.

In later operations resulted in lower discharge
 temperatures of the retorted shale. The belt
 wear was reduced to minimal.

Gas

Off-gas Collectors (Semi-Works)

Top Distributors

Middle Distributors

Bottom Distributors

Instruments

Retort Thermocouples

Retort Pressure Taps

SOLIDS

There has been no measurable wear to the shale handling equipment with minor exceptions as follows:

1. The screen on the Semi-Works screen feeder developed holes where the shale entered the screen from the surge bin. Both the Semi-Works and Pilot Plant screens developed fatigue cracks from vibrating motion. A plate was installed to relieve the wear on the screen inlet and the cracks were welded. A stronger screen is recommended.
2. The retorted shale weights on the Semi-Works retort was unable to withstand the retorted shale discharge temperatures of the preliminary operations in the Indirect Heated Mode. Improved operating conditions and better thermal efficiency in later operations resulted in lower discharge temperatures of the retorted shale. The belt wear was reduced to minimal.

3. The lining wear in both retorts was negligible and not detectable until after operation in the Indirect Heated Mode in the Semi-Works retort. In the area adjacent to the hot gas entry, the glaze from the bricks is gone and a rough, porous surface remains. Mortar between bricks in the same area has been eroded up to 3/4 inch.

4. The hydraulic cylinders required appreciable maintenance of rod seals in the early operating periods. An improved seal was used and an extension support was put on the cylinders and operating time extended before maintenance was required.

After cast iron ring seals were installed and alignment was checked, the cylinders did not require further maintenance.

5. The retorted shale rotary seals showed considerable wear in the initial units that were used. An improved design was developed by the manufacturer and the new seals were installed in August, 1975. Wear effect was decreased in all parts of the seals. The wear rate is shown in the following table:

TABLE 5-2
ROTARY SEAL WEAR RATES
Wear Rates, Inches

Date	Tonnage	End	Radial	Average Per 1000 Tons
Aug. 1975	0	0.017	0.017	---
Dec. 1975	5000	0.026	0.022	.0014
Apr. 1976	10000	0.040	0.044	.0036

3. The lining wear in both rotors was negligible and not detectable until after operation in the Indirect Beated Mode in the Semi-Works rotor. In the area adjacent to the hot gas entry, the glass from the bricks is gone and a rough, porous surface remains. Mortar between bricks in the same area has been eroded up to $3/4$ inch. The hydraulic cylinders required appreciable maintenance of rod seals in the early operating periods. An improved seal was used and an extension support was put on the cylinders and operating time extended before maintenance was required. After cast iron ring seals were installed and alignment was checked, the cylinders did not require further maintenance. 5. The retorted shale rotary seals showed considerable wear in the initial units that were used. An improved design was developed by the manufacturer and the new seals were installed in August, 1975. Wear effect was decreased in all parts of the seals. The wear rate is shown in the following table:

TABLE 5-2
ROTARY SEAL WEAR RATES
Wear Rates, Inches

Date	Tonnage	End	Radial	Average Per 1000 Tons
Aug. 1975	0	0.017	0.017	---
Dec. 1975	5000	0.036	0.032	.0014
Apr. 1976	10000	0.040	0.044	.0036

Gases

The service of the distributors has been good. The only exception to good performance has been some cracking of the welds along the top distributor between the water jacket and the stainless steel distributor pipe. There is no evidence to indicate the cracking occurred from other than fabrication defects in the shop welding.

Instruments

The retort thermocouple-pressure probe gave very rapid response to variations in retort operation but structurally needs improvement as several of the extended couples broke off. The pressure taps located in the retorting zone also would become plugged. The main pipe of the probe showed no unusual wear.

Gases

The service of the distributors has been good. The only exception to good performance has been some cracking of the welds along the top distributor between the water jacket and the stainless steel distributor pipe. There is no evidence to indicate the cracking occurred from other than fabrication defects in the shop welding.

Instrumentation

The retort thermocouple-pressure probe gave very rapid response to variations in retort operation but structurally needs improvement as several of the extended couples broke off. The pressure taps located in the retorting zone also would become plugged. The main pipe of the probe showed no unusual wear.

5.4 AUXILIARY SYSTEMS

The cooling water, fuel oil, plant air, propane and shale oil storage facilities are shown on Drawing 6. The steam, dust collection and thermal oxidizer systems are shown on Drawing 7. Except for the crude shale oil gaging tanks and dust collectors, the systems serve both the Pilot and Semi-Works Plants.

The cooling water system consists of a primary receiver and make-up tank, the interconnecting piping, the necessary temperature and regulating controls, the circulating pumps and the air-cooled heat exchanger. The usage of cooling water is:

Direct Mode Operation

Spray Oil Cooler (SW & PP)

Air-Gas Distributors (SW&PP)

Indirect Mode Operations

Bottom Gas Cooler (SW)

Wash Oil Cooler (SW)

Spray Oil Cooler (SW & PP)

The fuel oil is stored in four 500-barrel tanks and the fuel oil pumps circulate the oil through the plant area and back to the tanks. Fuel oil is used for:

Process Steam Boilers

Semi-Works Plant Heater

Plant Heating Steam Boiler

Thermal Oxidizer

5.4 AUXILIARY SYSTEMS

The cooling water, fuel oil, plant air, propane and shale oil storage facilities are shown on Drawing 6. The steam, dust collection and chemical oxidizer systems are shown on Drawing 7. Except for the crude shale oil piping tanks and dust collectors, the systems serve both the Pilot and Semi-Works Plants.

The cooling water system consists of a primary receiver and make-up tank, the interconnecting piping, the necessary temperature and regulating controls, the circulating pumps and the air-cooled heat exchanger. The usage of cooling water is:

<u>Indirect Mode Operations</u>	<u>Direct Mode Operation</u>
Spray Oil Cooler (SW & PP)	Spray Oil Cooler (SW & PP)
Wash Oil Cooler (SW)	Air-Gas Distributors (SW&PP)
Bottom Gas Cooler (SW)	

The fuel oil is stored in four 500-barrel tanks and the fuel oil pumps circulate the oil through the plant area and back to the tanks. Fuel oil is used for:

- Process Steam Boilers
- Semi-Works Plant Heater
- Plant Heating Steam Boiler
- Thermal Oxidizer

The plant air system utilizes a new compressor and two old compressors that were located in the old boiler house. The new compressor provides instrument and plant air to the control room for distribution. The two old compressors supply air to the bag filters that are air pulsation type. The two systems are valved and piped to spare each other primarily to insure the availability of air for the instruments.

There is no natural gas available at the Anvil Points site and therefore propane is used. The propane system consists of two 1200-gallon tanks, piping and instrumentation. To insure vapor phase propane in the cold winter months for start-up purposes, an additional 500-gallon tank and vaporizer are located in the retort area. Propane is supplied to:

Pilot Plant

- Direct Heated Mode Start-up

- Heater Burners

- Heater Pilots

Semi-Works Plant

- Direct Heated Mode Start-up

- Heater Pilots

- Thermal Oxidizer Pilots

- Laboratory

The plant air system utilizes a new compressor and two old compressors that were located in the old boiler house. The new compressor provides instrument and plant air to the control room for distribution. The two old compressors supply air to the bag filters that are air pulsation type. The two systems are valved and piped to spare each other primarily to insure the availability of air for the instruments.

There is no natural gas available at the Anvil Points site and therefore propane is used. The propane system consists of two 1200-gallon tanks, piping and instrumentation. To insure vapor phase propane in the cold winter months for start-up purposes, an additional 500-gallon tank and vaporizer are located in the retort area. Propane is supplied for:

- Pilot Plant
- Direct Heated Mode Start-up
- Heater Burners
- Heater Pilots
- Semi-Works Plant
- Direct Heated Mode Start-up
- Heater Pilots
- Thermal Oxidizer Pilots
- Laboratory

The tankage for shale oil storage at Anvil Points has a capacity of about 20,000 barrels. However, only about 17,000 barrels can be stored in usable tanks. Drawing 6 for shale oil storage primarily shows the rundown and gaging tanks. The Pilot Plant uses tanks 525 and 526. The Semi-Works Plant uses tanks 519 through 524. All of these tanks are steam-heated and insulated. The system has the capability of circulating the oil from a tank, through a pump while the tank is being agitated prior to the oil sample being taken.

The plant steam is produced by two package boilers. This system is tied to the plant steam heating system as a spare supply in case of failure. The plant steam is used for:

- Thermal Oxidizer Burner Fuel Atomization

- Propane Vaporization

- Crude Shale Oil Tank Heating

- Rotary Seal Purge Gas

- Crude Shale Oil Line Tracing

- Control Room Heating

- Shale Preparation Building Heating

Dust collection equipment was used to comply with regulations for particulate emissions. The State of Colorado Health Department in cooperation with the Mining Enforcement and Safety Administration (MESA) and the Colorado Bureau of Mines (CBOM) were the regulatory agencies for Anvil Points.

The tankage for shale oil storage at Anvil Pointe has a capacity of about 50,000 barrels. However, only about 17,000 barrels can be stored in usable tanks. Drawing 6 for shale oil storage primarily shows the rundown and paying tanks. The Pilot Plant uses tanks 525 and 526. The Semi-works Plant uses tanks 519 through 524. All of these tanks are steam-heated and insulated. The system has the capability of circulating the oil from a tank, through a pump while the tank is being agitated prior to the oil sample being taken.

The plant steam is produced by two package boilers. This system is tied to the plant steam heating system as a spare supply in case of failure. The plant steam is used for:

- Thermal Oxidizer Burner Fuel Atomization
- Propane Vaporization
- Crude Shale Oil Tank Heating
- Rotary Seal Purge Gas
- Crude Shale Oil Line Tracing
- Control Room Heating
- Shale Preparation Building Heating

Dust collection equipment was used to comply with regulations for particulate emissions. The State of Colorado Health Department in cooperation with the Mining Enforcement and Safety Administration (MESA) and the Colorado Bureau of Mines (CBOM) were the regulatory agencies for Anvil Pointe.

The necessary permits were received to construct and a final inspection by the Air Pollution Control Division, while the shale preparation areas and both Pilot and Semi-Works Plants were operating, resulted in a permanent permit to operate. The Paraho Project was not cited for a violation during the program.

The dust collectors are bag filter type. The particulate material from the retort plant collectors is transported to the retorted shale area. The particulates from the shale preparation areas are transported to the same canyon but separate from the retorted shale.

Since there was no effective way to utilize the product gas, the thermal oxidizer is used to burn the product gas from the Pilot and Semi-Works Direct and Indirect Heated Mode operations before emission to the atmosphere. A checkerbrick system was installed in the burner discharge area of the combustion chamber to improve the overall efficiency of combustion. Because of the smaller quantities of product gas to be burned from the Pilot retort, fuel oil is used as an auxiliary fuel. During stable periods of the Semi-Works retort operations, the low BTU gas from the Direct Heated Mode and the high BTU gas from the Indirect Heated Mode do not require auxiliary fuel oil to maintain combustion and complete oxidation takes place before emission. The pilot is maintained for safety purposes.

WESTON BOND

FLUORESCENT

52% COTTON FIBER

6. STARTUP PROCEDURES

6.1 DIRECT HEATED MODE STARTUP PROCEDURES

Many startup procedures have been previously used for vertical kiln gravity flow retorts, but all have presented problems or were not adaptable to larger size units. The development of a new procedure, based on a concept that could be adapted to commercial size retorts, was initiated at the beginning of Paraho operations. Success was achieved on Pilot Plant Run PP-1 and refinements continued through most of the Direct Heated Mode operation on both retorts.

This startup procedure is based on the principle of a controlled combustion of gaseous fuel within the bed to preheat the shale particles to ignition temperature. Propane has been used as the fuel for the ignition step. When proper operating temperatures are achieved within the bed, the propane fuel is removed and normal process flows established.

Minor variations to the original Pilot Plant procedures were required for the Semi-Works retort to prevent the combustion of product gases above the open bed. Changing the air gas ratios during the propane firing controlled this and led to the use of a full shale bed for the startup. This provides some preheating of the shale in the upper sections of the bed above the combustion zone making it less susceptible to process upsets during the

6. STARTUP PROCEDURES

6.1 DIRECT HEATED MODE STARTUP PROCEDURES

Many startup procedures have been previously used for vertical kiln gravity flow reactors, but all have presented problems or were not adaptable to larger size units. The development of a new procedure, based on a concept that could be adapted to commercial size reactors, was initiated at the beginning of Tarocho operations. Success was achieved on Pilot Plant Run PP-1 and refinements continued through most of the Direct Heated Mode operation on both reactors. This startup procedure is based on the principle of a controlled combustion of gaseous fuel within the bed to preheat the shale particles to ignition temperature. Propane has been used as the fuel for the ignition step. When proper operating temperatures are achieved within the bed, the propane fuel is removed and normal process flows established.

Minor variations to the original Pilot Plant procedures were required for the Semi-Works reactor to prevent the combustion of product gases above the open bed. Changing the air gas ratios during the propane firing controlled this and led to the use of a full shale bed for the startup. This provides some preheating of the shale in the upper sections of the bed above the combustion zone making it less susceptible to process upsets during the

early stages. The direct combustion within the bed provides a rapid startup reaching shale combustion temperatures within 18 minutes of the propane ignition.

This startup procedure was primarily developed in the Pilot Plant but the technique has proven safe and reliable for both retorts and can easily be adapted to commercial size. The startup is rapid, reaching normal operating conditions within nine hours. A minimum of specialty equipment is required such as a gaseous fuel source and control system and an air-fuel mixer in the top distributor air supply line. Final refinement includes a method of exhausting all products of combustion during the propane firing through the product gas thermal oxidizer. This technique provides pollution control throughout the operation.

A quick opening valve is required for the gaseous fuel supply. Flow rates must be achieved as rapidly as possible to prevent the dangers of explosive mixtures of air and gas being used. Individual flow rates are pre-set followed by purging, and then the ignition sequence is started. A safety shut off is also incorporated in this valve to provide a shutdown of the system in case of an air blower or power failure. The details of this installation are shown in Drawings 3 and 4.

The startup procedure begins with a full bed of raw shale. A non-compacted bed is assured by operating the grate and completely circulating shale through the retort

early stages. The direct combustion within the bed provides a rapid starting reaching shale combustion temperatures within 18 minutes of the propane ignition.

This startup procedure was primarily developed in the Pilot Plant but the technique has proven safe and reliable for both retorts and can easily be adapted to commercial size. The startup is rapid, reaching normal operating conditions within nine hours. A minimum of specialty equipment is required such as a gaseous fuel source and control system and an air-fuel mixer in the top distributor air supply line. Final refinement includes a method of exhausting all products of combustion during the propane firing through the product gas thermal oxidizer. This technique provides pollution control throughout the operation.

A quick opening valve is required for the gaseous fuel supply. Flow rates must be achieved as rapidly as possible to prevent the dangers of explosive mixtures of air and gas being used. Individual flow rates are pre-set followed by purging, and then the ignition sequence is started. A safety shut off is also incorporated in this valve to provide a shutdown of the system in case of an air blower or power failure. The details of this installation are shown in Drawings 3 and 4.

The startup procedure begins with a full bed of raw shale. A non-compacted bed is assured by operating the grate and completely circulating shale through the retort

while maintaining a level in the retort level hopper. One complete change of shale eliminates compaction due to the initial filling of the retort. No other special shale preparation or other materials are required. Flow rates are set to provide a rich mixture of propane in air at the top distributor with the additional air requirements for combustion being added at the mid distributor. To ignite the fuel mixture, igniters are inserted into the bed through special openings. Signal flares have proven to be well suited for this purpose as they can be dropped on the surface of the bed and buried in the shale by starting shale flow through the retort.

After the igniters have been inserted, propane is added to the air, supplying a combustible mixture that will burn within the shale bed when upward gas velocity is less than the flame velocity. Using a series of air and gas changes, the internal combustion can be controlled to preheat the shale bed and bring the shale to ignition temperatures at the normal combustion zone level.

As the shale reaches retorting and combustion temperatures, the propane supply is cut off and the recycle system started. A gradual buildup of air and gas additions is used to spread the combustion zone across the complete retort cross-section. This is a step-wise procedure. As the temperature profiles are established, both vertically and horizontally, the shale rate is increased until full

while maintaining a level in the retort level hopper. One complete change of shale eliminates compaction due to the initial filling of the retort. No other special shale preparation or other materials are required. Flow rates are set to provide a rich mixture of propane in air at the top distributor with the additional air requirements for combustion being added at the mid distributor. To ignite the fuel mixture, igniters are inserted into the bed through special openings. Signal flares have proven to be well suited for this purpose as they can be dropped on the surface of the bed and buried in the shale by starting shale flow through the retort.

After the igniters have been inserted, propane is added to the air, supplying a combustible mixture that will burn within the shale bed when upward gas velocity is less than the flame velocity. Using a series of air and gas changes, the internal combustion can be controlled to preheat the shale bed and bring the shale to ignition temperatures at the normal combustion zone level.

As the shale reaches retorting and combustion temperatures, the propane supply is cut off and the recycle system started. A gradual buildup of air and gas additions is used to spread the combustion zone across the complete retort cross-section. This is a step-wise procedure. As the temperature profiles are established, both vertically and horizontally, the shale rate is increased until full

operating conditions are achieved.

PROCEDURE

The startup time sequence can be varied greatly following the propane ignition since the process is operable over wide variations of air, gas, and shale rates. The period from propane ignition to normal operating conditions, using two level air input at 400 lbs/hr/ft² has been achieved in nine hours.

The procedure developed uses an initial retort loading of an inert material such as crushed and screened limestone or gravel. The system is then purged of oxygen using an inert gas.

Direct heated mode product gas from the Pilot Plant was used for purging because of its availability during this program. Gas circulation is started to purge the retort. The recirculation piping and oil recovery equipment. The heaters and oil recovery equipment are started when the oxygen content of the circulating gas stream drops below 2%. A continuous purge of inert gas is maintained to prevent air in-leakage during the preheating periods.

Low velocity stone movement is maintained during the retort preheating operation to establish the vertical temperature profile in both the top and lower section of the retort. This movement also prevents thermal expansion from locking the stone particles within the bed. During the preheating period, the stone rate is adjusted to maintain a desired off-gas temperature.

6.2 INDIRECT HEATED MODE STARTUP PROCEDURE

A reliable startup procedure for the Indirect Heated Mode was achieved using a technique of preheating the retort filled with a non-kerogen bearing rock. This provides a method of establishing a vertical temperature profile before feeding shale to the retort. This procedure enhances the mist formation in the preheating zone. The procedure developed uses an initial retort loading of an inert material such as crushed and screened limestone or gravel. The system is then purged of oxygen using an inert gas.

Direct Heated Mode product gas from the Pilot Plant was used for purging because of its availability during this program. Gas circulation is started to purge the retort, the recirculation piping and oil recovery equipment. The heaters and oil recovery equipment are started when the oxygen content of the circulating gas stream drops below 2%. A continuous purge of inert gas is maintained to prevent air in-leakage during the preheating periods.

Low velocity stone movement is maintained during the retort preheating operation to establish the vertical temperature profile in both the top and lower section of the retort. This movement also prevents thermal expansion from locking the stone particles within the bed. During the preheating period, the stone rate is adjusted to maintain a desired off-gas temperature.

6.2 INDIRECT HEATED MODE STARTUP PROCEDURE

A reliable startup procedure for the Indirect Heated Mode was achieved using a technique of preheating the retort filled with a non-kerogen bearing rock. This provides a method of establishing a vertical temperature profile before feeding ash to the retort. This procedure enhances the mist formation in the preheating zone. The procedure developed uses an initial retort loading of an inert material such as crushed and screened limestone or gravel. The system is then purged of oxygen using an inert gas.

Direct Heated Mode product gas from the Pilot Plant was used for purging because of its availability during this program. Gas circulation is started to purge the retort, the recirculation piping and oil recovery equipment. The heaters and oil recovery equipment are started when the oxygen content of the circulating gas stream drops below 2%. A continuous purge of inert gas is maintained to prevent air in-leakage during the preheating periods.

Low velocity stone movement is maintained during the retort preheating operation to establish the vertical temperature profile in both the top and lower section of the retort. This movement also prevents thermal expansion from locking the stone particles within the bed. During the preheating period, the stone rate is adjusted to maintain a desired off-gas temperature.

A slow rate of gas temperature increase through the heater must be maintained to prevent thermal distortion. The temperature level is raised within the bed of inert stone until sufficient temperature is achieved to provide retorting. When this temperature level is reached, the inert rock feed is replaced with raw shale. Gas flows and temperatures are adjusted as required to bring the shale feed changeover into normal operating conditions as smoothly and quickly as possible.

Purging with inert gas is continued until adequate product gas is being produced from the retorting of shale to maintain adequate pressure control. The startup provides a rapid method of achieving a normal Indirect Heated Mode operation with a minimum of process upset. The oil recovery equipment is fully commissioned, thus providing a clean gas to the heater throughout the startup. Full operating conditions can be achieved in about 12 hours.

LETTER BOX

THE LETTER BOX IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

IT IS A PLACE WHERE YOU CAN
WRITE A LETTER TO ANYONE YOU WANT TO
CONTACT.

7 COMPUTER DATA PROCESSING

7.1 INTRODUCTION

The computing equipment used was a Hewlett-Packard 9830A general purpose programmable calculator. The program language is called BASIC. Input is by typewriter keyboard and output by the 9866A line printer. There is a built-in tape drive for large capacity storage. The read/write memory size is 3808 16-bit words.

Programs are written and edited at the keyboard and are stored on tape cassettes. Data is stored in test data files on tape cassettes and called from the keyboard.

Manufacturer's software tapes were used for polynomial regression and analysis of variance.

NOTES APPLICABLE TO DIRECT AND INDIRECT MOSE MATERIAL AND HEAT BALANCES

Data input are of two different types. The first is raw data either recorded at the unit (e.g. off gas temperature), or determined at the laboratory. The other is calculated from other peripheral computer programs, (e.g. gas flows from manometer readings).

WATER BALANCE

A. Laboratory tests of raw shale are performed and

*Gas Engineering Handbook, American Gas Assoc., Inc.

2.1 INTRODUCTION

The computing equipment used was a Hewlett-Packard 8810A general purpose programmable calculator. The program language is called BASIC. Input is by typewriter keyboard and output by the 886A line printer. There is a built-in tape drive for large capacity storage. The read/write memory size is 1808 16-bit words.

Programs are written and edited at the keyboard and are stored on tape cassettes. Data is stored in test data files on tape cassettes and called from the keyboard.

Manufacturers' software tapes were used for polynomial

regression and analysis of variance.

PROGRAMS USED FOR GAS CALCULATIONS

A gas calculation program was written to calculate specific gravity, molecular weight, and gross and net heating value* based on the composition of the retort gas. The specific gravity determined in this program is then input to the flow calculations program along with orifice differential pressure and flowing temperature and pressure to calculate bottom, mid, top, and product gas flow rates (SCFM). The air flows, (Bottom, mid, and top), are also calculated. These values along with other input data are stored on computer data tapes. This information can then be loaded into common memory and run through the material and heat balance programs.

The reference for the flow calculation program is "Principles and Practice of Flow Meter Engineering by L. K. Spink (1967) Foxboro." Table 7-1 is a program listing.

NOTES APPLICABLE TO DIRECT AND INDIRECT MODE MATERIAL AND HEAT BALANCES

Data input are of two different types. The first is raw data either recorded at the unit (e.g. off gas temperature), or determined at the laboratory. The other is calculated from other peripheral computer programs, (e.g. gas flows from manometer readings).

WATER BALANCE

A. Laboratory tests of raw shale are performed and

*Gas Engineering Handbook, American Gas Assoc., Inc.

PROGRAMS USED FOR GAS CALCULATIONS

A gas calculation program was written to calculate specific gravity, molecular weight, and gross and net heating values based on the composition of the reform gas. The specific gravity determined in this program is then input to the flow calculations program along with orifice differential pressure and flowing temperature and pressure to calculate bottom, mid, top, and product gas flow rates (SCFM). The air flows, (bottom, mid, and top), are also calculated. These values along with other input data are stored on computer data tapes. This information can then be loaded into common memory and run through the material and heat balance programs.

The reference for the flow calculation program is "Principles and Practice of Flow Meter Engineering" by L. E. Spink (1967) Foxboro. Table 7-1 is a program listing.

NOTES APPLICABLE TO DIRECT AND INDIRECT FLOW MATERIAL AND HEAT BALANCES

Data input are of two different types. The first is raw data either recorded at the unit (e.g. off gas temperature), or determined at the laboratory. The other is calculated from other peripheral computer programs, (e.g. gas flows from manometer readings).

WATER BALANCE

A. Laboratory tests of raw shale are performed and *Gas Engineering Handbook, American Gas Assoc., Inc.

reported on an undried basis. The program input data then is internally adjusted using a moisture determination on an undried sample. In the Indirect Heated Mode water balance, the laboratory moisture is subtracted from F.A. water to obtain the "true" F.A. water. This was not done in the Direct Heated Mode water balance.

- B. It is assumed that the retorted shale is totally water-free. This was confirmed by several specially handled retorted shale samples.
- C. Water balances will reflect the continued improvement in accounting for water contents throughout the program. Major problems were associated with the sampling and analysis of raw shale feed and product gas and the accounting for miscellaneous condensate drainage.

ORGANIC NITROGEN

Analysis techniques for ammonia content in the product gas streams and condensed water were only developed during the final Direct Heated Mode runs. An accounting for this component was therefore not included in the Direct Heated Mode computer program, which results in an incomplete organic nitrogen balance.

The Indirect Heated Mode computer program does account for the ammonia contents and a complete organic nitrogen balance is therefore obtained.

10/10/68

reported on an undried basis. The program input data then is internally adjusted using a moisture determination on an undried sample. In the Indirect Heated Mode water balance, the laboratory moisture is subtracted from F.A. water to obtain the "true" F.A. water. This was not done in the Direct Heated Mode water balance.

B. It is assumed that the reported shale is totally water-free. This was confirmed by several specially handled reported shale samples.

C. Water balances will reflect the continued improvement in accounting for water contents throughout the program. Major problems were associated with the sampling and analysis of raw shale feed and product gas and the accounting for miscellaneous condensate drainage.

ORGANIC NITROGEN

Analysis techniques for ammonia content in the product gas streams and condensed water were only developed during the final Direct Heated Mode runs. An accounting for this component was therefore not included in the Direct Heated Mode computer program, which results in an incomplete organic nitrogen balance.

The Indirect Heated Mode computer program does account for the ammonia contents and a complete organic nitrogen balance is therefore obtained.

CARBONATE DECOMPOSITION (BTU/T)

Partitioning of mineral carbon dioxide is based on information from USBM Bulletin 635. Dolomite content was reported as 30% of mineral carbonate. If carbonate decomposition, measured as Lb-mol CO_2 /ton, is less than or equal to 2.5, this value is multiplied by 58,835 BTU/# mol as the heat of decomposition of MgCO_3 . The program treats carbonate decomposition in excess of 2.5 #/mol CO_2 /ton as liberated from the decomposition of CaCO_3 , whose heat of decomposition is 75,096 BTU/lb.-mol.

SHALE MOISTURE QUANTITIES

- A. The Tylab moisture is the wt% H_2O on the uncrushed shale.
- B. The lab moisture is the wt% H_2O on the crushed lab sample.

HEAT OF PYROLYSIS

The heat of pyrolysis used is 32 BTU/# for 30 GPT shale. In the work reported in U.S.B.M. RI-7482, "Heat Contents of Some Green River Oil Shales," endothermic reactions at retorting temperatures of 17 BTU/# for 15 gal/ton shale and 35 BTU/# for 32.4 gal/ton shale were reported.

SKIN HEAT LOSSES

The heat loss from the retort shell was measured under various ambient and operating conditions and compared

CARBONATE DECOMPOSITION (BTU/T)

Partitioning of mineral carbon dioxide is based on information from USNM Bulletin 632. Dolomite content was reported as 30% of mineral carbonate. If carbonate decomposition measured as lb-mol CO₂/ton, is less than or equal to 2.5, this value is multiplied by 28,832 BTU/lb-mol as the heat of decomposition of MgCO₃. The program treats carbonate decomposition in excess of 2.5 lb-mol CO₂/ton as liberated from the decomposition of CaCO₃, whose heat of decomposition is 75,096 BTU/lb-mol.

SHALE MOISTURE QUANTITIES

- A. The Tylah moisture is the wt % H₂O on the uncrushed shale.
- B. The lab moisture is the wt % H₂O on the crushed lab sample.

HEAT OF PYROLYSIS

The heat of pyrolysis used is 32 BTU/lb for 30 CPT shale. In the work reported in U.S.B.M. RI-7482, "Heat Contents of Some Green River Oil Shales," endothermic reactions at retorting temperatures of 17 BTU/lb for 15 gal/ton shale and 32 BTU/lb for 32.4 gal/ton shale were reported.

SKIN HEAT LOSSES

The heat loss from the retort shell was measured under various ambient and operating conditions and compared

to calculated values. From these losses, based on average operating and ambient conditions, a constant heat loss value of 10,000 BTU/T or about 2% of the heat input, was used throughout the heat balance calculations.

GAS ENTHALPY

The gas component enthalpies used in the heat balance were obtained from the "Circular of the National Bureau of Standards C461," as part of the work of the American Petroleum Institute Research Project 44. Polynomial regression was used to convert the tabular data to equation form.

7.2 DIRECT HEATED MODE

A flow chart of the Direct Heated Mode material balance is presented in Figure 7-1. The program listing for Part 1 is Table 7-2 and for Part 2 is Table 7-3.

MATERIAL BALANCES - Part 1, Preliminary Calculations

The input data from the data tape is converted by preliminary calculations in Part 1 and stored in a Calculated Data Array shown in Table 7-4. Some of these calculations are explained in Table 7-5.

The combustion reactions considered are formation of CO₂, CO, and water vapor. From a material balance of the Fischer Assay, the production of CO₂ and CO by pyrolysis is calculated. Mineral carbon dioxide is also calculated. Thus, net carbon oxides from combustion are determined. The oxygen

to calculated values. From these losses, based on average operating and ambient conditions, a constant heat loss value of 10,000 BTU/T or about 2% of the heat input, was used throughout the heat balance calculations.

GAS ENTHALPY

The gas component enthalpies used in the heat balance were obtained from the "Circular of the National Bureau of Standards 4461," as part of the work of the American Petroleum Institute Research Project 44. Polynomial regression was used to convert the tabular data to equation form.

7.1 DIRECT HEATED MODE

A flow chart of the Direct Heated Mode material balance is presented in Figure 7-1. The program listing for Part 1 is Table 7-2 and for Part 2 is Table 7-3.

MATERIAL BALANCES - Part 1, Preliminary Calculations

The input data from the data tape is converted by preliminary calculations in Part 1 and stored in a Calculated Data Array shown in Table 7-4. Some of these calculations are explained in Table 7-5.

The combustion reactions considered are formation of CO_2 , CO , and water vapor. From a material balance of the Fischer Assay, the production of CO_2 and CO by pyrolysis is calculated. Mineral carbon dioxide is also calculated. Thus, net carbon oxides from combustion are determined. The oxygen

input with air is calculated and the oxygen by difference is used to calculate the combustion water formed.

MATERIAL BALANCES - Part 2

The partial balances and the overall weight balance are discussed in Table 7-6. Execution of this Part 2 prints the complete material balance which excludes recycle gas streams.

HEAT BALANCE

The flow chart of the heat balance for the Direct Heated Mode is presented as Figure 7-3. The program listing in Table 7-7. The program uses preliminary calculations performed in the material balance and stored in the calculated data array.

The steps of the calculation are shown in Table 7-8. The bases of calculations are believed to be self-explanatory along with the preceding text captioned, "Notes Applicable to Direct and Indirect Mode Material and Heat Balances" in Section 7.1.

Figure 7-2 shows the heat balance boundary and identifies the streams tabulated in the print out. Table 7-9 is a print out of input data, the material balance, and the heat balance for Direct Heated Mode Run SW-20, combined Test "A".

input with air is calculated and the oxygen by difference is used to calculate the combustion water formed.

MATERIAL BALANCES - Part 2

The partial balances and the overall weight balance are discussed in Table 7-6. Execution of this Part 2 prints the complete material balance which excludes recycle gas streams.

HEAT BALANCE


The flow chart of the heat balance for the Direct Heated Mode is presented as Figure 7-1. The program listing in Table 7-7. The program uses preliminary calculations performed in the material balance and stored in the calculated data array.

The steps of the calculation are shown in Table 7-8. The bases of calculations are believed to be self-explanatory along with the preceding text captioned, "Notes Applicable to Direct and Indirect Mode Material and Heat Balances" in Section 7.1.


Figure 7-2 shows the heat balance boundary and identifies the streams tabulated in the print out. Table 7-9 is a print out of input data, the material balance, and the heat balance for Direct Heated Mode Run SW-20, combined Test "A".

DIRECT HEATED MATERIAL BALANCE COMPUTER FLOW CHART

Figure 7-1




S = "IN SHALE"
O = "IN OIL"
G = "IN GAS"
C = "FROM COMBUSTION"
T = "TOTAL"



PARAHO DIRECT HEATED RETORT

COMPUTER BALANCES

FIGURE 7.2



GAS FLOW CALCULATION PROGRAM

TABLE 7-1

```
10 REM PROGRAM TO CALCULATE GAS FLOWS WHEN GIVEN THE LINE SIZE, ORIF. D.
20 FIXED 3
30 PRINT "SAME T,P,&SG?"
40 INPUT K9
50 R=2=0
60 PRINT "PIPE I.D."
70 PRINT "ORIFICE DIAMETER"
80 INPUT D,D2
90 B=D2/D
100 PRINT "PIPE I.D.=";D;"ORIFICE DIA.=";D2
110 PRINT
120 K1=0.5993+(0.007/D)+((0.364+(0.076/SQRD))*B+4)
130 K2=0.07+(0.5/D)-3
140 IF K2 <= 0 THEN 230
150 K3=(K2+2.5)*(0.4*(1.6-(1/D))+5)
160 K4=0.5-B
170 IF K4 <= 0 THEN 250
180 K5=-((0.009+(0.034/D))*(K4+1.5))
190 K6=B-0.7
200 IF K6 <= 0 THEN 270
210 K7=(65/(D+2)+3)*(K6+2.5)
220 GOTO 280
230 K3=0
240 GOTO 160
250 K5=0
260 GOTO 190
270 K7=0
280 N=K1+K3+K5+K7
290 K0=N/(1+0.000015*(830-5000*B+9000*B+2-4200*(B+3)+(530/SQRD)))
300 PRINT "TYPE OF MATERIAL?0=AIR,1=GAS,2=PROPANE"
310 PRINT
320 INPUT X
330 F=5.6328*K0*(B*D)+2
340 IF X=0 THEN 370
350 IF X=1 THEN 400
360 IF X=2 THEN 430
370 F1=0.06196
380 F2=1.4
390 GOTO 450
400 F1=0.05592
410 F2=1.35
420 GOTO 450
430 F1=0.02513
440 F2=1.17
450 C1=F1*(830-5000*B+9000*B+2-4200*B+3+530/SQRD)/12835*K0
460 C2=(0.41+0.35*B+4)/(27.7*F2)
470 IF K9=1 THEN 510
480 PRINT "INPUT DEG F,P IN.HG. RES.,SP.GR.,H2O DIFF"
490 PRINT
500 INPUT T,P1,G,H
510 PRINT "INPUT H"
520 INPUT H
530 H=H*1.07
```


TABLE 7-1 (Contd)

```

540 R=T
550 Z=P1
560 P=P1*14.7/29.92
570 PRINT "INPUT SCFM TO CALC. DIFF., OR INPUT ZERO TO CALC. SCFM"
580 PRINT
590 INPUT S
600 PRINT S;"SCFM DESIRED"
610 P=P1*14.7/29.92
620 D=0
630 IF S>0 THEN 860
640 IF H>0 THEN 660
650 H=0.000001
660 F2=1+C1*SQR((T+460)/(H*P))
670 F3=1-(C2*H/P)
680 F4=SQR(520/(460+T))
690 F5=SQR(1/G)
700 F6=SQR(1+((P-11.5)*9.16*104*104*(1.188*G))/(460+T)3*.825)
710 F7=0.9988+(0.004*T/228)
720 K=F*F2*F3*F4*F5*F6*F7*SQR(H*P)
730 IF S>0 THEN 860
740 PRINT "SCFM","DEG.F","P IN. HG. ABS.," "IN.H2O","SP. GR."
750 PRINT K,T,P1,H,G
751 PRINT "STD. DEV.? 1=YES,0=NO"
752 INPUT Z9
753 IF Z9=1 THEN 1250
760 PRINT "SAME ORIFICE?1=YES,0=NO"
770 INPUT K2
780 IF K2=0 THEN 10
790 PRINT "SAME TEMP PRESS AND SG?1=YES,0=NO"
800 INPUT K3
810 IF K3=0 THEN 480
820 PRINT "INPUT H2O DIFF"
830 INPUT H
840 GOTO 530
850 GOTO 1060
860 IF D=0 THEN 900
870 D=D+1
880 IF D>3 THEN 950
890 GOTO 930
900 H=10
910 D=D+1
920 GOTO 660
930 J=K/SQRH
940 H=S2/J2
950 IF S>K+0.1 THEN 990
960 IF S<K-0.1 THEN 1010
970 IF S=K THEN 1030
980 GOTO 1030
990 H=H+0.01
1000 GOTO 660
1010 H=H-0.01
1020 GOTO 660

```


TABLE 7-1 (Contd)

DIRECT HEATED NODE MATERIAL BALANCE

TABLE 7-1

```

1025 H=H/1.07
1030 PRINT "SCFM", "IN. H2O", "DEG. F", "P IN. HG. ABS.", "SP. GR."
1040 PRINT K, H, T, P1, S
1050 IF X=10 THEN 1350
1059 X1=1
1060 GOTO 760
1070 PRINT
1080 INPUT X
1090 IF X=0 THEN 1210
1100 PRINT "INPUT TEMP. INCREMENT AND P IN. HG. INCREMENT"
1110 PRINT
1120 INPUT A, B
1130 PRINT A, B
1140 PRINT "NUMBER OF TEMP. AND PRESS. INCREMENTS DESIRED? INPUT N1 & N2"
1150 PRINT
1160 INPUT N1, N2
1170 PRINT N1, N2
1180 PRINT
1190 GOTO 1360
1200 GOTO 610
1210 PRINT "DO YOU WANT THE STD. DEV. OF THE FLOW (SCFM)? 1=YES, 0=NO"
1220 PRINT
1230 INPUT X
1240 IF X=0 THEN 1060
1250 PRINT "WHAT IS THE STD. DEV. OF THE MANOMETER SETTING?"
1260 INPUT H1
1270 PRINT H1
1280 K1=K*H1/H/2*1.07
1290 PRINT "SCFM="; K1; "+OR-"; K1
1300 GOTO 760
1310 PRINT
1320 INPUT X
1330 PRINT
1340 IF X=0 THEN 1420
1350 IF X=1 THEN 60
1360 T=T+A
1370 IF T<(R+N1*A) THEN 610
1380 T=R
1390 P1=P1+B
1400 IF P1<(Z+N2*B) THEN 610
1410 GOTO 1300
1420 STANDARD
1425 PRINT "INPUT S"
1426 GOTO 590
1430 END

```


DIRECT HEATED MODE MATERIAL BALANCE PART 2
DIRECT HEATED MODE MATERIAL BALANCE

TABLE 7-2

```

10 COM HSI(6),FSI(9),YSI(8),RSI(5),ASI(4),TSI(6),GSI(14),PSI(15),CSI(10,10)
20 K=0
30 CI(10,2)=0
40 FOR I=1 TO 10
50 CI(10,2)=CI(10,2)+G(I)
60 NEXT I
70 CI(10,2)=CI(10,2)+G(13)
80 CI(10,1)=(CI(10,2)+G(12))/CI(10,2)/100
90 FOR I=1 TO 10
100 CI(8,1)=G(I)*CI(10,1)
110 NEXT I
120 CI(1,1)=FI(1)*2000/60
130 CI(1,3)=YI(1)*2000/60
140 CI(7,2)=YI(7)/60*8.33
145 CI(6,9)=CI(1,1)*100/(100-FI(9))
150 CI(1,5)=0.79*(AI(1)+AI(2)+AI(3))
160 CI(3,7)=CI(6,9)*FI(5)/100+(CI(1,1)*FI(2))/(100-FI(2))
162 CI(1,6)=RI(4)*G(2)/100
164 CI(3,8)=RI(4)*G(12)/100
180 CI(3,9)=CI(3,8)/(CI(3,8)+CI(1,6)/CI(8,2))
190 CI(10,3)=RI(4)
195 CI(1,6)=CI(10,3)*G(2)/100
200 CI(7,1)=YI(6)/60*8.33+141.5/(YI(8)+131.5)
220 FOR I=1 TO 10
230 CI(9,1)=CI(8,1)+CI(1,6)/CI(8,2)
240 NEXT I
250 CI(2,1)=0.21*(AI(1)+AI(2)+AI(3))
260 K=CI(6,9)/2000*FI(3)/29.3
270 CI(10,6)=123*K
280 CI(10,7)=26*K
290 CI(10,8)=107*K
300 CI(10,9)=137*K
310 CI(10,10)=52*K
320 CI(10,4)=CI(9,6)-379/44/100*(CI(6,9)*FI(7)-CI(1,3)*YI(3))
330 CI(10,4)=CI(10,4)-CI(10,9)
340 CI(2,5)=CI(9,4)/2-CI(10,7)/2
350 CI(2,2)=CI(10,4)+CI(2,5)
360 CI(4,1)=CI(9,1)/CI(6,9)*2000
370 CI(6,10)=CI(2,1)-CI(2,2)-CI(9,3)
420 LINK 1
430 END

```


DIRECT HEATED MODE MATERIAL BALANCE PART 2

TABLE 7-3

DIRECT HEATED MODE MATERIAL BALANCE PART 2 (CONTD)

```

10 COM HSE[6],F8[9],Y3[8],R8[5],A8[4],T8[6],G8[14],P8[15],C8[10,10]
20 PRINT "MAT. BAL. PROG. LOADED. COPYRIGHT 1975,PARAHO DEV.CORP"
30 FORMAT F8.2,5X,F8.2,12X,F15.3
40 FORMAT 26X,F8.2,X,F3.0
50 PRINT "NOW RUN70"
60 STOP
70 C[1,2]=A[4]
80 C[2,10]=C[6,10]
100 C[1,4]=C[3,8]+C[9,2]/C[8,2]
110 PRINT "BALANCES", "IN", "OUT", "UNITS", "FR.REC."
120 PRINT
130 WRITE (15,30)"ATM. NITROGEN",C[1,5],C[1,6], "SCFM ",C[1,6]/C[1,5]
140 C[1,7]=C[6,9]*F[3]/100
150 C[1,8]=C[1,3]*Y[4]/100
160 WRITE (15,30)"ASH", " ",C[1,7],C[1,8], "#/MIN",C[1,8]/C[1,7]
170 C[6,6]=C[2,2]+C[2,10]
180 WRITE (15,30)"OXYGEN", " ",C[2,1],C[6,6], "SCFM ",C[6,6]/C[2,1]
190 WRITE (15,40)C[2,10], "TO H2O"
200 WRITE (15,40)C[2,2], "TO CO&CO2"
210 C[2,6]=C[10,4]*12/379+(C[2,2]-C[10,4])*24/379
220 C[2,7]=C[2,10]*4/379
230 C[1,9]=C[3,7]+C[2,10]*36/379
240 C[1,10]=C[7,2]+C[3,8]*18/379
250 WRITE (15,30)"WATER", " ",C[1,9],C[1,10], "#/MIN",C[1,10]/C[1,9]
260 FORMAT 13X,F8.2,X,"S",3X,F8.2,X,"L"
270 WRITE (15,260)C[3,7],C[7,2]
280 FORMAT 13X,F8.2,X,"C",3X,F8.2,X,"V"
290 WRITE (15,280)C[2,7]*36/4-C[4,1]*C[6,9]/2000*18/379,C[3,8]*18/379
300 C[2,8]=(100-F[8]-F[7]-F[5])*C[6,9]/100
310 C[2,9]=C[9,1]+2+C[9,5]*16+C[9,7]*28+C[9,8]*30+C[9,9]*43+C[9,10]*57
315 C[2,9]=C[2,9]/379
320 C[2,9]=C[2,9]+C[1,3]*(100-Y[4]-Y[3])/100+C[7,1]
330 C[2,9]=C[2,9]+C[2,7]+C[1,4]/379+G[13]*1.44+(C[9,6]+C[9,4])*12/379
332 C[2,9]=C[2,9]-(F[7]*C[6,9]-Y[3]*C[1,3])/100*12/44
340 WRITE (15,30)"KEROGEN", " ",C[2,8],C[2,9], "#/MIN",C[2,9]/C[2,8]
350 WRITE (15,40)C[1,3]*(100-Y[4]-Y[3])/100,"S"
360 WRITE (15,40)C[7,1], "O"
370 WRITE (15,40)C[2,9]-(C[1,3]*(100-Y[4]-Y[3])/100)-C[7,1], "G"
380 IF P[2]=0 THEN 620
390 IF P[5]=0 THEN 620
400 IF P[8]=0 THEN 620
410 C[6,7]=C[6,9]*(P[2]-F[7]*12/44)/100
420 C[6,8]=(C[1,3]*(P[5]-Y[3]*12/44)+C[7,1]*P[8])/100
430 C[6,8]=C[6,8]+(C[9,5]*12+C[9,7]*24+C[9,8]*24+C[9,9]*36)/379
440 C[6,8]=C[6,8]+(C[9,10]*48+C[1,4]*G[13]*1.2+(C[9,6]+C[9,4])*12)/379
442 C[6,8]=C[6,8]-12/44/100*(F[7]*C[6,9]-Y[3]*C[1,3])
450 WRITE (15,30)"ORGANIC CARBON",C[6,7],C[6,8], "#/MIN",C[6,8]/C[6,7]
460 WRITE (15,40)C[1,3]*(P[5]-Y[3]*12/44)/100,"S"
470 WRITE (15,40)C[7,1]*P[8]/100,"O"
480 WRITE (15,40)C[6,8]-(C[1,3]*(P[5]-Y[3]*12/44)+C[7,1]*P[8])/100,"G"

```


DIRECT HEATED MODE MATERIAL BALANCE PART 2 (CONTD)

TABLE 7-3

```

490 C[3,3]=C[6,9]*P[3]/100
500 C[3,4]=(C[7,1]*P[9]+C[1,3]*P[6])/100
510 C[3,4]=C[3,4]+C[7,2]*2/18
520 C[3,4]=C[3,4]+(C[9,1]*2+C[9,5]*4+C[9,7]*4+C[9,8]*6+C[9,9]*8)/379
530 C[3,4]=C[3,4]+C[9,10]*10/379+C[1,4]/379*G[13]*0.24+C[3,8]/379*2
540 C[3,4]=C[3,4]+C[1,4]*G[14]/379*3/100
550 WRITE (15,30)"TOT. HYDROGEN",C[3,3],C[3,4],"#/MIN",C[3,4]/C[3,3]
560 WRITE (15,40)C[1,3]*P[6]/100,"S"
570 WRITE (15,40)C[7,1]*P[9]/100,"O"
580 WRITE (15,40)C[3,4]-C[1,3]*P[6]/100-C[7,1]*P[9]/100,"G+H2O"
590 C[3,5]=C[6,9]*P[4]/100
600 C[3,6]=(C[7,1]*P[10]+C[1,3]*P[7]+G[14]*C[1,4]*14/379)/100
610 WRITE (15,30)"ORG. NITROGEN",C[3,5],C[3,6],"#/MIN",C[3,6]/C[3,5]
620 C[2,3]=C[1,1]+(A[1]+A[2]+A[3])/379*29+C[3,7]-C[6,9]*P[5]/100
630 C[2,4]=C[1,4]+C[1,2]*29/379+C[7,1]
640 C[2,4]=C[2,4]+C[7,2]+C[1,3]
650 WRITE (15,30)"O' ALL WEIGHT ",C[2,3],C[2,4],"#/MIN",C[2,4]/C[2,3]
660 PRINT
670 FORMAT F8.3,X,"#/MIN C",F8.3,X,"#/MIN H",F8.3,X,"C/H COMB RATIO"
680 WRITE (15,670)C[2,6],C[2,7],C[2,6]/C[2,7]
685 C[6,5]=100*(141.5/(131.5+Y[6]))+8.33*Y[6]/60)/(C[4]/100+C[6,9])
690 WRITE (15,30)Y[6]/(C[1,1]*60/2000*P[3])*100,"VOL%FA",C[6,5],"WT.%FA"
700 PRINT
705 LINK 5
710 END

```


CALCULATED DATA ARRAY FOR DIRECT MODE MATERIAL AND HEAT BALANCES
C [10,10]

1 = Mat.Bal.
Part 1

2 = Mat.Bal.
Part 2

3 = Heat Bal.

	1	2	3	4	5	6	7	8	9	10
1	Dry Shale #/min. (1-120)	S.G.Wet Gas (2-70)	Ret.Shale #/min. (1-130)	Dry Gas + H ₂ O SCFM (2-100)	N ₂ -SCFM IN (1-150)	N ₂ -SCFM OUT (1-195)	Ash In. #/min. (2-140)	Ash Out #/min. (2-150)	H ₂ O In, #/min. (2-230)	H ₂ O Out, #/min. (2-240)
2	O ₂ -SCFM in Air (1-250)	O ₂ -SCFM to burn C (1-350)	Wt. In. #/min. (2-620)	Wt. Out #/min. (2-630)		C burned #/min. (2-210)	H burned #/min. (2-220)	Kerogen in, #/min (2-300)	Kerogen out #/min (2-310)	O ₂ -SCFM to burn H (1-370) (2-80)
3			Hydrogen in, #/min (2-490)	Hydrogen Out, #/min (2-500)	Org N in, #/min (2-590)	Org N out, #/min (2-600)	H ₂ O In shale #/min (1-160)	H ₂ O In Gas, SCFM (1-164)	Fr. H ₂ O Vapor In Prod Gas (1-180)	
4	H ₂ -SCF/T Net After F.A. H ₂ (1-360)		CO ₂ -SCF/T Net.Comb. After F.A. + Min CO ₂ (3-50)	Btu/Tn C → CO ₂ (3-70)	CO-SCF/T Net Comb After FA CO (3-80)	Btu/Ton 2C + O ₂ → 2CO (3-90)	H ₂ -SCF/T Comb. By O ₂ (3-110)	BTU/Ton 2H ₂ + O ₂ → 2H ₂ O (3-120)	C/H Comb. Ratio (3-140)	
5	Shale in Btu/T (S1) (3-154)	Air in. Btu/T (S2) (3-157)	Gas In. Btu/T (S3) (3-330)	Cooling H ₂ O, Btu/T (w) (3-158)	Off Gas BTU/T (S5) (3-291)	Ret.Shale Btu/T (S6) (3-400)	Oil Mist Out, Btu/T (S7) (3-430)	Latent H ₂ O Btu/T (S8) (3-460)	Carb.Dec Btu/T (S9) (3-490)	Liq.H ₂ O As Gas Btu/T (S10) (3-520)
6	Heat In Btu/T (I) (3-570)	Heat Out Btu/T (O) (3-590)	Differr. Btu/T (U) (3-600)				Org C In #/Min (2-410)	Org C Out #/Min (2-420)		
7	Oil, #/ Min (1-200)	Liquid #/Min (1-140)		Carb. Decomp. % (3-910)						
8	Dry Gas FR. H ₂ (1-90) → (1-110)	FR N ₂	FR O ₂	FR CO	FR CH ₄	FR CO ₂	FR C ₂ H ₄	FR C ₂ H ₆	FR C ₃	FR C ₄
9	H ₂ -SCFM (1-220) → 240)	N ₂ SCFM	O ₂ SCFM	CO SCMF	CH ₄ SCFM	CO ₂ SCFM	C ₂ H ₄ SCFM	C ₂ H ₆ SCFM	C ₃ SCFM	C ₄ SCFM
10	Factor wet % Gas to Dry FR (1-80)	ΣG(1 to 10) + G(13) Ex. H ₂ O (1-40) → (1-70)	Prod. Gas SCFM (1-190)	O ₂ -SCFM to Burn C to CO ₂ (1-320)		Fischer Assay H ₂ - SCFM (1-270)	F.A. CO SCFM (1-280)	F.A. CH ₄ SCFM (1-290)	F.A. CO ₂ SCFM (1-300)	F.A. C ₂ H ₄ + C ₂ H ₆ (1-310)

TABLE 7-4

TABLE 7-5
DIRECT HEATED MODE MATERIAL BALANCES - PRELIMINARY CALCULATIONS

BASIS: DRY SHALE INPUT

$$\begin{aligned} C [1,3] &= (\text{Ret Shale TPH}) * 2000/60 \Rightarrow [\text{DRY RET SHALE \#/MIN}] < \textcircled{1} - 130 > \\ C [1,1] &= (\text{Raw Shale TPH}) * 2000/60 \Rightarrow [\text{DRY RAW SHALE \#/MIN}] < \textcircled{1} - 120 > \\ C [6,9] &= \frac{C [1,1] * 100}{[100 - \text{wt\% lab moist.}]} = [\text{LAB MOIST. SHALE \#/MIN}] < \textcircled{1} - 145 > \end{aligned}$$

FISCHER ASSAY ADJUSTMENT FIGURE TO CALCULATE
ASSUMED VALUES FOR THE PRODUCTION OF
H₂, CO, CH₄, & CO₂ BASED ON THE RAW SHALE F.A.GPT

$$K = \frac{C [6,9] * (\text{raw shale Fischer Assay GPT}) < \textcircled{1} - 260 >}{2000 * 29.3}$$

29.3 is the Raw Shale FA GPT from which the
production figures are based

$$\begin{aligned} \text{For H}_2 \text{ C } [10,6] &= 123 * K \Rightarrow [\text{SCFM H}_2 \text{ from F.A.}] < \textcircled{1} - 270 > \\ \text{For CO C } [10,7] &= 26 * K \Rightarrow [\text{SCFM CO from F.A.}] < \textcircled{1} - 280 > \\ \text{For CH}_4 \text{ C } [10,8] &= 107 * K \Rightarrow [\text{SCFM CH}_4 \text{ from F.A.}] < \textcircled{1} - 290 > \\ \text{For CO}_2 \text{ C } [10,9] &= 137 * K \Rightarrow [\text{SCFM CO}_2 \text{ from F.A.}] < \textcircled{1} - 300 > \end{aligned}$$

MAT BAL PART 1 = $\textcircled{1}$
MAT BAL PART 2 = $\textcircled{2}$
HEAT BAL = $\textcircled{3}$

KEY: EACH OF THE ABOVE EXPRESSIONS IS REFERENCED TO ITS POSITION
IN THE PROGRAM EXECUTION BY PROGRAM # & LINE #

< $\textcircled{1}$ - 100 means the expression may be found
in line 100 of mat bal part 1

IN THE ABOVE EQUATION IS DEFINED A TIME t

WHICH EACH OF THE THREE EXPRESSIONS IS SUBSTITUTED IN THE EQUATION

THEY ARE
 1. $t = 0$
 2. $t = 1$
 3. $t = 2$

$$\begin{aligned} \text{FOR } CO_2 \text{ C} [10' \text{ d}] &= 131 \times K \Rightarrow [SCM \text{ CO}_2 \text{ FROM } A \cdot \bar{V}] < \text{①} > - 300 < \\ \text{FOR } CH_4 \text{ C} [10' \text{ d}] &= 101 \times K \Rightarrow [SCM \text{ CH}_4 \text{ FROM } A \cdot \bar{V}] < \text{①} > - 330 < \\ \text{FOR } CO \text{ C} [10' \text{ d}] &= 30 \times K \Rightarrow [SCM \text{ CO FROM } A \cdot \bar{V}] < \text{①} > - 580 < \\ \text{FOR } H_2 \text{ C} [10' \text{ d}] &= 133 \times K \Rightarrow [SCM \text{ H}_2 \text{ FROM } A \cdot \bar{V}] < \text{①} > - 310 < \end{aligned}$$

Calculation (above) are based
 on 1/12 the new scale of CH₄ from which the

$$K = \frac{1000 \times 52.7}{C [10' \text{ d}] \times 1000 \text{ grams liter } CH_4 < \text{①} > - 340 <$$

H₂ CO₂ CH₄ + CO₂ based on the new scale A.V. CH₄
 WEIGHTED AVERAGE FOR THE EQUATION OF
 LITERAL WEIGHT AVERAGE LITERAL WEIGHT TO CALCULATE

$$\begin{aligned} C [10' \text{ d}] &= \frac{1000 \times 52.7}{C [10' \text{ d}] \times 1000} \times [THE NEW SCALE FROM A \cdot \bar{V}] < \text{①} > - 142 < \\ C [10' \text{ d}] &= (new scale) \times 1000 \times 50 \Rightarrow [THE NEW SCALE FROM A \cdot \bar{V}] < \text{①} > - 130 < \\ C [10' \text{ d}] &= (new scale) \times 1000 \times 50 \Rightarrow [THE NEW SCALE FROM A \cdot \bar{V}] < \text{①} > - 130 < \end{aligned}$$

NOTE: NEW SCALE FROM

DIRECT REVERSE MODE WEIGHTED AVERAGE - AVERAGE FROM EQUATION

TABLE 7-5 (Contd)

CALCULATION OF O₂ (SCFM) TO BURN C TO CO & CO₂

1. O₂ SCFM TO BURN C TO CO₂

$$C [10, 4] = (\text{SCFM CO}_2 \text{ IN PROD. GAS}) - \left[\frac{(C [6, 9] * (\text{Raw Shale wt\% min CO}_2) - C [1, 3] * (\text{Ret. Shale wt\% min CO}_2) * 379)}{44 * 100} \right] - C [10, 9]$$

< ① 330 >

2. O₂ SCFM TO BURN C TO CO

$$C [2, 5] = (\text{SCFM CO IN PROD GAS}) - C \frac{[10, 7]}{2} < ① - 340 >$$

3. O₂ SCFM TO FORM H₂O (BY DIFFERENCE ASSUMING A 100% OXYGEN BALANCE)

$$C [2, 10] = [(\text{SCFM O}_2 \text{ INPUT IN AIR}) - C [10, 4] - C [2, 5] - (\text{SCFM O}_2 \text{ IN PROD GAS})] < ① - 370 >$$

RESULTS:

a. $C [2, 2] = C [10, 4] + C [2, 5] = \text{SCFM O}_2 \text{ TO BURN C TO CO \& CO}_2 < ① - 350 >$

b. $\frac{C [10, 4] * 12}{379} + \frac{(C [2, 2] - C [10, 4]) * 24}{379} = \text{CARBON BURNED (\#/MIN)} < ② - 210 >$

c. $\frac{C [2, 10] * 4}{379} = \text{HYDROGEN BURNED (\#/MIN)} < ② - 220 >$

d. $C/H \text{ COMB RATIO} = C [2, 6] / C [2, 7] < ② - 680 >$

$$q = c \sqrt{10} \sin 10^\circ = c \sqrt{10} \sin 10^\circ < 0 - \text{отв}$$

$$p = \frac{c \sqrt{10}}{2} \sin 10^\circ = \frac{c \sqrt{10}}{2} \sin 10^\circ < 0 - \text{отв}$$

$$r = \frac{c \sqrt{10}}{2} \sin 10^\circ = \frac{c \sqrt{10}}{2} \sin 10^\circ < 0 - \text{отв}$$

$$s = c \sqrt{10} \sin 10^\circ = c \sqrt{10} \sin 10^\circ < 0 - \text{отв}$$

ответ:

$$c \sqrt{10} \sin 10^\circ = c \sqrt{10} \sin 10^\circ < 0 - \text{отв}$$

$$2. \text{ если } 10^\circ \text{ то } \sin 10^\circ = \frac{1}{2} \text{ и } \cos 10^\circ = \frac{\sqrt{3}}{2}$$

$$c \sqrt{10} \sin 10^\circ = c \sqrt{10} \sin 10^\circ < 0 - \text{отв}$$

$$3. \text{ если } 10^\circ \text{ то } \sin 10^\circ = \frac{1}{2} \text{ и } \cos 10^\circ = \frac{\sqrt{3}}{2}$$

$$< 0 - \text{отв}$$

$$c \sqrt{10} \sin 10^\circ = c \sqrt{10} \sin 10^\circ < 0 - \text{отв}$$

$$4. \text{ если } 10^\circ \text{ то } \sin 10^\circ = \frac{1}{2} \text{ и } \cos 10^\circ = \frac{\sqrt{3}}{2}$$

$$5. \text{ если } 10^\circ \text{ то } \sin 10^\circ = \frac{1}{2} \text{ и } \cos 10^\circ = \frac{\sqrt{3}}{2}$$

ответ: 1-2 (отв)

TABLE 7-6
DIRECT HEATED MODE MATERIAL BALANCE PART 2

BALANCES

A. ATMOSPHERIC NITROGEN BALANCE

$$N_2 \text{ IN (SCFM)} = C [1,5] = 0.79 * [\text{TOP} + \text{MID} + \text{BTM AIR (SCFM)}] < \textcircled{1} - 150 >$$

$$N_2 \text{ OUT (SCFM)} = C [1,6] = (\text{PROD. GAS SCFM}) * \frac{(\text{VOL\% } N_2 \text{ IN PROD GAS})}{100} < \textcircled{1} - 195 >$$

B. ASH BALANCE

$$\text{ASH IN (\#/MIN)} = C [1,7] = \left[\frac{\text{DRY RAW SHALES, \#/MIN} * 100}{(100 - \text{wt\% LAB MOISTURE})} \right] * \frac{(\text{Raw Shale wt\% Ash})}{100} < \textcircled{2} - 140 >$$

$$\text{ASH OUT (\#/MIN)} = C [1,8] = \frac{[\text{RET SHALE, \#/MIN}] * (\text{Ret Shale wt\% Ash})}{100} < \textcircled{2} - 150 >$$

C. OXYGEN BALANCE

$$O_2 \text{ IN (SCFM)} = C [2,1] = 0.21 * [\text{TOP} + \text{MID} + \text{BTM AIR (SCFM)}] < \textcircled{1} - 250 >$$

$$O_2 \text{ OUT (SCFM)} = C [6,6] = (\text{SCFM } O_2 \text{ TO BURN C TO CO \& CO}_2) + (\text{SCFM TO BURN H TO H}_2\text{O}) < \textcircled{2} - 170 >$$

$$C [2,2] \qquad \qquad \qquad C [2,10]$$

D. WATER BALANCE

$$H_2O \text{ IN (\#/MIN)} = C [1,9] = \left[\frac{(\text{DRY RAW SHALE, \#/MIN}) * 100}{(100 - \text{wt\% LAB MOISTURE})} \right] * \frac{(\text{Fischer Assay Wt\% H}_2\text{O})}{100} +$$

$$\frac{(\text{DRY RAW SHALE, \#/MIN}) * (\text{TYLAB MOISTURE, WT\%})}{(100 - \text{TYLAB MOISTURE, WT\%})} + \frac{(\text{SCFM } O_2 \text{ TO BURN H TO H}_2\text{O}) * 36}{379} < \textcircled{2} - 230 >$$

$$H_2O \text{ OUT (\#/MIN)} = C [1,10] = (\text{H}_2\text{O COLLECTED, \#/MIN}) + \frac{(\text{PROD. GAS SCFM}) * (\text{VOL\% H}_2\text{O}) * 18}{100 * (379 \text{ SCF/\# MOLE})} < \textcircled{2} - 240 >$$

- NOTE 1: THE RETORTED SHALE IS ASSUMED TO BE DRY
NOTE 2: TYLAB MOIST. IS ON THE UNCRUSHED RAW SHALE. LAB MOIST. IS ON THE CRUSHED LAB SAMPLE.
NOTE 3: THE "H₂O IN" CALCULATION ASSUMES FISCHER ASSAY H₂O AND LAB MOISTURE TO BE INDEPENDENT.
TO BE ABSOLUTELY ACCURATE, THE LAB MOISTURE SHOULD BE SUBTRACTED FROM THE FISCHER
ASSAY H₂O IN THE ABOVE CALCULATION BECAUSE THE F.A. H₂O INCLUDES LAB MOISTURE.

TABLE 7-6 (Contd)

E. KEROGEN BALANCE

$$\text{KEROGEN IN (\#/MIN)} = C[2,8] = C[6,9] * \frac{[100 - (\text{Raw shale wt\% ash}) - (\text{Raw shale wt\% min CO}_2) - (\text{Raw shale Fischer Assay wt\% H}_2\text{O})]}{100}$$

$$\text{KEROGEN OUT (\#/MIN)} = C[2,9] = \frac{1}{379} * \sum_i \left[\text{SCFM Comp } i \text{ IN PROD GAS (DRY BASIS)} \right] * (\text{M.W. of Comp } i)$$

where i is all gas components
except N₂, O₂, CO, CO₂, H₂O, and
oil

$$+ (\text{RETORTED SHALE, \#/MIN}) * \frac{[100 - (\text{RET SHALE WT\% ASH}) - (\text{RET SHALE WT\% MIN CO}_2)]}{100} + (\text{PROD OIL, \#/MIN})$$

$$+ (\text{HYDROGEN BURNED TO H}_2\text{O \#/MIN}) + \frac{[\text{PROD GAS, SCFM (WET)}] * (\text{VOL\% OIL}) * (144 \text{ \#/mole})}{(379 \text{ SCFM}) / (\text{\#/mole})}$$

$$+ (\text{CARBON BURNED TO CO \& CO}_2, \text{ \#/MIN}) - \left[C[6,9] * (\text{Raw shale wt\% min CO}_2) - (\text{ret shale, \#/min}) * (\text{ret shale wt\% min CO}_2) \right] * \frac{12}{44 * 100} \quad 2 - 310 - 332$$

F. ORGANIC CARBON BALANCE

$$\text{ORGANIC C IN (\#/MIN)} = C[6,7] = C[6,9] * \frac{[(\text{Raw Shale wt\% C}) - (\text{Raw Shale wt\% min CO}_2) * \frac{12}{44}]}{100} < \textcircled{2} - 410 >$$

$$\text{ORGANIC C OUT (\#/MIN)} = C[6,8] = (\text{Ret Shale \#/MIN}) * \frac{[(\text{Ret Shale wt\% C}) - (\text{Ret shale wt\% min CO}_2) * \frac{12}{44} + (\text{Prod oil \#/min}) * (\text{oil wt\% C})]}{100}$$

$$+ \frac{12 * C}{379 \text{ SCFM} / (\text{\#/mole})} * \sum_i (\text{SCFM Comp } i \text{ IN PROD GAS (DRY BASIS)}) * (\text{NO. OF CARBON ATOMS IN COMP } i)$$

i Where i includes CH₄, C₂H₄,
C₂H₆, C-3's, C-4's

$$+ \frac{[\text{PROD GAS, SCFM (WET)}] * (\text{VOL\% OIL}) * 1.2 + (\text{CARBON BURNED TO CO \& CO}_2, \text{ \#/MIN})}{379}$$

$$- C[6,9] * [(\text{Raw shale wt\% min CO}_2) - (\text{Ret shale, \#/min}) * (\text{Ret Shale wt\% min CO}_2)] * \frac{12}{44 * 100} < \textcircled{2} - 420 > 442 >$$

NOTE: $C[6,9] = \frac{(\text{dry raw shale, \#/min}) * 100}{(100 - \text{Raw shale wt\% Lab Moisture})} = \text{LAB MOIST. SHALE, \#/MIN}$

10-11-68

WESTON BOND

STATIONERY
DIVISION

TABLE 7-6 (Contd)

G. TOTAL HYDROGEN BALANCE

$$\text{HYDROGEN IN (\#/MIN)} = C [3,3] = \frac{C [6,9] * (\text{RAW SHALE WT\% H})}{100} < \textcircled{2} - 490 >$$

$$\text{HYDROGEN OUT (\#/MIN)} = C [3,4] = \frac{[(\text{PROD OIL, \#/MIN}) * (\text{OIL WT\% H}) + (\text{RET SHALE \#/MIN}) * (\text{RET SHALE WT\% H})]}{100}$$

$$+ (\text{H}_2\text{O COLLECTED, \#/MIN}) * \frac{2}{18} + \frac{1 \text{ \# H}}{379 \text{ SCF}} * \sum_i (\text{SCFM Comp } i \text{ IN PROD GAS (DRY BASIS)} * (\text{no. of H Atoms in Comp } i))$$

where i includes H₂, CH₄, C₂H₄,
C₂H₆, C-3's & C-4's

$$+ \frac{[\text{PROD GAS, SCFM (WET)}] * (\text{VOL\% OIL}) * 0.24}{379} + (\text{H}_2\text{O IN PROD GAS, SCFM}) * \frac{2}{379} < \textcircled{2} - 500 \rightarrow 540 >$$

H. ORGANIC NITROGEN BALANCE

$$\text{ORGANIC NITROGEN IN (\#/MIN)} = C [3,5] = \frac{C [6,9] * (\text{Raw Shale wt\% N})}{100} < \textcircled{2} - 590 >$$

$$\text{ORGANIC NITROGEN OUT (\#/MIN)} = C [3,6] = \frac{[(\text{PROD OIL, \#/MIN}) * (\text{OIL WT\% N}) + (\text{RET SHALE, \#/MIN}) * (\text{RET SHALE WT\% N})]}{100} < \textcircled{2} - 600 >$$

I. OVERALL WEIGHT BALANCE

$$\text{TOTAL WEIGHT IN (\#/MIN)} = C [2,3] = (\text{DRY RAW SHALE, \#/MIN}) + (\text{TOT AIR INPUT, \#/MIN}) + (\text{H}_2\text{O IN RAW SHALE, \#/MIN})$$


$$- \left[\frac{(\text{DRY SHALE, \#/MIN}) * 100}{(100 - \text{wt\% lab moisture})} \right] * \frac{(\text{Raw shale Fischer Assay wt\% H}_2\text{O})}{100} < \textcircled{2} - 620 >$$

$$\text{TOTAL WEIGHT OUT (\#/MIN)} = C [2,4] = \frac{[\text{PROD GAS, SCFM (WET)}] * (\text{SPECIFIC GRAVITY (WET GAS)} * (29 \frac{\text{\#}}{\text{\# mole}}))}{379 \frac{\text{SCF}}{\text{\# mole}}}$$

$$+ (\text{PROD OIL, \#/MIN}) + (\text{H}_2\text{O COLLECTED, \#/MIN}) + (\text{RET SHALE, \#/MIN}) < \textcircled{2} - 630,640 >$$

DIRECT HEATED MODE-HEAT BALANCE PROGRAM FLOW CHART

Figure 7-3



DIRECT HEATED WIRE-HEAT BALANCE PROGRAM FLOW CHART

Figure 7-3




TABLE 7-7
DIRECT HEATED MODE HEAT BALANCE

```

10 DIM HSI(6),FSI(9),YI(8),RSI(5),ASI(4),TSI(6),CSI(4),PSI(15),CST(10,10)
11 DIM S1,S2,S3,W,S5,S6,S7,S8,S9,S0,I,O,U
20 PRINT "HEAT BALANCE PROGRAM LOADED. COPYRIGHT 1975, PARAHO DEV. CORP."
22 PRINT
23 FIXED 3
25 PRINT "BASIS: 1 TON DRY SHALE          DATUM: 77 DEG F"
50 CI(4,3)=CI(10,4)*60/FI(1)
70 CI(4,4)=CI(4,3)/379*169180
80 CI(4,5)=2*(CI(2,2)-CI(10,4))*60/FI(1)
90 CI(4,6)=CI(4,5)/379*95033/2
110 CI(4,7)=CI(2,10)*2*60/FI(1)
120 CI(4,8)=CI(4,7)/379*207934/2
140 CI(4,9)=CI(2,6)/CI(2,7)
150 PRINT "C/H COMB RATIO"CI(4,9)
154 S1=(4/10+5*TI(6)+2+0.2068*TI(6)-16)*2000
155 Z=TI(4)/10+3
156 X1=(0.2421+0.2413+0.0027*Z+0.0255*Z+2)/2+29
157 S2=X1*(TI(4)-77)*(AC(1)+AC(2)+AC(3))*60/379/FI(1)
158 W=FI(1)+FI(2)*60*8.33/FI(1)
159 S5=0
160 Z=TI(1)/10+3
170 X=X+CI(1)/100*(0.415+0.367+0.7783*Z-2.138*Z+2+1.991*Z+3)/2+2.016
180 X=X+CI(2)/100*(0.248+0.248-0.0021*Z+0.0255*Z+2-0.0008*Z+3)/2+28
190 X=X+CI(3)/100*(0.2192+0.2175+0.0194*Z+0.0296*Z+2)/2+32
200 X=X+CI(4)/100*(0.248+0.248-0.0001*Z+0.0299*Z+2)/2+28
210 X=X+CI(5)/100*(0.532+0.506+0.3303*Z+0.213*Z+2)/2+16
220 X=X+CI(6)/100*(0.2014+0.1906+0.1461*Z-0.0657*Z+2)/2+44
230 X=X+CI(7)/100*(0.371+0.332+0.517*Z-0.1022*Z+2)/2+28.05
240 X=X+CI(8)/100*(0.419+0.376+0.5604*Z-0.0225*Z+2)/2+30.1
250 X=X+CI(9)/100*(0.3986+0.3489+0.656*Z-0.1313*Z+2)/2+44.1
260 X=X+CI(10)/100*(0.398+0.346+0.682*Z-0.178*Z+2)/2+58.1
270 X=X+CI(12)/100*(0.445+0.443+0.0177*Z+0.11*Z+2-0.0645*Z+3)/2+18
280 X=X+CI(13)/100*(0.408+0.368+0.51*Z+0.264*Z+2-0.429*Z+3)/2+100
285 IF S5>0 THEN 330
290 PRINT "MEAN CP OFF GAS";X;"BTU/LB-MOLE DEG F";TI(1);"OFF GAS TEMP"
291 S5=X*(TI(1)-77)*(RI(1)+RI(2)+RI(3)+RI(4))*60/379/FI(1)*CI(1,4)/RI(4)
300 Z=TI(2)/10+3
301 GOTO 170
330 S3=X*(TI(2)-77)*(RI(1)+RI(2)+RI(3))*60/379/FI(1)*CI(1,4)/RI(4)
340 PRINT "MEAN CP REC GAS";X;"BTU/LB-MOLE DEG F";TI(2);"REC GAS TEMP"
350 PRINT
360 PRINT TAB(5) "HEAT IN"TAB(35) "HEAT OUT"
370 PRINT
380 FORMAT 37X,"OFF GAS",15X,F8.0
390 WRITE (15,380)S5
400 S6=0.2224*(TI(3)-77)*2000*YI(1)/FI(1)
410 FORMAT "C+02 TO CO",11X,F8.0,7X,"RET SH OUT",12X,F8.0
420 WRITE (15,410)CI(4,4),S6
430 S7=YI(6)*8.33*(141.5/(YI(8)+131.5))*(0.478*TI(1)-36.8)/FI(1)
440 FORMAT "C+O2 TO CO",12X,F8.0,7X,"OIL MIST OUT",10X,F8.0
450 WRITE (15,440)CI(4,6),S7
460 S8=(FI(5)+FI(2))*2000*1250/100
470 FORMAT "H2+O2 TO H2O",10X,F8.0,7X,"LATENT HT FR H2O",6X,F8.0
480 WRITE (15,470)CI(4,8),S8
490 S9=2000/100*(FI(7)-YI(3)*YI(1)/FI(1))/44
491 IF S9<2.5 THEN 497
492 S9=(S9-2.5)*75096+2.5*58835
493 GOTO 500
497 S9=S9*58835
500 FORMAT "AIR IN",16X,F8.0,7X,"CARBONATE DECOMP",6X,F8.0
510 WRITE (15,500)S2,S9

```


TABLE 7-7 (Contd)
DIRECT HEATED MODE HEAT BALANCE (CONT)

```

520 Q0=YI7*H0.33*(0.417*TI11-32.1)/FI11
530 X2=32+2000
540 FORMAT "SHALE IN",14%,F8.0,7%,"PYROLYSIS",13%,F8.0
550 WRITE (15,540)S1,X2
560 FORMAT "GAS IN",16%,F8.0,7%,"COOLING H2O",11%,F8.0
570 I=CI4,41+CI4,61+CI4,81+S1+S2+S3
580 WRITE (15,560)S3,W
585 L=10000
590 Q=S5+S6+S7+S8+S9+S0+W+L+X2
600 U=I-0
610 FORMAT 37%,"LIO H2O OFF AS GAS",4%,F8.0
620 WRITE (15,610)S0
625 FORMAT 37%,"SKIN LOSSES",11%,F8.0
626 WRITE (15,625)L
630 FORMAT 37%,"DIFFERENCE",12%,F8.0
635 WRITE (15,630)U
640 FORMAT 23%,"-----",30%,"-----"
645 WRITE (15,640)
650 FORMAT 10%,"TOTAL IN",4%,F8.0,17%,"TOTAL OUT",3%,F8.0
650 WRITE (15,650)I,U+U
895 PRINT
900 CI7,31=2000*FI71/100/44
910 CI7,41=20*(FI71-YI31*YI11)/44/CI7,31*100
920 PRINT "CARBONATE DECOMP",CI7,41,"%"
980 CI5,11=S1
990 CI5,21=S2
1000 CI5,31=S3
1010 CI5,41=W
1020 CI5,51=S5
1030 CI5,61=S6
1040 CI5,71=S7
1050 CI5,81=S8
1060 CI5,91=S9
1065 CI5,101=S0
1070 CI6,11=I
1075 CI6,21=0
1080 CI6,31=U
1090 PRINT
1100 PRINT
1105 STANDARD
1106 FIND 2
1110 END

```



TABLE 7-8

DIRECT HEATED MODE HEAT BALANCE


HEAT IN

BASIS: 1 TON DRY SHALE DATUM: 77°F


COMBUSTION REACTIONS



$$Btu/T = \frac{[(SCFM O_2 \text{ to BURN } C \rightarrow CO_2) * (60 \frac{Min}{Hr})] * (169180 \frac{Btu}{\# \text{ mole}})}{[(\text{DRY SHALE, } \frac{TONS}{HR}) * 379 \frac{SCF}{\# \text{ mole}}]} < \textcircled{3} - 70 >$$



$$Btu/T = \frac{[2 * (SCFM O_2 \text{ TO BURN } C \rightarrow CO) * (60 \frac{Min}{Hr})]}{[(\text{DRY SHALE, } \frac{TONS}{Hr}) * 379 \frac{SCF}{\# \text{ mole}}]} * (\frac{95033}{2} \frac{Btu}{\# \text{ mole}}) < \textcircled{3} - 90 >$$



$$Btu/T = \frac{[2 * (SCFM O_2 \text{ TO BURN } H \rightarrow H_2O * (60 \frac{Min}{Hr}))]}{[(\text{DRY SHALE, } \frac{TONS}{Hr}) * (379 \frac{SCF}{\# \text{ mole}})]} * (\frac{207934}{2} \frac{Btu}{\# \text{ mole}}) < \textcircled{3} - 120 >$$

$$\frac{AIR \text{ IN}}{Btu/T} = \left[\frac{29}{2} * \left(0.2421 + 0.2418 + 0.0027 * T[4] + 0.0256 * \left[\frac{T[4]^2}{10^3} \right] \right) \frac{Btu}{MoF} * \frac{(T[4] - 77) * (SCFM \text{ AIR INPUT}) * 60 \frac{Min}{Hr}}{379 \frac{SCF}{\# \text{ mole}} * (\text{DRY SHALE, } \frac{TONS}{HR})} \right] < \textcircled{3} - 157 >$$

T [4] = Air Blower Discharge T °F

$$\frac{SHALE \text{ IN}}{Btu/T} = \left[4 * 10^{-5} * T[6]^2 + 0.2068 * T[6] - 16 \frac{Btu}{\#} \right] * (2000 \# / \text{Ton}) < \textcircled{3} - 154 >$$

T [6] = shale in T °F

$$\frac{GAS \text{ IN}}{Btu/T} = \left[\sum (\text{vol\% OF GAS COMP } i) * \left[\frac{\text{ENTHALPY OF COMP } i \text{ AT}}{\text{GAS BLOWER DISCHG TEMP } ^\circ F} \right] * (\text{M.W. OF COMP } i) \right] \frac{Btu}{\# \text{ mole } ^\circ F}$$

$$* (T[2] - 77) ^\circ F * (\text{TOT GAS SCFM}) * 60 \frac{Min}{Hr} \\ (379 \frac{SCF}{\# \text{ mole}}) * (\text{DRY SHALE, } \frac{tons}{Hr}) < \textcircled{3} - 330 >$$

T [2] = Gas blower discharge T °F

TABLE 7-8 (Contd)

HEAT OUT

$$\text{RET SHALE OUT} = \frac{(0.2224 \frac{\text{Btu}}{\# \text{ } ^\circ\text{F}}) * (T [3] - 77) ^\circ\text{F} * (\frac{2000 \#}{\text{Ton}}) * (\text{RET SHALE TPH})}{(\text{DRY RAW SHALE, TPH})} < \textcircled{3} - 400 > \quad T [3] = \text{Retorted shale } T ^\circ\text{F}$$

$$\text{OIL MIST OUT} = \frac{(\text{PRODUCT OIL, GPH}) * (\text{OIL DENSITY, } \frac{\#}{\text{Gal}}) * \left[(0.478 \frac{\text{Btu}}{\# \text{ } ^\circ\text{F}}) * [1] ^\circ\text{F} - 36.8 \frac{\text{Btu}}{\#} \right]}{(\text{DRY RAW SHALE, TPH})} < \textcircled{3} - 430 >$$

$$\text{LATENT HEAT FISCHER ASSAY H}_2\text{O} = \frac{T [1] = \text{OFF GAS } T ^\circ\text{F}}{100} = \frac{[(\text{Raw shale wt\%}) + (\text{Raw Shale wt\%}) * (\frac{2000 \#}{\text{Ton}}) * 1250 \frac{\text{Btu}}{\#}]}{\text{F.A. H}_2\text{O} \quad \text{LAB MOISTURE}} < \textcircled{3} - 460 >$$

CARBONATE DECOMPOSITION

$$= \frac{(2000 \frac{\#}{\text{ton}})}{100 \quad (44 \frac{\#}{\text{mole}})} * \left[(\text{Raw shale min. CO}_2, \text{ wt\%}) - \frac{(\text{Ret shale min CO}_2, \text{ wt\%}) * (\text{Ret shale, TPH})}{(\text{Dry Raw Shale, TPH})} \right] < \textcircled{3} - 490 \rightarrow 497 >$$

If the carbonate decomposition, measured as # mole CO₂/ton, is less than or equal to 2.5, multiply amount liberated by 58,835 Btu/# mole as the heat of decomposition of MgCO₃. It is assumed that all carbonate decomposition in excess of 2.5 # mole/ton production of CO₂ is liberated from the decomposition of CaCO₃, whose heat of decomposition is 75,096 Btu/# mole.

$$\text{PYROLYSIS} = (32 \text{ Btu/\#}) * (2000 \frac{\#}{\text{Ton}}) - 530$$

Btu/T

$$\text{COOLING H}_2\text{O} = \frac{(\text{Cooling Water, } T ^\circ\text{F}) * (\text{Cooling Water, GPM}) * (60 \frac{\text{Min}}{\text{Hr}}) * (8.33 \frac{\#}{\text{Gal}}) * (1 \frac{\text{Btu}}{\# \text{ } ^\circ\text{F}})}{(\text{Dry Raw Shale, TPH})} < \textcircled{3} - 158 >$$

Btu/T

$$\text{LIQ H}_2\text{O OFF AS GAS} = \frac{(\text{H}_2\text{O Collected GPH}) * (8.33 \frac{\#}{\text{Gal}}) * \left[0.417 \frac{\text{Btu}}{\# \text{ } ^\circ\text{F}} * T [1] ^\circ\text{F} - 32.1 \frac{\text{Btu}}{\#} \right]}{(\text{Dry Raw Shale, TPH})} < \textcircled{3} - 520 >$$

$$\text{SKIN LOSSES} = 10,000 \text{ Btu/Ton} < \textcircled{3} - 585 >$$

Btu/T

TABLE 7-8 (Contd)

$$\text{DIFFERENCE} = \sum \text{HEAT INPUTS} - \sum \text{HEAT OUTPUTS} < \textcircled{3} - 600 >$$

Btu/Ton

$$\text{TOTAL HEAT IN} = \text{COMBUSTION REACTIONS} + \text{AIR IN} + \text{SHALE IN} + \text{GAS IN.} < \textcircled{3} - 570 >$$

Btu/Ton

$$\text{TOTAL HEAT OUT} = \text{RET. SHALE OUT} + \text{OIL MIST OUT} + \text{LATENT HT FA H}_2\text{O} + \text{CARBONATE DECOMPOSITION} + \text{PYROLYSIS} \\ + \text{COOLING WATER} + \text{LIQUID WATER OFF AS GAS} + \text{SKIN LOSSES} < \textcircled{3} - 590 >$$

YIELD CALCULATIONS

$$\text{OIL COLLECTED} = \frac{(\text{PROD OIL GPH}) * 100}{(\text{DRY RAW SHALE, } \frac{\#}{\text{min}}) * (\text{60 Min}) (\frac{\text{Ton}}{\text{Hr}}) * (\text{RAW SHALE F.A., } \frac{\text{GAL}}{\text{TON}})} < \textcircled{1} - 685 >$$

VOL% FISCHER ASSAY

$$\text{OIL COLLECTED} = \frac{(\text{PROD OIL, GPH}) * (\text{OIL DENSITY } \frac{\#}{\text{GAL}}) * 100}{(\text{Raw Shale F.A. Oil, Wt\%}) * (\text{Lab Moist: } \frac{\text{Shale } \#}{\text{Min}})} < \textcircled{1} - 690 >$$

WT% FISCHER ASSAY

NOTE: The vol% F.A. calculation is based on dry shale,
the wt% F.A. calculation is based on lab moist
shale which includes the wt% lab moisture.

$$\text{CARBONATE DECOMPOSITION} = \frac{[(\text{Raw shale min CO}_2, \text{ Wt\%}) - (\text{Ret shale min CO}_2, \text{ wt\%}) * (\text{Ret shale, TPH})]}{(\text{Raw shale, TPH})} * 100 < \textcircled{3} - 900, 910 >$$

Wt%

(Raw shale min CO₂, wt%)

$$\begin{aligned}
 \text{CARBONATE DECOMPOSITION} &= \left[\frac{(\text{LTA SPITE WTH CO}_3' \text{ MTS}) - (\text{MTC SPITE WTH CO}_3' \text{ MTS}) + (\text{BMS SPITE' LTR})}{(\text{LTA SPITE' LTR})} \right] \cdot 100 < \textcircled{3} - 300' \text{BYO} >
 \end{aligned}$$

SPITE WHICH INCLUDES THE MTS PER MOUNTAIN.
 CUM MTS L.Y. CALCULATION IS BASED ON THE MOUNTAIN
 NOTE: THE MTS L.Y. CALCULATION IS BASED ON THE MOUNTAIN

$$\begin{aligned}
 \text{MIS LIPCHER VERA} &= \frac{(\text{LTA SPITE L.Y. OIL' MTS}) + (\text{TRIP MOUNT SPITE' MTS})}{100} \\
 \text{OIL COLLECTED} &= \frac{(\text{LTA OIL' MTS}) + (\text{OIL MOUNT MTS}) + 100}{100} < \textcircled{1} - 880 >
 \end{aligned}$$

$$\begin{aligned}
 \text{MIS LIPCHER VERA} &= \frac{(\text{LTA SPITE L.Y. OIL' MTS}) + (\text{TRIP MOUNT SPITE' MTS})}{100} \\
 \text{OIL COLLECTED} &= \frac{(\text{LTA OIL' MTS}) + (\text{OIL MOUNT MTS}) + 100}{100} < \textcircled{1} - 880 >
 \end{aligned}$$

$$\begin{aligned}
 \text{MIS LIPCHER VERA} &= \frac{(\text{LTA SPITE L.Y. OIL' MTS}) + (\text{TRIP MOUNT SPITE' MTS})}{100} \\
 \text{OIL COLLECTED} &= \frac{(\text{LTA OIL' MTS}) + (\text{OIL MOUNT MTS}) + 100}{100} < \textcircled{1} - 880 >
 \end{aligned}$$

$$\begin{aligned}
 \text{MIS LIPCHER VERA} &= \frac{(\text{LTA SPITE L.Y. OIL' MTS}) + (\text{TRIP MOUNT SPITE' MTS})}{100} \\
 \text{OIL COLLECTED} &= \frac{(\text{LTA OIL' MTS}) + (\text{OIL MOUNT MTS}) + 100}{100} < \textcircled{1} - 880 >
 \end{aligned}$$

$$\begin{aligned}
 \text{MIS LIPCHER VERA} &= \frac{(\text{LTA SPITE L.Y. OIL' MTS}) + (\text{TRIP MOUNT SPITE' MTS})}{100} \\
 \text{OIL COLLECTED} &= \frac{(\text{LTA OIL' MTS}) + (\text{OIL MOUNT MTS}) + 100}{100} < \textcircled{1} - 880 >
 \end{aligned}$$

SPITE 1-8 (contd)

TABLE 7-9

H(6)
UNIT 2 RUN 20 TEST 1.15916 MADDYV 0 HRS 303 0
F(9)
DRY SH,TPH 11.17 MOIST.% 0.96 FA,GPT 27.2 FA OIL,WT% 10.39
FA H2O 1.66 FA G+L 2.29 MIN CO2 17.71 ASH 66.93 LAB MOIST 0.71
Y(8)
RET,SH,TPH 9.15166 FA GPT 0.28 MIN CO2 15.86 ASH 82.28
H2O IN OIL,WT% 4.8 DRY OIL,GPH 290.69 H2O LIQ,GPH 12.95 API 21.4
R(5)
BTM GAS,SCFM 2255 MID 245 TOP 254 PROD 1340 H2O PPH 0
A(4)
BTM AIR,SCFM 0 MID 158 TOP 709 1.016
T(6)
OFF GAS,F 145 GAS BL DIS 241 RET SH 384 AIR BL DIS 184
PROD OIL 139 SHALE IN 36
G(14),ALL MOL%
H2 2.07 H2 54.20 O2 0.01 CO 2.08 CH4 1.82 CO2 19.99
C2H4 0.55 C2H6 0.51 C3H8 0.59 C4H8 0.30 0.00 H2O,G 17.55
COND.OIL 0.34 0.30
P(15)
BARO 23.94 RAWMO 17.05 H 1.84 H 0.51 RET C 6.3 H 0.17 basis
N 0.21 OIL C 84.62 H 11.5 N 2 CWDT 18 GPM 80
MAT. BAL. PROG. LOADED. COPYRIGHT 1975,PARAHO DEV.CORP
NOW RUN70

BALANCES	IN	OUT	UNITS	FR.REC.
ATM. NITROGEN	684.93	726.29	SCFM	1.060
ASH	250.98	251.00	#/MIN	1.000
OXYGEN	182.07	181.94	SCFM	0.999
		81.53 TO H2O		
		100.41 TO CO&CO2		
WATER	17.53	12.97	#/MIN	0.738
	9.83 S	1.80 L		
	6.43 C	11.17 V		
KEROGEN	51.37	53.82	#/MIN	1.048
		5.67 S		
		37.35 O		
		10.79 G		
ORGANIC CARBON	45.32	46.44	#/MIN	1.013
		6.02 S		
		31.60 O		
		8.81 G		
TOT. HYDROGEN	6.90	7.40	#/MIN	1.073
		0.52 S		
		4.30 O		
		2.59 G+H2O		
ORG. NITROGEN	1.91	1.39	#/MIN	0.726
O'ALL WEIGHT	442.23	448.37	#/MIN	1.014
	3.548 #/MIN C	0.860 #/MIN H		
	95.68 VOL%FA	95.99 WT%FA		

HEAT BALANCE PROGRAM LOADED. COPYRIGHT 1975, PARAHO DEV. CORP.

BASIS: 1 TON DRY SHALE DATUM: 77 DEG F
C/H COMB RATIO 4.123
MEAN CP OFF GAS 7.887 BTU/LB-MOLE DEG F 145.000 OFF GAS TEMP
MEAN CP REC GAS 7.983 BTU/LB-MOLE DEG F 241.000 REC GAS TEMP

HEAT IN		HEAT OUT	
C+O2 TO CO2	212828	OFF GAS	31120
C+O2 TO CO	15687	RET SH OUT	111879
H2+O2 TO H2O	240265	OIL MIST OUT	6522
AIR IN	9251	LATENT HT FA H2O	65500
SHALE IN	-17007	CARBONATE DECOMP	126115
GAS IN	51132	PYROLYSIS	64000
		COOLING H2O	64433
		LIQ H2O OFF AS GAS	274
		SKIN LOSSES	10000
		DIFFERENCE	32313
TOTAL IN	512156	TOTAL OUT	512156
CARBONATE DECOMP	26.628	%	

TABLE 3-2

UNIT 1		UNIT 2		UNIT 3		UNIT 4		UNIT 5		UNIT 6		UNIT 7		UNIT 8		UNIT 9		UNIT 10		UNIT 11		UNIT 12		UNIT 13		UNIT 14		UNIT 15		UNIT 16		UNIT 17		UNIT 18		UNIT 19		UNIT 20		UNIT 21		UNIT 22		UNIT 23		UNIT 24		UNIT 25		UNIT 26		UNIT 27		UNIT 28		UNIT 29		UNIT 30		UNIT 31		UNIT 32		UNIT 33		UNIT 34		UNIT 35		UNIT 36		UNIT 37		UNIT 38		UNIT 39		UNIT 40		UNIT 41		UNIT 42		UNIT 43		UNIT 44		UNIT 45		UNIT 46		UNIT 47		UNIT 48		UNIT 49		UNIT 50		UNIT 51		UNIT 52		UNIT 53		UNIT 54		UNIT 55		UNIT 56		UNIT 57		UNIT 58		UNIT 59		UNIT 60		UNIT 61		UNIT 62		UNIT 63		UNIT 64		UNIT 65		UNIT 66		UNIT 67		UNIT 68		UNIT 69		UNIT 70		UNIT 71		UNIT 72		UNIT 73		UNIT 74		UNIT 75		UNIT 76		UNIT 77		UNIT 78		UNIT 79		UNIT 80		UNIT 81		UNIT 82		UNIT 83		UNIT 84		UNIT 85		UNIT 86		UNIT 87		UNIT 88		UNIT 89		UNIT 90		UNIT 91		UNIT 92		UNIT 93		UNIT 94		UNIT 95		UNIT 96		UNIT 97		UNIT 98		UNIT 99		UNIT 100		UNIT 101		UNIT 102		UNIT 103		UNIT 104		UNIT 105		UNIT 106		UNIT 107		UNIT 108		UNIT 109		UNIT 110		UNIT 111		UNIT 112		UNIT 113		UNIT 114		UNIT 115		UNIT 116		UNIT 117		UNIT 118		UNIT 119		UNIT 120		UNIT 121		UNIT 122		UNIT 123		UNIT 124		UNIT 125		UNIT 126		UNIT 127		UNIT 128		UNIT 129		UNIT 130		UNIT 131		UNIT 132		UNIT 133		UNIT 134		UNIT 135		UNIT 136		UNIT 137		UNIT 138		UNIT 139		UNIT 140		UNIT 141		UNIT 142		UNIT 143		UNIT 144		UNIT 145		UNIT 146		UNIT 147		UNIT 148		UNIT 149		UNIT 150		UNIT 151		UNIT 152		UNIT 153		UNIT 154		UNIT 155		UNIT 156		UNIT 157		UNIT 158		UNIT 159		UNIT 160		UNIT 161		UNIT 162		UNIT 163		UNIT 164		UNIT 165		UNIT 166		UNIT 167		UNIT 168		UNIT 169		UNIT 170		UNIT 171		UNIT 172		UNIT 173		UNIT 174		UNIT 175		UNIT 176		UNIT 177		UNIT 178		UNIT 179		UNIT 180		UNIT 181		UNIT 182		UNIT 183		UNIT 184		UNIT 185		UNIT 186		UNIT 187		UNIT 188		UNIT 189		UNIT 190		UNIT 191		UNIT 192		UNIT 193		UNIT 194		UNIT 195		UNIT 196		UNIT 197		UNIT 198		UNIT 199		UNIT 200		UNIT 201		UNIT 202		UNIT 203		UNIT 204		UNIT 205		UNIT 206		UNIT 207		UNIT 208		UNIT 209		UNIT 210		UNIT 211		UNIT 212		UNIT 213		UNIT 214		UNIT 215		UNIT 216		UNIT 217		UNIT 218		UNIT 219		UNIT 220		UNIT 221		UNIT 222		UNIT 223		UNIT 224		UNIT 225		UNIT 226		UNIT 227		UNIT 228		UNIT 229		UNIT 230		UNIT 231		UNIT 232		UNIT 233		UNIT 234		UNIT 235		UNIT 236		UNIT 237		UNIT 238		UNIT 239		UNIT 240		UNIT 241		UNIT 242		UNIT 243		UNIT 244		UNIT 245		UNIT 246		UNIT 247		UNIT 248		UNIT 249		UNIT 250		UNIT 251		UNIT 252		UNIT 253		UNIT 254		UNIT 255		UNIT 256		UNIT 257		UNIT 258		UNIT 259		UNIT 260		UNIT 261		UNIT 262		UNIT 263		UNIT 264		UNIT 265		UNIT 266		UNIT 267		UNIT 268		UNIT 269		UNIT 270		UNIT 271		UNIT 272		UNIT 273		UNIT 274		UNIT 275		UNIT 276		UNIT 277		UNIT 278		UNIT 279		UNIT 280		UNIT 281		UNIT 282		UNIT 283		UNIT 284		UNIT 285		UNIT 286		UNIT 287		UNIT 288		UNIT 289		UNIT 290		UNIT 291		UNIT 292		UNIT 293		UNIT 294		UNIT 295		UNIT 296		UNIT 297		UNIT 298		UNIT 299		UNIT 300		UNIT 301		UNIT 302		UNIT 303		UNIT 304		UNIT 305		UNIT 306		UNIT 307		UNIT 308		UNIT 309		UNIT 310		UNIT 311		UNIT 312		UNIT 313		UNIT 314		UNIT 315		UNIT 316		UNIT 317		UNIT 318		UNIT 319		UNIT 320		UNIT 321		UNIT 322		UNIT 323		UNIT 324		UNIT 325		UNIT 326		UNIT 327		UNIT 328		UNIT 329		UNIT 330		UNIT 331		UNIT 332		UNIT 333		UNIT 334		UNIT 335		UNIT 336		UNIT 337		UNIT 338		UNIT 339		UNIT 340		UNIT 341		UNIT 342		UNIT 343		UNIT 344		UNIT 345		UNIT 346		UNIT 347		UNIT 348		UNIT 349		UNIT 350		UNIT 351		UNIT 352		UNIT 353		UNIT 354		UNIT 355		UNIT 356		UNIT 357		UNIT 358		UNIT 359		UNIT 360		UNIT 361		UNIT 362		UNIT 363		UNIT 364		UNIT 365		UNIT 366		UNIT 367		UNIT 368		UNIT 369		UNIT 370		UNIT 371		UNIT 372		UNIT 373		UNIT 374		UNIT 375		UNIT 376		UNIT 377		UNIT 378		UNIT 379		UNIT 380		UNIT 381		UNIT 382		UNIT 383		UNIT 384		UNIT 385		UNIT 386		UNIT 387		UNIT 388		UNIT 389		UNIT 390		UNIT 391		UNIT 392		UNIT 393		UNIT 394		UNIT 395		UNIT 396		UNIT 397		UNIT 398		UNIT 399		UNIT 400		UNIT 401		UNIT 402		UNIT 403		UNIT 404		UNIT 405		UNIT 406		UNIT 407		UNIT 408		UNIT 409		UNIT 410		UNIT 411		UNIT 412		UNIT 413		UNIT 414		UNIT 415		UNIT 416		UNIT 417		UNIT 418		UNIT 419		UNIT 420		UNIT 421		UNIT 422		UNIT 423		UNIT 424		UNIT 425		UNIT 426		UNIT 427		UNIT 428		UNIT 429		UNIT 430		UNIT 431		UNIT 432		UNIT 433		UNIT 434		UNIT 435		UNIT 436		UNIT 437		UNIT 438		UNIT 439		UNIT 440		UNIT 441		UNIT 442		UNIT 443		UNIT 444		UNIT 445		UNIT 446		UNIT 447		UNIT 448		UNIT 449		UNIT 450		UNIT 451		UNIT 452		UNIT 453		UNIT 454		UNIT 455		UNIT 456		UNIT 457		UNIT 458		UNIT 459		UNIT 460		UNIT 461		UNIT 462		UNIT 463		UNIT 464		UNIT 465		UNIT 466		UNIT 467		UNIT 468		UNIT 469		UNIT 470		UNIT 471		UNIT 472		UNIT 473		UNIT 474		UNIT 475		UNIT 476		UNIT 477		UNIT 478		UNIT 479		UNIT 480		UNIT 481		UNIT 482		UNIT 483		UNIT 484		UNIT 485		UNIT 486		UNIT 487		UNIT 488		UNIT 489		UNIT 490		UNIT 491		UNIT 492		UNIT 493		UNIT 494		UNIT 495		UNIT 496		UNIT 497		UNIT 498		UNIT 499		UNIT 500		UNIT 501		UNIT 502		UNIT 503		UNIT 504		UNIT 505		UNIT 506		UNIT 507		UNIT 508		UNIT 509		UNIT 510		UNIT 511		UNIT 512		UNIT 513		UNIT 514		UNIT 515		UNIT 516		UNIT 517		UNIT 518		UNIT 519		UNIT 520		UNIT 521		UNIT 522		UNIT 523		UNIT 524		UNIT 525		UNIT 526		UNIT 527		UNIT 528		UNIT 529		UNIT 530		UNIT 531		UNIT 532		UNIT 533		UNIT 534		UNIT 535		UNIT 536		UNIT 537		UNIT 538		UNIT 539		UNIT 540		UNIT 541		UNIT 542		UNIT 543		UNIT 544		UNIT 545		UNIT 546		UNIT 547		UNIT 548		UNIT 549		UNIT 550		UNIT 551		UNIT 552		UNIT 553		UNIT 554		UNIT 555		UNIT 556		UNIT 557		UNIT 558		UNIT 559		UNIT 560		UNIT 561		UNIT 562		UNIT 563		UNIT 564		UNIT 565		UNIT 566		UNIT 567		UNIT 568		UNIT 569		UNIT 570		UNIT 571		UNIT 572		UNIT 573		UNIT 574		UNIT 575		UNIT 576		UNIT 577		UNIT 578		UNIT 579		UNIT 580		UNIT 581		UNIT 582		UNIT 583		UNIT 584		UNIT 585		UNIT 586		UNIT 587		UNIT 588		UNIT 589		UNIT 590		UNIT 591		UNIT 592		UNIT 593		UNIT 594		UNIT 595		UNIT 596		UNIT 597		UNIT 598		UNIT 599		UNIT 600		UNIT 601		UNIT 602		UNIT 603		UNIT 604		UNIT 605		UNIT 606		UNIT 607		UNIT 608		UNIT 609		UNIT 610		UNIT 611		UNIT 612		UNIT 613		UNIT 614		UNIT 615		UNIT 616		UNIT 617		UNIT 618		UNIT 619		UNIT 620		UNIT 621		UNIT 622		UNIT 623		UNIT 624		UNIT 625		UNIT 626		UNIT 627		UNIT 628		UNIT 629		UNIT 630		UNIT 631		UNIT 632		UNIT 633		UNIT 634		UNIT 635		UNIT 636		UNIT 637		UNIT 638		UNIT 639		UNIT 640		UNIT 641		UNIT 642		UNIT 643		UNIT 644		UNIT 645		UNIT 646		UNIT 647		UNIT 648		UNIT 649		UNIT 650		UNIT 651		UNIT 652		UNIT 653		UNIT 654		UNIT 655		UNIT 656		UNIT 657		UNIT 658		UNIT 659		UNIT 660		UNIT 661		UNIT 662		UNIT 663		UNIT 664		UNIT 665		UNIT 666		UNIT 667		UNIT 668		UNIT 669		UNIT 670		UNIT 671		UNIT 672		UNIT 673		UNIT 674		UNIT 675		UNIT 676		UNIT 677		UNIT 678		UNIT 679		UNIT 680		UNIT 681		UNIT 682		UNIT 683		UNIT 684		UNIT 685		UNIT 686		UNIT 687		UNIT 688		UNIT 689		UNIT 690		UNIT 691		UNIT 692		UNIT 693		UNIT 694		UNIT 695		UNIT 696		UNIT 697		UNIT 698		UNIT 699		UNIT 700		UNIT 701		UNIT 702		UNIT 703		UNIT 704		UNIT 705		UNIT 706		UNIT 707		UNIT 708		UNIT 709		UNIT 710		UNIT 711		UNIT 712		UNIT 713		UNIT 714		UNIT 715		UNIT 716		UNIT 717		UNIT 718		UNIT 719		UNIT 720		UNIT 721		UNIT 722		UNIT 723		UNIT 724		UNIT 725		UNIT 726		UNIT 727		UNIT 728		UNIT 729		UNIT 730		UNIT 731		UNIT 732		UNIT 733		UNIT 734		UNIT 735		UNIT 736		UNIT 737		UNIT 738		UNIT 739		UNIT 740		UNIT 741		UNIT 742		UNIT 743		UNIT 744		UNIT 745		UNIT 746		UNIT 747		UNIT 748		UNIT 749		UNIT 750		UNIT 751		UNIT 752		UNIT 753		UNIT 754		UNIT 755		UNIT 756		UNIT 757		UNIT 758		UNIT 759		UNIT 760		UNIT 761		UNIT 762		UNIT 763		UNIT 764		UNIT 765		UNIT 766		UNIT 767		UNIT 768		UNIT 769		UNIT 770		UNIT 771		UNIT 772		UNIT 773		UNIT 774		UNIT 775		UNIT 776		UNIT 777		UNIT 778		UNIT 779		UNIT 780		UNIT 781		UNIT 782		UNIT 783		UNIT 784		UNIT 785		UNIT 786		UNIT 787		UNIT 788		UNIT 789		UNIT 790		UNIT 791		UNIT 792		UNIT 793		UNIT 794		UNIT 795		UNIT 796		UNIT 797		UNIT 798		UNIT 799		UNIT 800		UNIT 801		UNIT 802		UNIT 803		UNIT 804		UNIT 805		UNIT 806		UNIT 807		UNIT 808		UNIT 809		UNIT 810		UNIT 811		UNIT 812		UNIT 813		UNIT 814		UNIT 815		UNIT 816		UNIT 817		UNIT 818		UNIT 819		UNIT 820		UNIT 821		UNIT 822		UNIT 823		UNIT 824		UNIT 825		UNIT 826		UNIT 827		UNIT 828		UNIT 829		UNIT 830		UNIT 831		UNIT 832		UNIT 833		UNIT 834		UNIT 835		UNIT 836		UNIT 837		UNIT 838		UNIT 839		UNIT 840		UNIT 841		UNIT 842		UNIT 843		UNIT 844		UNIT 845		UNIT 846		UNIT 847		UNIT 848		UNIT 849		UNIT 850		UNIT 851		UNIT 852		UNIT 853		UNIT 854		UNIT 855		UNIT 856		UNIT 857		UNIT 858		UNIT 859		UNIT 860		UNIT 861		UNIT 862		UNIT 863		UNIT 864		UNIT 865		UNIT 866		UNIT 867		UNIT 868		UNIT 869		UNIT 870		UNIT 871		UNIT 872		UNIT 873		UNIT 874		UNIT 875		UNIT 876		UNIT 877		UNIT 878		UNIT 879		UNIT 880		UNIT 881		UNIT 882		UNIT 883		UNIT 884		UNIT 885		UNIT 886		UNIT 887		UNIT 888		UNIT 889		UNIT 890		UNIT 891		UNIT 892		UNIT 893		UNIT 894		UNIT 895		UNIT 896		UNIT 897		UNIT 898		UNIT 899		UNIT 900		UNIT 901		UNIT 902		UNIT 903		UNIT 904		UNIT 905		UNIT 906		UNIT 907		UNIT 908		UNIT 909		UNIT 910		UNIT 911		UNIT 912		UNIT 913		UNIT 914		UNIT 915		UNIT 916		UNIT 917		UNIT 918		UNIT 919		UNIT 920		UNIT 921		UNIT 922		UNIT 923		UNIT 924		UNIT 925		UNIT 926		UNIT 927		UNIT 928		UNIT 929		UNIT 930		UNIT 931		UNIT 932		UNIT 933		UNIT 934		UNIT 935		UNIT 936		UNIT 937		UNIT 938		UNIT 939		UNIT 940		UNIT 941		UNIT 942		UNIT 943		UNIT 944		UNIT 945		UNIT 946		UNIT 947		UNIT 948		UNIT 949		UNIT 950		UNIT 951		UNIT 952		UNIT 953		UNIT 954		UNIT 955		UNIT 956		UNIT 957		UNIT 958		UNIT 959		UNIT 960		UNIT 9	
--------	--	--------	--	--------	--	--------	--	--------	--	--------	--	--------	--	--------	--	--------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	---------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	----------	--	--------	--

7.3 INDIRECT HEATED MODE

A flow chart of the Indirect Heated Mode material balance is presented in Figure 7-4. The program listing for Part 1 is presented in Table 7-10 and for Part 2 in Table 7-11. There are no combustion calculations in this balance. In view of this, the water balance is slightly modified from the basis used for the Direct Heated Mode material balance. The material balance excludes recycle gas streams. The calculated data array is shown in Table 7-12.

The partial balances and the overall balance are discussed in Table 7-13 (5 pages).

ALTERNATE MATERIAL BALANCE - C₅+ LIQ. BASIS

A slightly different Indirect Heated Mode material balance is used to calculate C₅+ Liquid Basis Yield. Table 7-14 is the program listing for Part 1 and Table 7-15 lists Part 2. See Table 7-16 for the principal factors in C₅+ liquid yield calculations.

HEAT BALANCE

The flow chart of the heat balance for the Indirect Heated Mode is presented as Figure 7-6. The program listing is Table 7-17 (five pages). Some of these calculations are explained in Table 7-18 (2 pages).

A flow chart of the Indirect Heated Mode material balance is presented in Figure 7-4. The program listing for Part I is presented in Table 7-10 and for Part II in Table 7-11. There are no combustion calculations in this balance. In view of this, the water balance is slightly modified from the basis used for the Direct Heated Mode material balance. The material balance excludes recycle gas streams. The calculated data array is shown in Table 7-12.

The partial balances and the overall balance are discussed in Table 7-13 (2 pages).


ALTERNATE MATERIAL BALANCE - C₂ + L₁₀ BASIS

A slightly different Indirect Heated Mode material balance is used to calculate C₂ + Liquid Basis Yield. Table 7-14 is the program listing for Part I and Table 7-15 lists Part II. See Table 7-16 for the principal factors in C₂ + liquid yield calculations.

HEAT BALANCE

The flow chart of the heat balance for the Indirect Heated Mode is presented as Figure 7-6. The program listing is Table 7-17 (five pages). Some of these calculations are explained in Table 7-18 (2 pages).

INDIRECT HEATED MODE MATERIAL BALANCE COMPUTER PROGRAM FLOW CHART Figure 7-4



INDIRECT MODE MATERIAL BALANCE PART 2

INDIRECT MODE MATERIAL BALANCE PART 1

TABLE 7-10

```

10 COM HSI[6],FS[9],Y5[8],RS[5],TS[9],GS[15],PS[13],CS[10,10]
30 PRINT
40 PRINT "MAT. BAL. PROG. LOADED. COPYRIGHT 1976,PARAHO DEV.CORP"
50 C[1,2]=R[5]
60 C[1,1]=F[1]*2000/50
70 C[1,3]=Y[1]*2000/50
80 C[7,2]=Y[7]/60*8.33
160 C[6,9]=C[1,1]*100/(100-F[9])
170 C[1,9]=C[6,9]*(F[5]-F[9])/100+(C[1,1]*F[2])/(100-F[2])
180 C[7,1]=Y[6]/60*8.33+141.5/(Y[8]+131.5)
190 FOR I=1 TO 10
200 C[9,I]=R[4]*G[I]/100
210 NEXT I
220 FOR I=5 TO 9
230 C[7,I]=R[4]*G[I+5]/100
240 NEXT I
260 FORMAT F8.2,5X,F8.2,12X,F15.3
270 FORMAT 27X,F8.2,4,F3.0
280 PRINT "BALANCES", "IN", "OUT", "UNITS", "FR.REC."
290 PRINT
300 C[1,7]=C[6,9]*F[3]/100
310 C[1,8]=C[1,3]*Y[4]/100
320 WRITE (15,260)"ASH", C[1,7],C[1,8],"#/MIN",C[1,8]/C[1,7]
340 C[1,10]=C[7,2]+C[7,7]*18.02/379.3
350 WRITE (15,260)"WATER", C[1,9],C[1,10],"#/MIN",C[1,10]/C[1,9]
360 FORMAT 27X,F8.2,4,"L"
370 WRITE (15,360)C[7,2]
380 FORMAT 27X,F8.2,4,"V"
390 WRITE (15,380)C[7,7]*18.02/379.3
420 C[2,8]=(100-F[8]-F[7]-F[5])*C[6,9]/100
430 C[2,9]=(C[9,1]*2.02+C[9,5]*16.04+C[9,7]*28.05+C[9,8]*30.07)/379.3
440 C[2,9]=C[2,9]+(C[9,9]*42.67+C[9,10]*56.99+C[7,5]*72.15+C[7,6]*34.08)/379.3
450 C[2,9]=C[2,9]+(C[7,8]*144+C[7,9]*17.03+C[9,6]*44.01+C[9,4]*28.01)/379.3
460 C[2,9]=C[2,9]+C[1,3]*(100-Y[4]-Y[3])/100+C[7,1]
470 C[2,9]=C[2,9]-(F[7]*C[6,9]-Y[3]*C[1,3])/100
480 WRITE (15,260)"KEROGEN", C[2,8],C[2,9],"#/MIN",C[2,9]/C[2,8]
490 WRITE (15,270)C[1,3]*(100-Y[4]-Y[3])/100,"S"
500 WRITE (15,270)C[7,1],"O"
510 WRITE (15,270)C[2,9]-(C[1,3]*(100-Y[4]-Y[3])/100)-C[7,1],"G"
520 LINK 4
530 END

```


INDIRECT MODE MATERIAL BALANCE PART 2

TABLE 7-11

```

10 COM HSI[6],FSI[9],YI[8],RSI[5],TSI[9],GSI[15],PSI[13],CSI[10,10]
20 FORMAT F8.2,5X,F8.2,12X,F15.3
30 FORMAT 27X,F8.2,X,F3.0
40 FORMAT F8.2,2X,F8.2,2X,F8.2,2X,F8.2
50 DISP "NOW RUN 70"
70 IF PI[2]=0 THEN 330
80 IF PI[5]=0 THEN 330
90 IF PI[8]=0 THEN 330
100 CI[6,7]=CI[6,9]*(PI[2]-FI[7]*12.01/44.01)/100
110 CI[6,8]=(CI[1,3]*(PI[5]-YI[3]*12.01/44.01)+CI[7,1]*PI[8])/100
120 CI[6,8]=CI[6,8]+(CI[9,5]*12.01+CI[9,7]*24.02+CI[9,8]*24.02+CI[9,9]*36.03)/379.3
130 CI[6,8]=CI[6,8]+(CI[7,5]*60.06+CI[9,10]*48.04+CI[7,8]*120)/379.3
140 CI[6,8]=CI[6,8]+(CI[9,6]+CI[9,4])*12.01/379.3
150 CI[6,8]=CI[6,8]-12.01/44.01/100*(FI[7]*CI[6,9]-YI[3]*CI[1,3])
160 WRITE (15,20)"ORG. CARBON ",CI[6,7],CI[6,8],"/MIN",CI[6,8]/CI[6,7]
170 WRITE (15,30)CI[1,3]*(PI[5]-YI[3]*12.01/44.01)/100,"S"
180 WRITE (15,30)CI[7,1]*PI[8]/100,"0"
190 WRITE (15,30)CI[6,8]-(CI[1,3]*(PI[5]-YI[3]*12.01/44.01)+CI[7,1]*PI[8])/100,"G"
200 CI[3,3]=CI[6,9]*(PI[3]-FI[5]*2.02/18.02)/100
210 CI[3,4]=(CI[7,1]*PI[9]+CI[1,3]*PI[6])/100
220 CI[3,4]=CI[3,4]+(CI[9,1]*2.02+CI[9,5]*4.03+CI[9,7]*4.03+CI[9,8]*6.05)/379.3
240 CI[3,4]=CI[3,4]+(CI[9,9]*6.64+CI[9,10]*8.95+CI[7,5]*12.09+CI[7,6]*2.02)/379.3
250 CI[3,4]=CI[3,4]+(CI[7,8]*24+CI[7,9]*3.02)/379.3
260 WRITE (15,20)"ORG. HYDROGEN ",CI[3,3],CI[3,4],"/MIN",CI[3,4]/CI[3,3]
270 WRITE (15,30)CI[1,3]*PI[6]/100,"S"
280 WRITE (15,30)CI[7,1]*PI[9]/100,"0"
290 WRITE (15,30)CI[3,4]-CI[1,3]*PI[6]/100-CI[7,1]*PI[9]/100,"G"
300 CI[3,5]=CI[6,9]*PI[4]/100
310 CI[3,6]=(CI[7,1]*PI[10]+CI[1,3]*PI[7]+CI[7,9]*14.01/3.793)/100
320 WRITE (15,20)"ORG. NITROGEN ",CI[3,5],CI[3,6],"/MIN",CI[3,6]/CI[3,5]
330 CI[2,3]=CI[1,1]*(1+FI[2]/(100-FI[2]))
340 CI[2,4]=RI[4]*CI[1,2]*28.97/379.3+CI[7,1]
350 CI[2,4]=CI[2,4]+CI[7,2]+CI[1,3]
360 WRITE (15,20)"O'ALL WEIGHT ",CI[2,3],CI[2,4],"/MIN",CI[2,4]/CI[2,3]
370 PRINT
380 CI[6,5]=100*(141.5/(131.5+YI[8])*8.33*YI[6]/60)/(FI[4]/100*CI[6,9])
390 CI[6,4]=YI[6]/(CI[6,9]*60/2000*FI[3])*100
400 CI[7,3]=CI[6,9]*FI[7]
410 CI[7,4]=CI[1,3]*YI[3]
420 CI[7,10]=(CI[7,3]-CI[7,4])*100/CI[7,3]
430 WRITE (15,40)CI[6,4],"/VOL%FA",CI[6,5],"/WT.%FA",CI[7,10],"/% CARB DEC"
440 PRINT
445 LINK 5
450 END

```


CALCULATED DATA ARRAY FOR INDIRECT HEATED MODE BALANCE

TABLE 7-12

J

C(10,10)

	1	2	3	4	5	6	7	8	9	10
1	Raw Shale Dry #/min	S.G. Wet Gas (as re- ported)	RETORTED SHAPE #/min.				ASH IN #/min	ASH OUT #/min	H ₂ O IN #/min	H ₂ O OUT #/min.
2			TOTAL WT IN #/min	TOTAL WT OUT #/min.				KEROGEN IN #/Min.	KEROGEN OUT #/Min.	
3			TOTAL H ₂ IN #/min	TOTAL H ₂ OUT #/Min.	ORGANIC N ₂ IN #/min	ORGANIC N ₂ OUT 3/min.				
4										
5	HEAT IN RAW SHALE BTU/TON	HEAT IN OIL COND. BTU/TON	HEAT IN RECL. GAS BTU/TON		HEAT OUT OFF GAS BTU/TON	HEAT OUT RET.SHALE BTU/TON	HEAT OUT OIL MIST BTU/TON	HEAT OUT H ₂ O VAP. BTU/TON	HEAT OUT CARB.DEC. BTU/TON	HEAT OUT H ₂ O VAPOR BTU/TON
6	TOTAL HEAT IN BTU/TON	TOTAL HEAT OUT BTU/Tn	HEAT DIFFER. BTU/TON	YIELD VOL% F.A.	YIELD WT% F.A.		ORGANIC C IN #/Min.	ORGANIC C OUT #/Min	MOIST RAW SHAPE #/Min	REC.COND. H ₂ O OUT #/Min
7	PRODUCT OIL #/Min	H ₂ O w/oil #/min	MINERAL CO ₂ IN #/Min	MINERAL CO ₂ OUT #/min.	C ₅ OUT IN PRODUCT GAS SCFM	H ₂ S OUT IN PROD. GAS SCFM	H ₂ O OUT IN PROD. GAS SCFM	OIL OUT IN PROD. GAS SCFM	NH ₃ OUT IN PROD. GAS SCFM	CARBONATE DECOMP. %
8										
9	H ₂ OUT IN PROD. GAS SCFM	N ₂ OUT IN PROD. GAS SCFM	O ₂ OUT IN PROD. GAS SCFM	CO OUT IN PROD. GAS SCFM	CH ₄ OUT IN PROD. GAS SCFM	CO ₂ OUT IN PROD. GAS SCFM	C ₂ H ₄ OUT IN PROD. GAS SCFM	C ₂ H ₆ OUT IN PROD. GAS. SCFM	C ₃ 's OUT IN PROD. GAS SCFM	C ₄ 's OUT IN PROD. GAS SCFM

01101101

1	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484	1485	1486	1487	1488	1489	1490</
---	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	--------

TABLE 7-13
BASIS: 1 TON DRY SHALE

INDIRECT MATERIAL BALANCE

ASH BALANCE

$$\text{ASH IN \#/min.} = \left[\frac{(\text{dry raw shale in, \#/min})(100)}{(100 - \text{wt.\% lab moisture})} \right] \left[\frac{(\text{wt.\% ash in raw shale})}{100} \right]$$

↑
to convert from dry to wet basis

$$\text{ASH OUT \#/min.} = (\text{retorted shale out, \#/min}) \frac{(\text{wt.\% ash in retorted shale})}{100}$$

KEROGEN BALANCE

$$\text{KEROGEN IN \#/min} = (100 - \text{wt\% ash} - \text{wt\% mineral CO}_2 - \text{wt\% Fischer Assay H}_2\text{O}) \times \left[\frac{(\text{dry raw shale in, \#/min})(100)}{(100 - \text{wt\% lab moisture})} \right]$$

$$\text{KEROGEN OUT \#/min} = \frac{(\text{product gas, SCFM})}{(379.3 \text{ SCF/\# mol})(100)} \sum_i (\text{volume \% of comp. } i)(\text{M.W. of comp. } i)$$

where i is all gas componenets
except N₂, O₂ and H₂O

$$+ (\text{retorted shale out, \#/min}) \frac{(100 - \text{wt\% mineral CO}_2 - \text{wt\% ash})}{100} + (\text{product oil, \#/min})$$

$$- \left[\frac{(\text{wt\% mineral CO}_2)(\text{raw shale in, \#/min})(100) - (\text{wt\% mineral CO}_2)(\text{retorted shale out, \#/min})}{(100 - \text{wt\% lab moisture})} \right]$$

100

↗
adjustment to 1st term for release of mineral CO₂

TABLE 7-13 (Contd)

WATER BALANCE

$$\text{WATER IN \#/min} = \left[\frac{(\text{dry raw shale in, \#/min}) (100)}{(100 - \text{wt\% lab moisture})} \right] \frac{(\text{Fischer Assay wt\% H}_2\text{O} - \text{lab moisture wt\% net})}{100}$$

$$+ \frac{(\text{dry raw shale in, \#/min}) (\text{tylab moisture, wt\%})}{(100 - \text{tylab moisture, wt\%})}$$

$$\text{WATER OUT \#/min} = (\text{H}_2\text{O out in oil \& condensate, \#/min}) + \frac{(\text{product gas, SCFM}) (\text{Volume \% H}_2\text{O}) (18.2\text{\#/mole})}{(100) (379.3 \text{ SCF/\# mol})}$$

NOTE:

It is assumed that the retorted shale is totally water-free. This was confirmed by several specially handled retorted shale samples.

(Bjncd) EI-T EIGAT

SCHEMATIC

$$WATER IN EIGAT = \left[\frac{(100 - \text{WATER IN EIGAT})}{(100 - \text{WATER IN EIGAT})} \right] \times \left[\frac{(1001 \text{ TONNE/HR OF WATER IN EIGAT})}{(1001 \text{ TONNE/HR OF WATER IN EIGAT})} \right]$$

(WATER IN EIGAT) (WATER IN EIGAT) (WATER IN EIGAT)

$$\text{WATER IN EIGAT} = \frac{(1001 \text{ TONNE/HR OF WATER IN EIGAT})}{(1001 \text{ TONNE/HR OF WATER IN EIGAT})} \times \left[\frac{(1001 \text{ TONNE/HR OF WATER IN EIGAT})}{(1001 \text{ TONNE/HR OF WATER IN EIGAT})} \right]$$

WATER IN EIGAT = 1001 TONNE/HR OF WATER IN EIGAT

TABLE 7-13 (Contd)

TOTAL HYDROGEN BALANCE

$$\text{TOTAL HYDROGEN IN \#/min} = \frac{(\text{dry raw shale in, \#/min})}{(100 - \text{wt\% lab moisture})} \left[\frac{(\text{wt\% H}_2 \text{ in raw shale}) - (\text{wt\% lab moisture}) 2.02/18.02}{100} \right]$$

$$+ \left[\frac{(\text{dry raw shale in, \#/min}) (\text{wt\% ty lab moisture})}{(100 - \text{wt\% ty lab moisture})} \right] \frac{2.02}{18.02}$$

$$\text{TOTAL HYDROGEN OUT \#/min} = \frac{(\text{product oil out, \#/min}) (\text{wt\% H in oil}) + (\text{retorted shale out \#/min}) (\text{Wt\% H in retorted shale})}{100}$$

$$+ (\text{H}_2\text{O in product oil and condensate, \#/min}) \left(\frac{2.02}{18.02} \right)$$

$$+ \frac{(1.01 \text{ \#H/\#mol}) (\text{product gas, SCFM})}{(100) (379.3 \text{ SCF/\# mol})} \sum_i (\text{volume \% of H bearing Gas comp. i}) (\text{No. of H atoms in comp. i})$$

↑
summed over all hydrogen bearing components

TABLE 1-13 (CONT'D)

SWATH BATHYMETRY DATA

$$100 \left[\frac{50.81 \sqrt{50.5} (\text{swath delay} - \text{swath delay at 0 ft}) - (\text{swath delay at 0 ft})}{100 - \text{swath delay at 0 ft}} \right] + \text{swath delay at 0 ft}$$

$$\left[\frac{18.05}{5.05} \left(\frac{\text{swath delay} - \text{swath delay at 0 ft}}{100 - \text{swath delay at 0 ft}} \right) + \text{swath delay at 0 ft} \right]$$

100

$$\left(\frac{18.05}{5.05} \right) (\text{swath delay} - \text{swath delay at 0 ft}) + \text{swath delay at 0 ft}$$

$$\left(\frac{18.05}{5.05} \right) (\text{swath delay} - \text{swath delay at 0 ft}) + \text{swath delay at 0 ft}$$

swath delay at 0 ft

TABLE 7-13 (Contd)

ORGANIC CARBON BALANCE

$$\text{ORGANIC CARBON IN \#/min} = \left[\frac{(\text{dry raw shale in, \#/min})(100)}{(100 - \text{wt\% lab moisture})} \right] \left[\frac{(\text{wt\% C in raw shale}) - (\text{wt\% mineral CO}_2) \frac{12.01}{44.01}}{100} \right]$$

$$\text{ORGANIC CARBON OUT \#/min} = (\text{retorted shale, \#/min}) \left[(\text{wt\% C in retorted shale}) - (\text{wt\% mineral CO}_2) \frac{12.01}{44.01} \right]$$

$$+ (\text{product oil, \#/min}) (\text{wt\% C in oil})$$

$$+ \frac{(12.01 \frac{\text{\#C}}{\text{\#mol}}) (\text{product gas, SCFM})}{(379.3 \text{ SCF/\#mol}) (100)} \sum_i (\text{Volume \% of C bearing gas comp. i}) (\text{No. of Carbons in comp. i})$$

↑ summed over all carbon bearing
gas components

$$- \frac{(12.01)}{(44.01) (100)} \left[(\text{wt\% mineral CO}_2) \frac{(\text{dry raw shale in, \#/min}) (100)}{(100 - \text{wt\% lab moisture})} - (\text{wt\% mineral CO}_2) (\text{retorted shale out, \#/min}) \right]$$

↖
adjustment to remove mineral CO₂ from
organic carbon balance.

CARBONATE DECOMPOSITION

$$\text{CARBONATE DECOMPOSITION WT\%} = \frac{[(\text{dry raw shale, \#/min}) (100) (\text{wt\% mineral CO}_2) - (\text{retorted shale, \#/min}) (\text{wt\% mineral CO}_2)] (100)}{(\text{dry raw shale, \#/min}) (100) (\text{wt\% mineral CO}_2) (100 - \text{wt\% lab moisture})}$$

WESTON BOND

FLUORESCENT

25% COTTON FIBER

TABLE 7-13 (Contd)

ORGANIC NITROGEN BALANCE

$$\text{ORGANIC NITROGEN IN \#/min} = \frac{(\text{dry raw shale in, \#/min})(100)}{(100 - \text{wt\% lab moisture})} \frac{(\text{wt\% N in raw shale})}{(100)}$$

$$\text{ORGANIC NITROGEN OUT \#/min} = \left[\begin{aligned} &(\text{product oil, \#/min})(\text{wt\% N in oil}) + (\text{retorted shale, \#/min})(\text{wt\% N in shale}) \\ &+ (\text{NH}_3 \text{ in product gas, SCFM}) \left(14.01 \frac{\# \text{ N}}{\# \text{ mol}} \right) \left(\frac{3.793 \text{ HSCF}}{\# \text{ mol}} \right) \end{aligned} \right] \frac{100}{100}$$

OVERALL BALANCE

$$\text{TOTAL WEIGHT IN \#/min} = (\text{dry raw shale in, \#/min}) \left[1 + \frac{(\text{tylab moisture, wt\%})}{(100 - \text{tylab moisture, wt\%})} \right]$$

$$\text{TOTAL WEIGHT OUT \#/min} = \frac{(\text{product gas, SCFM})(\text{specific gravity of gas})(28.97)}{(379.3 \text{ SCF/\# mol})} + (\text{product oil, \#/min})$$

$$+ (\text{H}_2\text{O in oil \& condensate, \#/min}) + (\text{retorted shale, \#/min})$$

INDIRECT MOISTURE BALANCE
 FOR CS+ LIG. WASTE PART 1
 TABLE 7-14

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

10-5 to 11-5 is constant, 10-5 to 11-5 is constant, 10-5 to 11-5 is constant

INDIRECT MODE MATERIAL BALANCE

for C5+ LIQ. BASIS PART 1

TABLE 7-14

```

10 COM HSI(6),FSI(9),YI(8),RSI(5),TSI(9),GSI(15),PSI(13),CSI(10,10)
20 PRINT
30 Z1=0
40 PRINT "MAT. BAL. PROG. LOADED. COPYRIGHT 1976,PARAHO DEV.CORP"
50 PRINT "INPUT VOL% LT & HEAVY NAP IN GAS, & THEIR LIQ API'S"
60 INPUT GI(11),GI(14),A1,A2
70 PRINT GI(11),GI(14),A1,A2
80 M1=504.6619-12.2636*A1+0.0921*A1^2
90 M2=504.6619-12.2636*A2+0.0921*A2^2
100 CI(7,5)=RI(4)*GI(11)/100
110 CI(7,8)=RI(4)*GI(14)/100
120 CI(4,1)=CI(7,5)/379*M1+CI(7,8)/379*M2
130 CI(4,2)=8.341*(141.5/(131.5+(GI(11)*A1+GI(14)*A2)/(GI(11)+GI(14))))
140 CI(4,3)=CI(4,1)*60/CI(4,2)
150 CI(1,2)=RI(5)
160 CI(1,1)=FI(1)*2000/60
170 CI(1,3)=YI(1)*2000/60
180 CI(7,2)=YI(7)/60*8.337
190 CI(6,9)=CI(1,1)*100/(100-FI(9))
200 CI(4,5)=CI(7,5)/379*M1*60/(8.33*(141.5/(131.5+A1)))/(CI(6,9)*60/2000)
210 CI(4,6)=CI(7,8)/379*M2*60/(8.33*(141.5/(131.5+A2)))/(CI(6,9)*60/2000)
220 CI(4,7)=(CI(7,5)*M1+CI(7,8)*M2)/379
230 PRINT "LT NAP=";CI(4,5);"GAL/TON, HEAVY NAP=";CI(4,6);"GAL/TON"
240 CI(1,9)=CI(6,9)*(FI(5)-FI(9))/100+(CI(1,1)*FI(2))/(100-FI(2))
250 CI(7,1)=YI(6)/60*8.33*141.5/(YI(8)+131.5)
260 FOR I=1 TO 10
270 CI(9,I)=RI(4)*GI(I)/100
280 NEXT I
290 FOR I=6 TO 7
300 CI(7,I)=RI(4)*GI(I+5)/100
310 IF Z1=1 THEN 350
320 NEXT I
330 I=9
340 Z1=1
350 FORMAT F8.2,5%,F3.2,12%,F15.3
360 FORMAT 27%,F8.2,%,F3.0
370 PRINT "BALANCES","IN","OUT","UNITS","FR.REC."
380 PRINT
390 CI(1,7)=CI(6,9)*FI(3)/100
400 CI(1,8)=CI(1,3)*YI(4)/100
410 WRITE (15,350)"ASH",CI(1,7),CI(1,8),"#/MIN",CI(1,8)/CI(1,7)
420 CI(1,10)=CI(7,2)+CI(7,7)*18.02/379.3
430 WRITE (15,350)"WATER",CI(1,9),CI(1,10),"#/MIN",CI(1,10)/CI(1,9)
440 FORMAT 27%,F8.2,%,F3.0
450 WRITE (15,440)CI(7,2)
460 FORMAT 27%,F8.2,%,F3.0
470 WRITE (15,460)CI(7,7)*18.02/379.3
480 CI(2,8)=(100-FI(8)-FI(7)-FI(5))*CI(6,9)/100
490 CI(2,9)=(CI(9,1)*2.02+CI(9,5)*16.04+CI(9,7)*28.05+CI(9,8)*30.07)/379.3
500 CI(2,9)=CI(2,9)+(CI(9,9)*42.67+CI(9,10)*56.99+CI(7,6)*34.08)/379.3
510 CI(2,9)=CI(2,9)+(CI(7,9)*17.03+CI(9,6)*44.01+CI(9,4)*28.01)/379.3
520 CI(2,9)=CI(2,9)+CI(1,3)*(100-YI(4)-YI(3))/100+CI(7,1)+CI(4,1)
530 CI(2,9)=CI(2,9)-(FI(7)*CI(6,9)-YI(3)*CI(1,3))/100
540 WRITE (15,350)"KEROGEN",CI(2,8),CI(2,9),"#/MIN",CI(2,9)/CI(2,8)
550 WRITE (15,360)CI(1,3)*(100-YI(4)-YI(3))/100,"S"
560 WRITE (15,360)CI(7,1)+CI(4,1),"O"
570 WRITE (15,360)CI(2,9)-(CI(1,3)*(100-YI(4)-YI(3))/100)-CI(7,1)-CI(4,1),"G"
580 LINK 7
590 END

```


INDIRECT MODE MATERIAL BALANCE
FOR C5+ LIQ. BASIS PART 2

TABLE 7-15

```

10 COM HSI[6],FS[9],YS[8],RS[5],TS[9],GS[15],PS[13],CS[10,10]
20 FORMAT F8.2,5X,F8.2,12X,F15.3
30 FORMAT 27X,F8.2,X,F3.0
40 FORMAT F8.2,2X,F8.2,2X,F8.2,2X,F8.2
50 DISP "NOW RUN 70"
70 IF P[2]=0 THEN 330
80 IF P[5]=0 THEN 330
90 IF P[8]=0 THEN 330
95 Y=C[4,1]
100 C[6,7]=C[6,9]*(P[2]-F[7]*12.01/44.01)/100
110 C[6,8]=(C[1,3]*(P[5]-Y[3]*12.01/44.01)+(C[7,1]+Y)*P[8])/100
120 C[6,8]=C[6,8]+(C[9,5]*12.01+C[9,7]*24.02+C[9,8]*24.02+C[9,9]*36.03)/379.3
130 C[6,8]=C[6,8]+(C[9,10]*48.04)/379.3
140 C[6,8]=C[6,8]+(C[9,6]+C[9,4])*12.01/379.3
150 C[6,8]=C[6,8]-12.01/44.01/100*(F[7]*C[6,9]-Y[3]*C[1,3])
160 WRITE (15,20)"ORG. CARBON ",C[6,7],C[6,8],"/MIN",C[6,8]/C[6,7]
170 WRITE (15,30)C[1,3]*(P[5]-Y[3]*12.01/44.01)/100,"S"
180 WRITE (15,30)(C[7,1]+Y)*P[8]/100,"O"
190 WRITE (15,30)C[6,8]-(C[1,3]*(P[5]-Y[3]*12.01/44.01)+(C[7,1]+Y)*P[8])/100,"G"
200 C[3,3]=C[6,9]*(P[3]-F[5]*2.02/18.02)/100
210 C[3,4]=(C[7,1]+Y)*P[9]+C[1,3]*P[6]/100
220 C[3,4]=C[3,4]+(C[9,1]*2.02+C[9,5]*4.03+C[9,7]*4.03+C[9,8]*6.05)/379.3
230 C[3,4]=C[3,4]+(C[9,9]*6.64+C[9,10]*8.95+C[7,6]*2.02)/379.3
240 C[3,4]=C[3,4]+(C[7,9]*3.02)/379.3
250 WRITE (15,20)"ORG. HYDROGEN ",C[3,3],C[3,4],"/MIN",C[3,4]/C[3,3]
270 WRITE (15,30)C[1,3]*P[6]/100,"S"
280 WRITE (15,30)(C[7,1]+Y)*P[9]/100,"O"
290 WRITE (15,30)C[3,4]-C[1,3]*P[6]/100-(C[7,1]+Y)*P[9]/100,"G"
300 C[3,5]=C[6,9]*P[4]/100
310 C[3,6]=((C[7,1]+Y)*P[10]+C[1,3]*P[7]+C[7,9]*14.01/3.793)/100
320 WRITE (15,20)"ORG. NITROGEN ",C[3,5],C[3,6],"/MIN",C[3,6]/C[3,5]
330 C[2,3]=C[1,1]*(1+F[2]/(100-F[2]))
340 C[2,4]=R[4]*C[1,2]*28.97/379.3+C[7,1]+Y
350 C[2,4]=C[2,4]+C[7,2]+C[1,3]
360 WRITE (15,20)"O'ALL WEIGHT ",C[2,3],C[2,4],"/MIN",C[2,4]/C[2,3]
370 PRINT
380 C[6,5]=100*(C[4,7]+(141.5/(131.5+Y[8])*8.33*Y[6]/60))/(F[4]/100*C[6,9])
390 C[6,4]=(Y[6]+C[4,3])/C[6,9]*60/2000*F[3]*100
400 C[7,3]=C[6,9]*F[7]
410 C[7,4]=C[1,3]*Y[3]
420 C[7,10]=(C[7,3]-C[7,4])*100/C[7,3]
430 WRITE (15,40)C[6,4],"VOL%FAC5+LIQYIELD",C[6,5],"WT.%FA",C[7,10],"% CARB DEC"
440 PRINT
445 LINK 5
450 END

```


TABLE 7-16

C5+ LIQUID YIELD CALCULATIONS

$$\text{M.W. of LIGHT NAPHTHA} = 504.66 - 12.66(\text{light naphtha } ^\circ\text{API}) + 0.0921 (\text{light naphtha } ^\circ\text{API})^2$$

$$\text{M.W. of HEAVY NAPHTHA} = 504.66 - 12.66 (\text{heavy naphtha } ^\circ\text{API}) + 0.0921 (\text{heavy naphtha } ^\circ\text{API})^2$$

$$\text{TOTAL COMBINED NAPHTHA, \#/min} = \frac{(\text{light naphtha in gas, SCFM})(\text{M.W. of light naphtha})}{(379 \text{ SCF/\#mol})} + \frac{(\text{heavy naphtha in gas, SCFM})(\text{M.W. of heavy naphtha})}{(379 \text{ SCF/\#mol})}$$

$$\text{TOTAL COMBINED NAPHTHA, gal/hr} = \frac{(\text{total combined naphtha, \#/min})(60 \text{ min/hr})}{(\text{density of combined naphtha, \#/gal})}$$

$$\text{LIGHT NAPHTHA Gal/ton} = \frac{(\text{light naphtha in gas, SCFM})(\text{M.W. of light naphtha})}{(379 \text{ SCF/\# mol})(\text{light naphtha density, \#/gal})(\text{moist raw shale in, tph})}$$

$$\text{HEAVY NAPHTHA Gal/ton} = \frac{(\text{heavy naphtha in gas, SCFM})(\text{M.W. of heavy naphtha})}{(379 \text{ SCF/\# mol})(\text{heavy naphtha density, \#/gal})(\text{moist raw shale in, tph})}$$

$$\text{VOL\% of F.A.} = \frac{(\text{dry oil, gph}) + (\text{total combined naphtha, gph})}{(\text{moist raw shale, tph})(\text{F.A. raw shale, gpt})}$$

Adjustments have also been made to the component & elemental balances to account for the differences inherent to the C5+ basis.

to the C2+ phase.

$$A_{C2+} = \frac{(C_{C2+} - C_{C2+}^{(0)})}{(C_{C2+} - C_{C2+}^{(0)})} \times 100\%$$

$$C_{C2+} = \frac{(C_{C2+} - C_{C2+}^{(0)})}{(C_{C2+} - C_{C2+}^{(0)})} \times 100\%$$

$$C_{C2+} = \frac{(C_{C2+} - C_{C2+}^{(0)})}{(C_{C2+} - C_{C2+}^{(0)})} \times 100\%$$

$$C_{C2+} = \frac{(C_{C2+} - C_{C2+}^{(0)})}{(C_{C2+} - C_{C2+}^{(0)})} \times 100\%$$

$$C_{C2+} = \frac{(C_{C2+} - C_{C2+}^{(0)})}{(C_{C2+} - C_{C2+}^{(0)})} \times 100\%$$

$$C_{C2+} = \frac{(C_{C2+} - C_{C2+}^{(0)})}{(C_{C2+} - C_{C2+}^{(0)})} \times 100\%$$


$$C_{C2+} = \frac{(C_{C2+} - C_{C2+}^{(0)})}{(C_{C2+} - C_{C2+}^{(0)})} \times 100\%$$

TABLE 1

C2+ PHASE CONCENTRATION

In Section 7.1 presented previously, the text captioned "Notes Applicable to Direct and Indirect Mode Material and Heat Balances," discusses some of the bases of calculations. Further explanation is presented in Table 7-18 in two parts.

Figure 7-5 shows the heat balance boundary and identifies the streams tabulated in the print out. Table 7-19 is a print out of input data, the material balance, and heat balance for Indirect Heated Mode Run SW-28, combined tests A-4.1 and A-4.2.



In Section 7.1 presented previously, the text captioned "Notes Applicable to Direct and Indirect Mode Material and Heat Balances," discusses some of the bases of calculations. Further explanation is presented in Table 7-18 in two parts.

Figure 7-5 shows the heat balance boundary and identifies the streams tabulated in the print out. Table 7-19 is a print out of input data, the material balance, and heat balance for indirect heated Mode Run SW-38, combined tests A-4.1 and A-4.2.





FIGURE 7.5

INDIRECT HEATED MODE HEAT BALANCE PROGRAM FLOW CHART Figure 7-6



INDIRECT HEATED MODE HEAT BALANCE

TABLE 7-17

```

10 COM HSC(6),FSC(9),Y3(8),RSC(5),TSC(9),GSC(15),PSC(13),CSC(10,10)
20 DIM S1,S2,S3,W,S5,S6,S7,S8,S9,S0,I,O,U,D,D1,D2,D3,D4,W0,W1,W2,V0,V1,Z,X
30 PRINT "HEAT BALANCE PROGRAM LOADED. COPYRIGHT 1976, PARAHQ DEV. CORP."
40 PRINT
50 FIXED 3
60 PRINT "BASIS: 1 TON DRY SHALE          DATUM: 77 DEG F"
70 D=0
80 IF P(12)=0 THEN 140
90 W0=T(5)/1000
100 W1=(0.7513-29.27*W0+506.06*W0^2-3420.7*W0^3+14844*W0^4)*29.92/14.696
110 W2=W1/(P(1)+P(11))*100
120 V0=100-G(13)
130 V1=100-W2
140 Z=T(3)/1000
150 X=G(1)*((1546.3+3401*Z+62.2*Z^2+1.29*Z^3)-1805.8)*2.02
160 X=X+G(2)*((113.8+247.8*Z+3.86*Z^2+3.82*Z^3)-133.1)*28
170 X=X+G(3)*((98.9+220.3*Z+14.3*Z^2+0.445*Z^3)-116.35)*32
180 X=X+G(4)*((113.7+248.3*Z+5.86*Z^2+3.52*Z^3)-133.1)*28
190 X=X+G(5)*((222.4+544*Z+169.2*Z^2+14.6*Z^3)-268.8)*16
200 X=X+G(6)*((76.15+195.2*Z+59.1*Z^2-10.8*Z^3)-91.48)*44
210 X=X+G(7)*((130.4+372.7*Z+201*Z^2-19*Z^3)-161.9)*28
220 X=X+G(8)*((135.9+409.4*Z+255.2*Z^2-21.4*Z^3)-170.86)*30.1
230 X=X+0.5*G(9)*((109.3+346.6*Z+233.6*Z^2-28.1*Z^3)-138.4)*42.1
240 X=X+0.5*G(9)*((111.6+377.6*Z+287.2*Z^2-36.2*Z^3)-143.27)*44.1
250 X=X+0.5*G(10)*((106.2+356.2*Z+258.7*Z^2-38.1*Z^3)-135.4)*36.1
260 X=X+0.2*G(10)*((101.9+367.9*Z+302.6*Z^2-44.6*Z^3)-132.34)*58.1
270 X=X+0.3*G(10)*((112.1+379.9*Z+284.6*Z^2-38.9*Z^3)-143.8)*58.1
280 X=X+G(11)*((110+377*Z+285.9*Z^2-40.8*Z^3)-141.3)*72.1
290 X=X+G(12)*((-7.12+229*Z+35.8*Z^2-1.33*Z^3)-10.7)*34.1
300 X=X+G(13)*((201.4+444.5*Z+21.19*Z^2+8.58*Z^3)-236.2)*18
310 X=X+G(14)*((105.3+372*Z+288.6*Z^2-45*Z^3)-136.3)*144
320 X=X+G(15)*((-15+474*Z+140*Z^2-11.3*Z^3)-22.3)*17
330 X=X/100
350 IF D=1 THEN 430
360 IF D=2 THEN 610
370 IF D=3 THEN 480
380 D1=X*R(3)*60/379/F(1)
390 Z=T(4)/1000
410 D=1
420 GOTO 150
430 D2=X*R(2)*60/379/F(1)
440 Z=T(1)/1000
460 D=3
470 GOTO 150
480 D4=X*(R(1)+R(2)+R(3)+R(4))*60/379/F(1)
510 IF P(12)=0 THEN 590
530 FOR I=1 TO 12
540 G(I)=G(I)*V1/V0
550 NEXT I
560 G(14)=G(14)*V1/V0
570 G(15)=G(15)*V1/V0
580 G(13)=W2
590 D=2
592 Z=T(5)/1000
600 GOTO 150
610 D3=X*R(1)*60/379/F(1)
620 S3=D1+D2+D3
630 S5=D4
640 S1=(4/10+5*T(8)+2+0.2068*T(6)-16)*2000
650 PRINT

```


INDIRECT HEATED MODE HEAT BALANCE (CONTD)

TABLE 7-17 (CONTD)

```

660 PRINT TAB5"          HEAT IN"TAB35"          HEAT OUT"
670 PRINT
680 FORMAT "SHALE IN",14X,F8.0,7X,"OFF GAS",15X,F8.0
690 WRITE (15,680)S1,S5
700 S6=0.2224*(T[6]-77)*2000*Y[1]/F[1]
710 FORMAT "TOP GAS IN",12X,F8.0,7X,"RET SH OUT",12X,F8.0
720 WRITE (15,710)D1,S6
730 S7=Y[6]*8.33*(141.5/(Y[8]+131.5))*(0.478*T[1]-36.8)/F[1]
740 FORMAT "MID GAS IN",12X,F8.0,7X,"OIL MIST OUT",10X,F8.0
750 WRITE (15,740)D2,S7
760 S8=(F[2]*1000/(100-F[2])+(F[5]-F[9])*1250/(100-F[9]))*2000
770 FORMAT "BOT GAS IN",12X,F8.0,7X,"H2O VAPORIZATION",6X,F8.0
780 WRITE (15,770)D3,S8
790 S2=Y[6]*8.33*141.5/(Y[8]+131.5)*70/F[1]
800 S9=2000/100*(F[7]*100/(100-F[9])-Y[3]*Y[1]/F[1])/44
810 IF S9<2.5 THEN 840
820 S9=(S9-2.5)*75095+2.5*58835
830 GOTO 850
840 S9=S9*58835
850 FORMAT "OIL CONDENSATION",6X,F8.0,7X,"CARBONATE DECOMP",6X,F8.0
860 WRITE (15,850)S2,S9
870 Z0=T[1]/1000
880 Z1=(T[1]+77)/2000
890 Z=Z0+Z1
900 Z2=Z0+2+Z1+2
910 Z3=Z0+3+Z1+3
920 S0=Y[7]*8.33*(0.4455+0.8846+0.0354*Z+0.054*Z2-0.0162*Z3)*(T[1]-77)/F[1]*3
930 X2=32*2000
940 FORMAT 37X,"PYROLYSIS",13X,F8.0
950 WRITE (15,940)X2
960 I=S1+S2+S3
970 L=10000
980 O=S0+S5+S6+S7+S8+S9+L+X2
990 U=I-O
1000 FORMAT 37X,"LIO H2O OFF AS VAPOR",2X,F8.0
1010 WRITE (15,1000)O
1020 FORMAT 37X,"SKIN LOSSES",11X,F8.0
1030 WRITE (15,1020)
1040 FORMAT 37X,"DIFFERENCE",12X,F8.0
1050 WRITE (15,1040)J
1060 FORMAT 23X,"-----",30X,"-----"
1070 WRITE (15,1060)
1080 FORMAT 10X,"TOTAL IN",4X,F8.0,17X,"TOTAL OUT",3X,F8.0
1090 WRITE (15,1080)I,O+U
1100 C[5,1]=S1
1101 C[5,2]=S2
1110 C[5,3]=S3
1120 C[5,5]=S5
1130 C[5,6]=S6
1140 C[5,7]=S7
1150 C[5,8]=S8
1160 C[5,9]=S9
1170 C[5,10]=S0
1180 C[6,1]=I
1190 C[6,2]=O
1200 C[6,3]=U
1210 PRINT
1220 PRINT
1230 STANDARD
1240 FIND 3
1250 END

```

INDIRECT HEATED MODE HEAT BALANCE (CONTD)
TABLE 7-17 (CONTD)

```

1500 END
1490 PRINT 3
1480 STRAND3
1470 PRINT
1460 PRINT
1450 CLS:J=0
1440 CLS:J=0
1430 CLS:J=0
1420 CLS:J=0
1410 CLS:J=0
1400 CLS:J=0
1390 CLS:J=0
1380 CLS:J=0
1370 CLS:J=0
1360 CLS:J=0
1350 CLS:J=0
1340 CLS:J=0
1330 CLS:J=0
1320 CLS:J=0
1310 CLS:J=0
1300 CLS:J=0
1290 CLS:J=0
1280 CLS:J=0
1270 CLS:J=0
1260 CLS:J=0
1250 CLS:J=0
1240 CLS:J=0
1230 CLS:J=0
1220 CLS:J=0
1210 CLS:J=0
1200 CLS:J=0
1190 CLS:J=0
1180 CLS:J=0
1170 CLS:J=0
1160 CLS:J=0
1150 CLS:J=0
1140 CLS:J=0
1130 CLS:J=0
1120 CLS:J=0
1110 CLS:J=0
1100 CLS:J=0
1090 CLS:J=0
1080 CLS:J=0
1070 CLS:J=0
1060 CLS:J=0
1050 CLS:J=0
1040 CLS:J=0
1030 CLS:J=0
1020 CLS:J=0
1010 CLS:J=0
1000 CLS:J=0
990 CLS:J=0
980 CLS:J=0
970 CLS:J=0
960 CLS:J=0
950 CLS:J=0
940 CLS:J=0
930 CLS:J=0
920 CLS:J=0
910 CLS:J=0
900 CLS:J=0
890 CLS:J=0
880 CLS:J=0
870 CLS:J=0
860 CLS:J=0
850 CLS:J=0
840 CLS:J=0
830 CLS:J=0
820 CLS:J=0
810 CLS:J=0
800 CLS:J=0
790 CLS:J=0
780 CLS:J=0
770 CLS:J=0
760 CLS:J=0
750 CLS:J=0
740 CLS:J=0
730 CLS:J=0
720 CLS:J=0
710 CLS:J=0
700 CLS:J=0
690 CLS:J=0
680 CLS:J=0
670 CLS:J=0
660 CLS:J=0
650 CLS:J=0
640 CLS:J=0
630 CLS:J=0
620 CLS:J=0
610 CLS:J=0
600 CLS:J=0
590 CLS:J=0
580 CLS:J=0
570 CLS:J=0
560 CLS:J=0
550 CLS:J=0
540 CLS:J=0
530 CLS:J=0
520 CLS:J=0
510 CLS:J=0
500 CLS:J=0
490 CLS:J=0
480 CLS:J=0
470 CLS:J=0
460 CLS:J=0
450 CLS:J=0
440 CLS:J=0
430 CLS:J=0
420 CLS:J=0
410 CLS:J=0
400 CLS:J=0
390 CLS:J=0
380 CLS:J=0
370 CLS:J=0
360 CLS:J=0
350 CLS:J=0
340 CLS:J=0
330 CLS:J=0
320 CLS:J=0
310 CLS:J=0
300 CLS:J=0
290 CLS:J=0
280 CLS:J=0
270 CLS:J=0
260 CLS:J=0
250 CLS:J=0
240 CLS:J=0
230 CLS:J=0
220 CLS:J=0
210 CLS:J=0
200 CLS:J=0
190 CLS:J=0
180 CLS:J=0
170 CLS:J=0
160 CLS:J=0
150 CLS:J=0
140 CLS:J=0
130 CLS:J=0
120 CLS:J=0
110 CLS:J=0
100 CLS:J=0
90 CLS:J=0
80 CLS:J=0
70 CLS:J=0
60 CLS:J=0
50 CLS:J=0
40 CLS:J=0
30 CLS:J=0
20 CLS:J=0
10 CLS:J=0
0 CLS:J=0

```


TABLE 7-18
BASIS: 1 TON DRY SHALE DATUM: 77°F

HEAT BALANCE (INDIRECT MODE)

HEAT IN:

$$\text{Oil Condensation} = \frac{(\text{Oil produced, gph}) (\text{Oil density, \#/gal}) (70 \text{ Btu/lb})}{(\text{dry raw shale, tph})} \text{ Btu/Ton}$$

$$\text{Raw Shale In} = \left[4 \times 10^{-5} (\text{temp. shale in, } ^\circ\text{F})^2 + 0.2068 (\text{temp. shale in, } ^\circ\text{F}) - 16, \text{Btu/\#} \right] (2000\#/\text{ton}) \text{ Btu/Ton}$$

$$\text{TOP GAS IN} = \left[\sum (\text{vol\% of gas comp. } i) \left(\frac{\text{enthalpy of comp. } i \text{ at top}}{\text{dist. inlet temp, Btu/\#}} \right) (\text{M.W. of comp. } i) \right] \left[\frac{(\text{top gas, SCFM}) (60 \text{ min/hr})}{(100) (379 \text{ SCF/\#mol}) (\text{dry raw shale, tph})} \right] \text{ Btu/Ton}$$

$$\text{MID GAS IN} = \left[\sum (\text{vol\% of gas comp. } i) \left(\frac{\text{enthalpy of comp. } i \text{ at mid}}{\text{dist. inlet temp, Btu/\#}} \right) (\text{M.W. of comp. } i) \right] \left[\frac{(\text{mid gas, SCFM}) (60 \text{ min/hr})}{(100) (379 \text{ SCF/\#mol}) (\text{dry raw shale, tph})} \right] \text{ Btu/Ton}$$

$$\text{BOTTOM GAS IN} = \left[\sum (\text{vol\% of gas* comp. } i) \left(\frac{\text{enthalpy of comp. } i \text{ at bottom}}{\text{gas inlet temp, Btu/\#}} \right) (\text{M.W. of comp. } i) \right] \left[\frac{(\text{bottom gas, SCFM}) (60 \text{ min/hr})}{(100) (379 \text{ SCF/\#mol}) (\text{dry raw shale, tph})} \right] \text{ Btu/Ton}$$

*where the water content of the recycle gas is adjusted for condensation that occurs in the bottom gas cooler.

HEAT OUT:

$$\text{RETORTED SHALE OUT} = \frac{(0.2224 \text{ Btu/\#}^\circ\text{F}) (\text{retorted shale temp} - 77, ^\circ\text{F}) (2000\#/\text{ton}) (\text{retorted shale, tph})}{\text{Raw shale, tph}} \text{ btu/ton}$$

$$\text{OIL MIST OUT} = \frac{(\text{oil produced, gph}) (\text{oil density \#/gal}) [0.478 (\text{off gas temp, } ^\circ\text{F}) - 36.8]}{(\text{dry raw shale, tph})} \text{ Btu/ton}$$

Heat Balance (Indirect Heated Mode) Contd.

Table 7-18 (Contd)

PYROLYSIS OUT = (32 Btu/#) (2000 #/ton)
Btu/ton

SKIN LOSSES = 10,000 Btu/ton
Btu/ton

LIQUID WATER OUT =
$$\frac{(\text{off gas temp} - 77) (\text{liquid H}_2\text{O, gph}) (8.337 \text{ #/gal}) \left[1.3301 + 0.0354 \left(\frac{\text{TDIT}}{1000} \right) + 0.054 \left(\frac{\text{TDIT}}{1000} \right)^2 - 0.0162 \left(\frac{\text{TDIT}}{1000} \right)^3 \right]}{3 (\text{dry raw shale, tph})}$$

AS VAPOR
Btu/ton

Where TDIT is top distributor inlet temperature, °F

OFF GAS =
$$\left[\sum (\text{vol\% of gas comp. i}) \left(\frac{\text{enthalpy of comp. i at off}}{\text{gas temp, Btu/\#}} \right) (\text{M.W. of comp. i}) \right] \left[\frac{(\text{off gas rate, SCFM}) (60 \text{ min/hr})}{(100) (379 \text{ SCF/\# mol}) (\text{dry raw shale in, tph})} \right]$$

Btu/Ton

H₂O
VAPORIZATION = (2000#/ton)
$$\left[\frac{(\text{tylab moisture, wt\%}) (1000 \text{ Btu/\#})}{(100 - \text{tylab moisture, wt\%})} + \frac{(\text{raw shale F.A. water, wt\%} - \text{lab moisture, wt\%}) (1250 \text{ Btu/\#})}{(100 - \text{lab moisture, wt\%})} \right]$$

Btu/ton

CARBONATE
DECOMPOSITION =
$$\frac{(2000 \text{ #/ton})}{(100) \left(44 \frac{\text{\#}}{\text{\# mol}} \right)} \left[\frac{(\text{raw shale min. CO}_2, \text{ wt\%}) (100)}{(100 - \text{lab moisture, wt\%})} - \frac{(\text{retorted shale, tph}) (\text{ret. shale min. CO}_2, \text{ wt\%})}{(\text{raw shale, tph})} \right]$$

mol

then if carbonate decomposition, measured as #mol/ton of CO₂, is less than or equal to 2.5, multiply amount liberated by 58,835 Btu/# mol as the heat of decomposition of MgCO₃. It is assumed that all carbonate decomposition in excess of 2.5 # mol/ton production of CO₂ is liberated from the decomposition of CaCO₃, whose heat of decomposition is 75096 Btu/#mol.

Difference =
$$\sum \text{Heat Inputs} - \sum \text{Heat Outputs}$$

Btu/ton

HEAT IN = shale in + top gas in + mid gas in + bottom gas in + oil condensation
Btu/Ton

HEAT OUT = off gas out + retorted shale out + oil mist out + H₂O vaporization + carbonate decomposition + pyrolysis
+ liquid H₂O out as vapor + skin losses + difference

Mean (Mean Between Groups) Standard Error

1-16 (Mean)

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

Mean (Mean Between Groups) Standard Error

Mean

TABLE 7-19

H(6)
 UNIT 2 RUN 28 TEST 1000 MMDDYY 31976 HRS 36 0
 F(9)
 DRY SH,TPH 10.21 MOIST. % 1.23 FA,GPT 26.3 FA OIL,WT% 10.02
 FA H2O 1.68 FA G+L 2.03 MIN CO2 17.7 ASH 67.98 LAB MOIST 0.58
 Y(8)
 RET SH,TPH 9.1 FA GPT 0.5 MIN CO2 19.47 ASH 76.68
 H2O IN OIL,WT% 1.1 DRY OIL,GPH 247.5 H2O LIQ,GPH 36.6 API 20.2
 R(5)
 BTM GAS,SCFM 2034 MID 0 TOP 1792 PROD 91 S.G. 0.719
 T(9)
 OFF GAS,F 326 GAS BL DIS 214 TOP DIST 1299 MID DIST 214
 BOT DIST 150 RET SH 336 PROD OIL 147 SHALE IN 40
 GAS COND OUT 150
 G(15),ALL MOL %
 H2 17.72 N2 0.40 O2 0.00 CO 1.93 CH4 22.68 CO2 10.75
 C2H4 8.98 C2H6 3.19 C3'S 1.61 C4'S 0.43 C5'S 0.02
 H2S 1.99 H2O 28.82 OIL 0.62 NH3 0.86
 P(13)
 BARD 24.1 RAW %: C 16.16 H 1.7 N 0.45 RET %: C 8.37
 H 0.33 N 0.34 OIL %: C 84.89 H 11.44 N 2.03 BOT PR 4.1

MAT. BAL. PROG. LOADED. COPYRIGHT 1976,PARAHO DEV.CORP

BALANCES	IN	OUT	UNITS	FR.REC.
ASH	232.71	232.60	#/MIN	1.000
WATER	8.00	6.33	#/MIN	0.791
		5.08 L		
		1.25 V		
KEROGEN	43.27	45.89	#/MIN	1.061
		11.68 S		
		32.05 O		
		2.17 G		
ORG. CARBON	38.78	38.15	#/MIN	0.984
		9.27 S		
		27.21 O		
		1.67 G		
ORG. HYDROGEN	5.17	5.19	#/MIN	1.004
		1.00 S		
		3.67 O		
		0.53 G		
ORG. NITROGEN	1.54	1.71	#/MIN	1.111
O'ALL WEIGHT	344.57	345.46	#/MIN	1.003

91.64 VOL%FA 93.44 WT%FA 2.53 % CARB DEC

HEAT BALANCE PROGRAM LOADED. COPYRIGHT 1976, PARAHO DEV. CORP.

BASIS: 1 TON DRY SHALE DATUM: 77 DEG F

HEAT IN		HEAT OUT	
SHALE IN	-15328	OFF GAS	146097
TOP GAS IN	402104	RET SH OUT	102679
MID GAS IN	0	OIL MIST OUT	22419
BOT GAS IN	20853	H2O VAPORIZATION	52567
OIL CONDENSATION	13184	CARBONATE DECOMP	12034
		PYROLYSIS	64000
		LIQ H2O OFF AS VAPOR	3364
		SKIN LOSSES	10000
		DIFFERENCE	7654
TOTAL IN	420813	TOTAL OUT	420813

WESTON BOND

FLUORESCENT

EXTRACTOR FIBER

TABLE A-1

TABLE A-1												
RUN NO.	PURPOSE	MODE	TESTS	START DATE	TIME	FINISH DATE	TIME	DAYS OPERATING TIME	% OPERATING TIME	SHALE RETORTED TONS	OIL PRODUCED GALLONS	REASON FOR OUTAGE
1-1	PRELIMINARY SHUTDOWN	DIRECT	0	5/28/74	1325	5/31/74	1440	1.03	94.0			ELECTRICAL FAILURE
1-2	PRELIMINARY SHUTDOWN	DIRECT	3	6/2/74	0925	6/6/74	1600	4.27	100.0	181.9	1829	PLANNED SHUT-DOWN
2-1	START UP TESTS	DIRECT	0	6/16/74	1117	6/19/74	1400	3.11	99.3	87.0	1497	ELECTRICAL FAILURE
3-1	START UP TESTS	DIRECT	0	6/25/74	1618	6/25/74	1700	.03	100.0			GRATE SETTING
3-2	START UP TESTS	DIRECT	0	6/25/74	2155	6/26/74	0425	.27	100.0			PROCESS UPSET
3-3	START UP TESTS	DIRECT	0	6/28/74	1950	6/29/74	1240	.73	100.0			LOSS OF COMBUSTION ZONE
3-4	START UP TESTS	DIRECT	0	6/29/74	1653	6/30/74	0400	.46	100.0	6.36	112	PROCESS UPSET
4-1	START UP TESTS	DIRECT	0	7/10/74	1317	7/10/74	1820	.21	100.0			LOSS OF COMBUSTION ZONE
4-2	START UP TESTS	DIRECT	0	7/11/74	1235	7/11/74	1800	.22	100.0			FAULTY START UP
4-3	START UP TESTS	DIRECT	0	7/12/74	1635	7/13/74	0150	1.39	57.3			ESP FAILURE
4-4	START UP TESTS	DIRECT	0	7/16/74	1235	7/17/74	0600	.72	100.0	20.4	392	FAULTY START UP
5	START UP TESTS & VAR. STUDY	DIRECT	5	7/24/74	1602	8/1/74	1602	8.00	91.4	129.3	2863	PLANNED SHUT-DOWN
6	MASS RATE TESTS	DIRECT	6	8/6/74	1500	8/15/74	1600	9.04	97.9	196.8	4767	PLANNED SHUT-DOWN
7	START UP TESTS FOR S.W.	DIRECT	0	10/6/74	1023	10/7/74	0515	.78	100.0	12.8	250	LOSS OF FEED
8-1	START UP TESTS	DIRECT	0	10/31/74	0837	10/31/74	0950	.05	100.0			LOSS OF COMBUSTION ON START UP
8-2	START UP TESTS	DIRECT	0	10/31/74	1557	10/31/74	1718	.05	100.0			LOSS OF COMBUSTION ON START UP
8-3	START UP TESTS	DIRECT	0	11/1/74	1610	11/1/74	1730	.05	100.0			LOSS OF COMBUSTION ON START UP
8-4	START UP TESTS	DIRECT	0	11/2/74	1138	11/2/74	1307	.05	100.0			LOSS OF COMBUSTION ON START UP
8-5	START UP TESTS	DIRECT	0	11/2/74	1924	11/2/74	2058	.06	100.0			LOSS OF COMBUSTION ON START UP
8-6	START UP TESTS	DIRECT	0	11/3/74	1114	11/3/74	1138	.01	100.0			LOSS OF COMBUSTION ON START UP
8-7	START UP TESTS	DIRECT	0	11/3/74	1419	11/3/74	1649	.08	100.0			LOSS OF COMBUSTION ON START UP
8-8	START UP TESTS	DIRECT	0	11/4/74	1444	11/5/74	0520	.60	100.0	20.2	303	FAULTY START UP
9-1	START UP TESTS	DIRECT	0	11/19/74	1103	11/19/74	2100	.41	100.0			LOSS OF COMBUSTION ZONE
9-2	START UP TESTS	DIRECT	0	11/20/74	2046	11/20/74	2207	.06	100.0			LOSS OF COMBUSTION ZONE
9-3	MASS RATE TEST	DIRECT	4	11/21/74	0905	11/25/74	1100	4.08	97.0	117.2	2541	PLANNED SHUT-DOWN
10-1	MASS RATE TEST	DIRECT	0	12/7/74	0920	12/7/74	1928	.42	94.2			PROCESS UPSET
10-2	MASS RATE TEST	DIRECT	4	12-8-74	1313	12/12/74	1000	3.87	99.4	134.2	3362	PROCESS UPSET
11	PRELIMINARY SHUTDOWN	INDIRECT	1	3/28/75	1407	4/2/75	0230	5.52	88.7	119.9	1067	LOSS OF PRESSURE CONTROL
12-1	PRELIMINARY SHUTDOWN	INDIRECT	0	4/5/75	0856	4/7/75	1550	2.29	86.6			GAS LEAK AT DISTRIBUTOR
12-2	PRELIMINARY SHUTDOWN	INDIRECT	0	4/11/75	1550	4/13/75	2315	2.34	81.8			DISCH. GRATE FAILURE
12-3	PRELIMINARY SHUTDOWN	INDIRECT	0	4/15/75	1035	4/16/75	0038	.58	94.6			HEATER & TOP ROTARY SEAL FAILURE
12-4	PRELIMINARY SHUTDOWN	INDIRECT	0	4/20/75	0945	4/20/75	1000	2.01	100.0	116.8	2664	HEATER FAILURE
13-1	MASS RATE TEST	DIRECT	0	5/12/75	0330	5/15/75	0930	3.25	96.6			AIR BLOWER FAILURE
13-2	MASS RATE TEST	DIRECT	0	5/17/75	2247	5/23/75	1414	5.67	86.9			RECYCLE BLOWER FAILURE
13-3	VARIABLE STUDY	DIRECT	0	5/27/75	1743	6/4/75	0615	7.52	95.0	368.0	7851	LOSS OF COMBUSTION ZONE
14-1	START UP TESTS	INDIRECT	0	6/11/75	1726	6/13/75	0610	1.53	99.3			FAULTY PROCESS CONDITIONS
14-2	START UP TESTS	INDIRECT	0	6/14/75	1430	6/22/75	2100	8.27	96.4			FAULTY PROCESS CONDITIONS
14-3	START UP TESTS	INDIRECT	0	6/23/75	2243	6/25/75	2150	2.00	100.0			FAULTY PROCESS CONDITIONS
14-4	START UP TESTS	INDIRECT	0	6/27/75	1820	7/1/75	1300	3.76	94.8	266.6	5792	BLOWER LIMITATIONS & HEATER FAILURE

TABLE A-1 (CONT.)

[illegible]

SEMI-WORKS OPERATING SUMMARY

TABLE B-1

RUN NO.	PURPOSE	MCDE	TESTS	START DATE	TIME	FINISH DATE	TIME	DAYS OPERATING TIME	% OPERATING TIME	SHALE RETORTED TONS	OIL PRODUCED GALLONS	REASON FOR OUTAGE
1-1	PRELIMINARY SHAKEDOWN	DIRECT	0	8/27/74	1020	8/27/74	1400	.15	100.0			FAULTY START UP
1-2	PRELIMINARY SHAKEDOWN	DIRECT	0	9/5/74	1120	9/6/74	1545	1.18	100.0			GRATE FAILURE
1-3	PRELIMINARY SHAKEDOWN	DIRECT	0	9/18/74	0921	9/18/74	1332	.17	100.0			FAULTY START UP PROCEDURE
1-4	PRELIMINARY SHAKEDOWN	DIRECT	0	9/23/74	1358	9/24/74	0450	.62	100.0	188.6	3860	GRATE FAILURE
2-1	START UP TESTS	DIRECT	0	10/15/74	1300	10/16/74	1125	.93	100.0			E.S.P. FAILURE
2-2	START UP TESTS	DIRECT	0	10/21/74	1330	10/21/74	2240	.38	100.0	195.4	2109	E.S.P. FAILURE
3-1	START UP TESTS	DIRECT	0	11/12/74	1438	11/12/74	2130	.29	100.0			PROCESS UPSET
3-2	START UP TESTS	DIRECT	0	11/14/74	1017	11/16/74	0730	1.88	100.0	449.5	6800	OIL DRAIN PLUGGED
4-1	DEMONSTRATION RUN	DIRECT	0	11/26/74	0915	11/27/74	1201	1.12	100.0			PROCESS UPSET
4-2	DEMONSTRATION RUN	DIRECT	0	11/30/74	1005	11/30/74	2330	.56	100.0			LOSS OF COMBUSTION ZONE
4-3	DEMONSTRATION RUN	DIRECT	0	12/2/74	1238	12/4/74	0945	.88	100.0	565.7	11190	PROCESS UPSET - FINES IN RAW SHALE
5-1	DEMONSTRATION RUN	DIRECT	0	12/12/74	2059	12/13/74	0213	.22	100.0			PROCESS UPSET
5-2	DEMONSTRATION RUN	DIRECT	0	12/14/74	0958	12/15/74	2000	1.42	99.3			E.S.P. FAILURE
5-3	DEMONSTRATION RUN	DIRECT	4	12/22/74	1336	1/1/75	0330	9.58	90.0	2367.8	45528	PROCESS UPSET - FINES IN RAW SHALE
6-1	DEMONSTRATION RUN	DIRECT	0	1/9/75	1257	1/10/75	0721	.77	100.0			LOSS OF COMBUSTION ZONE
6-2	DEMONSTRATION RUN	DIRECT	0	1/13/75	1246	1/14/75	0200	.55	100.0	217.0	4575	LOSS OF COMBUSTION ZONE
7	DEMONSTRATION RUN	DIRECT	32	1/17/75	0940	3/14/75	0940	56.0	88.3	12159	280124	PLANNED SHUTDOWN
8-1	REPEATABILITY TEST	DIRECT	0	4/25/75	2205	4/26/75	0500	.29	100.0			PROCESS UPSET
8-2	REPEATABILITY TEST	DIRECT	0	4/30/75	1650	5/3/75	0220	2.40	76.5			LOSS OF COMBUSTION ZONE
8-3	REPEATABILITY TEST	DIRECT	7	5/4/75	0825	5/16/75	1614	12.33	97.1	3785.7	87460	AIR-GAS BLOCKAGE TO MID. DIST.
9	MASS RATE TEST	DIRECT	1	5/24/75	0045	6/4/75	0820	10.31	91.1	2910.2	62298	RECYCLE BLOWER MOTOR FAILURE
10-1	PRELIMINARY SHAKEDOWN	INDIRECT	0	6/22/75	1518	6/22/75	2145	.27	78.2			LOSS OF RETORT PRESSURE CONTROL
10-2	PRELIMINARY SHAKEDOWN	INDIRECT	0	7/9/75	2225	7/13/75	1925	3.87	93.5			FAULTY PROCESS CONDITIONS
10-3	PRELIMINARY SHAKEDOWN	INDIRECT	0	7/19/75	2055	7/23/75	0600	3.38	97.6			FAULTY PROCESS CONDITIONS
10-4	PRELIMINARY SHAKEDOWN	INDIRECT	5	7/29/75	1110	8/6/75	0730	7.85	99.4	3631.8	54736	FAULTY PROCESS CONDITIONS
11-1	MASS RATE TEST	DIRECT	0	8/12/75	1545	8/14/75	0845	2.71	100.0			LOSS OF COMBUSTION ZONE
11-2	MASS RATE TEST	DIRECT	1	8/15/75	1435	8/24/75	0328	8.95	97.9			LOSS OF COMBUSTION ZONE
11-3	MASS RATE TEST	DIRECT	0	8/25/75	1455	8/27/75	2400	2.38	95.8	3304.1	66963	LOSS OF COMBUSTION ZONE
12	REPRODUCIBILITY	DIRECT	0	9/29/75	1015	10/1/75	0030	1.59	100.0	367.9	9374	FAULTY OPERATION CONDITIONS
13	REPRODUCIBILITY	DIRECT	0	10/2/75	1145	10/3/75	1705	1.22	100.0	244.9	4719	FAULTY OPERATION CONDITIONS
14	REPRODUCIBILITY	DIRECT	0	10/5/75	0330	10/5/75	0700	.15	100.0	15.7	50	FAULTY START UP
15	REPRODUCIBILITY	DIRECT	0	10/5/75	1841	10/7/75	1800	1.97	99.5	472.8	10296	FAULTY OPERATION CONDITIONS
16	REPRODUCIBILITY	DIRECT	0	10/8/75	2255	10/13/75	0900	4.42	98.0	1226.5	23573	FAULTY OPERATION CONDITIONS
17-1	REPRODUCIBILITY	DIRECT	0	10/16/75	0908	10/16/75	1330	.18	100.0			FAULTY START UP
17-2	REPRODUCIBILITY	DIRECT	0	10/16/75	2029	10/17/75	0234	.25	100.0			FAULTY START UP
17-3	REPRODUCIBILITY	DIRECT	0	10/18/75	1136	10/18/75	2300	.48	100.0			FAULTY START UP
17-4	REPRODUCIBILITY	DIRECT	3	10/19/75	1106	10/24/75	0615	4.80	100.0	1206.1	27110	PROCESS UPSET - FINES IN RAW SHALE
18	DEMONSTRATION RUN	DIRECT	0	10/25/75	0047	10/25/75	2200	.88	100.0	148.2	3509	FAULTY OPERATION CONDITIONS
19-1	DEMONSTRATION RUN	DIRECT	0	10/27/75	0012	10/27/75	0310	.12	100.0			FAULTY START UP
19-2	DEMONSTRATION RUN	DIRECT	2	10/28/75	1030	11/6/75	1950	4.39	100.0			PROCESS UPSET - FINES IN RAW SHALE
19-3	DEMONSTRATION RUN	DIRECT	0	11/2/75	0639	11/3/75	0915	1.11	100.0	1262.8	29438	FAULTY START UP
20	DEMONSTRATION RUN	DIRECT	20	11/4/75	2145	11/30/75	1140	25.58	99.7	6771	167356	LOSS OF COMBUSTION ZONE
21	START UP TEST	INDIRECT	1	12/10/75	1640	12/15/75	0315	4.42	94.6	813.4	12870	LOSS OF RETORT PRESSURE CONTROL

TABLE B-1 (CONT.)

REASON FOR OUTAGE

APPENDIX C

Run Evaluations and Equipment Changes

<u>Run No.</u>	<u>Process Operated</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
PP-	Cold Flow Test	4/9/74	Particle residence time in the retort is independent of radial position.	None
PP-	Cold Flow Test	5/8/74	Particle residence time in the retort is independent of particle size.	None
PP-1	Direct Heated	5/28/74	Initial air and gas rates for process operability were established. Momentary power outages plagued run. Three test periods obtained. Planned shutdown.	None
PP-2	Direct Heated	6/16/74	The importance of maintaining plug solids flow in the retort was demonstrated. Grate misalignment and inadequate feed screening caused carryover of dust to the precipitator. Problems described above and a power failure resulted in a shutdown.	None
PP-3	Direct Heated	6/25/76	Variations in fire-off procedures were investigated. Four unsuccessful fireoffs were made. Equilibrium conditions were never obtained.	Re-centered grate pusher bar.
PP-4	Direct Heated	7/10/74	The ability to place the retort in standby and restart several hours later was demonstrated. It was concluded that the bed height above the top air/gas distributor was too great, causing refluxing and consequent bridging. Equilibrium conditions were not obtained.	None

WATER

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

the water is not sufficient

<u>Run No.</u>	<u>Process Operated</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
PP-5	Direct Heated	7/24/76	Five equilibrium test periods were obtained. Three standbys were required for equipment failure and power outages. Bridging occurred during the run, but operation was continued as scheduled.	The bed height was lowered by one foot to prevent refluxing.
PP-6	Direct Heated	6/6/74	Five equilibrium test periods were obtained at mass rates exceeding 400 #/hr/ft ² . Bridging occurred during run, but did not stop operation.	None
PP-7	Direct Heated	10/6/74	Equilibrium conditions were not attained. Problems were encountered with shale feed rate control causing fluctuations in bed temperatures.	None
PP-8	Direct Heated	10/31/74	Various start-up procedures were investigated. Eight fire-offs were made, with six resulting in loss of fire. The eighth fire-off failed due to fluctuations in shale feed rate similar to PP-7.	None
PP-9	Direct Heated	11/19/74	Four equilibrium test periods were obtained at mass rates up to 633 #/hr/ft ² . Start-up success was improved by using signal flares rather than diesel soaked blocks to ignite a fire.	Bed height was lowered for start-up only to minimize refluxing conditions.
PP-10	Direct Heated	12/7/74	Four equilibrium test periods were obtained at higher mass rates to 640 #/hr/ft ² .	None

amblyopisium truncatum and -var.

Plantlet now stippled but not
showing as foot was of
petioles.

amblyopisium

now showing that amblyopisium was
very cydneum petio. petioles
has small (1) truncatum not leafy
but more gibbous. petioles more
now petioles now, not as gibbous
petioles as petioles

now showing that amblyopisium was
petioles and now as petioles
but more gibbous. petioles more
now petioles now, not as gibbous
petioles as petioles

now showing that amblyopisium was
petioles and now as petioles
but more gibbous. petioles more
now petioles now, not as gibbous
petioles as petioles

now showing that amblyopisium was
petioles and now as petioles
but more gibbous. petioles more
now petioles now, not as gibbous
petioles as petioles

not showing now stippled but
showing as foot was of
petioles.

now

now showing that amblyopisium was
petioles and now as petioles
but more gibbous. petioles more
now petioles now, not as gibbous
petioles as petioles

2-10-51

between 2-10-51

2-10-51

2-10-51

between 2-10-51

2-10-51

2-10-51

between 2-10-51

2-10-51

2-10-51

between 2-10-51

2-10-51

2-10-51

between 2-10-51

2-10-51

2-10-51

between 2-10-51

2-10-51

2-10-51

between 2-10-51

2-10-51

<u>Run No.</u>	<u>Process Operated</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
PP-11	Indirect Heated	3/27/75	Initial characteristics of the Indirect heated process were determined. A stable operating period was obtained. Erratic retort pressure control caused air in leakage and undersirable combustion. Complete retorting was not attained.	A double rotary seal was installed to minimize gas losses. Orifice holes were enlarged to accommodate higher gas rates.
PP-12	Indirect Heated	4/5/75	Further definition of Indirect heated process. Four start-up attempts were made. Continued operation was handicapped by poor pressure control, grate stoppages, gas leaks, and heater problems.	A smaller product gas control valve was installed for improved pressure control. Permanent drain lines were installed at low point collection points.
PP-13	Direct Heated	5/12/75	Considerable success was realized in putting the retort back on line after standbys up to 7.6 hours in length. Problems with auxiliary equipment interfered with establishing equilibrium throughout run.	Product gas control valve changed back to direct mode size. Bed height increased.
PP-14	Indirect Heated	6/11/76	Experience was gained in start-up procedures for Indirect heated operation by transition from direct heated operation. Density product gas caused blower operation problems - difficult to maintain. Design gas to shale ratios caused refluxing during all operation. Run terminated by heater failure.	An oil coalescer assembly upstream of the ESP was installed to lower the mist loading and stabilize the electrostatic precipitator operation.
PP-15	Indirect and Direct Heated	7/4/75	Several stand-bys were required for mechanical repairs preventing equilibrium conditions from being established. The recycle gas heaters were inoperable after the first three start-up attempts. Operation was continued as direct heated retort.	An additional suction stage was installed on the recycle gas blower to improve operation with light gas.

<u>Run No.</u>	<u>Process Operated</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
PP-16	Direct Heated	12/8/75	This run represents the longest period of continuous operation thus far achieved. Product gas from the Pilot Plant was used as an emergency source of purge gas for Indirect mode operation in the semi-works. A total of 16 equilibrium test periods were obtained with successful duplication of test conditions established in semi-works run SW-20. A minimum of operator attention was required. Stand-bys were required occasionally for the minor equipment repairs. Following a stand-by to clean the middle distributor orifices excessive wet fines in the raw shale led to a decision to shutdown.	Bed height decreased.
PP-17	Direct Heated	2/26/76	Start-up procedure of PP-16 was successfully duplicated. Drive chain broke on bottom rotary seal necessitating a stand-by. Return to operating conditions after standby was unsuccessful.	None
PP-18	Direct Heated	3/3/76	Fire-off successful. Operation was regained from three standbys, one of 18.1 hours duration. Operation was primarily intended for an emergency supply of purge gas to the semi-works in indirect operation. Mechanical problems required four standbys. Shutdown was caused by shearing of the bottom rotary seal hub.	None
PP-19	Direct Heated	3/31/76	Three equilibrium test periods were obtained while running richer than normal shale (32 gpt). Parametric studies of air split to the top and middle distributors were performed. One standby was required for hub repair on the bottom rotary seal.	None

Sub-sonic flight performance

Altitude 1000

Time 0:00

Distance 1000

Altitude 1000

Sub-sonic flight performance

Altitude 1000

Time 0:00

Distance 1000

Altitude 1000

Sub-sonic flight performance

Altitude 1000

Time 0:00

Distance 1000

Altitude 1000

Sub-sonic flight performance

Altitude 1000

Time 0:00

Distance 1000

Altitude 1000

Sub-sonic flight performance

Altitude 1000

Time 0:00

Distance 1000

Altitude 1000

Sub-sonic flight performance
Altitude 1000
Time 0:00
Distance 1000
Altitude 1000

<u>Run No.</u>	<u>Process Operated</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
SW-	Cold Flow Test	8/23/74	Particle resident time was not affected by size. Particles near the walls are slower in descent than those in the center. Particles near the flat side walls were 8% slower than those in the remainder of the bed. There was not a significant difference in residence time between the four quadrants of the retort.	None
SW-1	Direct Heated	8/27/74	An initial equipment shakedown was performed. Four start-up procedures were investigated. Damage to the thermocouple probe was evident in the first three start-up attempts from overheating. Hydraulic system failures on grate mechanism ended two start-up trials.	Additional propane capacity was added to supply fire-off requirements. Insulation was added to the thermocouple junction box for protection. A new thermocouple probe was required.
SW-2	Direct Heated	10/15/74	The second start-up was satisfactory until problems were encountered with the precipitator. Partial bridging and pluggage of the off-gas collectors ended start-up one. The second start-up was terminated by a short in the electrostatic precipitator.	Hydraulic seals on the grate cylinders were replaced with high temperature resistant material. Other modifications to the grate cylinders were made to prevent heat and dust problems. Grate contour changes made to correct shale flow pattern.
SW-3	Direct Heated	11/12/74	Start-up procedures were further developed. Fines and dust carry-over plugged off-gas collectors and prevented efficient flow of oil from the precipitator.	Extensive maintenance was performed on the electrostatic precipitator. Grate hydraulic cylinders were relocated to prevent dust and heat contamination of the seals.
SW-4	Direct Heated	11/26/74	Start-up procedures were further developed. Unsuccessful start-ups were attributed to excessive fines feed to the retort.	None

SEYCOLLUM LIBR

ET DOBESSUM

MESLON BOND

Run No.	Process Operated	Start Date	Key Results	Pre-Run Equipment Modifications
SW-5	Direct Heated	12/12/74	The third start-up ran for over nine days and four equilibrium test periods were obtained. Leaner shale was used on the third start-up. The start-up procedure developed for PP-9 and PP-10 were adapted to the Semi-Works. The final shutdown was attributed to excessive fines fed to the retort.	The precipitator was modified by installation of sludge removal pots. Flushing oil was provided for the bottom of the precipitator to remove sludge.
SW-6	Direct Heated	1/9/75	Start-up procedures were further investigated and modified.	The 10-inch top distributors were replaced with 6-inch diameter to improve shale flow. A drain system on the recycle gas lines was installed to prevent oil build-up at the orifice plates.
SW-7	Direct Heated	1/17/75	This run represented 56 days of operation without the need to empty the retort and fire-off again. A total of 32 equilibrium test periods were obtained. Considerable success was realized in restarting after lengthy stand-bys. Stand-bys were required for cleaning of the off-gas collectors, external removal of bridged material, and mechanical failure and checks. Oil rundown lines required occasional cleaning.	Rodding ports were installed on the side of the retort above the top distributor to provide a means to dislodge bridged material externally.
SW-8	Direct Heated	4/26/75	Seven test periods were obtained during the third start-up with no evidence of bridging. Coke build-up in the middle air/gas distributors terminated the third run.	A polishing screen was installed to remove fines produced at various transfer points and in the storage bins.
SW-9	Direct Heated	5/24/75	Mass rates as high as 625 #/hr/ft ² were attained. Start-up was accomplished with lean shale. Stand-bys were required for mechanical equipment repairs. Mechanical failure of the recycle blower motor required shutdown.	None

Run No.	Process Operated	Start Date	Key Results	Pre-Run Equipment Modifications
SW-10	Indirect Heated	6/22/75	Various start-up procedures were investigated combining direct/indirect operation.	A coalescer system was installed to relieve oil mist loading to the precipitator. Stainless steel 10-inch gas distributors were installed with large orifice hole openings. A second rotary seal was added at the bottom of the retort. Provision was made to use the 300 BHP blower while the 700 was under repair. Different bed height adjustments were tried.
SW-11	Direct Heated	8/12/75	Experience was gained in higher mass rate operation. The loss of bed temperature measurements in the combustion zone resulted in loss of control locations and consequent shutdown of each of the three start-up attempts.	None
SW-12	Direct Heated	9/29/75	A shakedown of new equipment and modifications performed during the turnaround was accomplished.	A major turnaround was undertaken for equipment cleanup, repair and modification as follows: Rotary solids distributor was lengthened and off-gas collectors removed; new temperature and pressure probe installed; 6-inch diameter air/gas distributor replaced 10-inch. Orifice holes in top air-gas distributor were reduced in size for better distribution.
SW-13	Direct Heated	10/2/75	Operational problems were attributed to too great a bed height above the top air/gas distributor. Refluxing conditions resulted.	None

<u>Run No.</u>	<u>Process Operating</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
SW-14	Direct Heated	10/5/75	A larger top size on the raw shale feed was tried to compensate for too much bed height. A portion of the combustion zone was lost shortly after fire-off requiring shutdown.	None
SW-15	Direct Heated	10/5/75	Larger top size shale was tried again with results shown that retorting of the larger particles was complete.	None
SW-16	Direct Heated	10/8/75	An investigation of larger top size feed continued. Restriction of flow through the middle air/gas distributor and a partial bridge forced a shutdown.	None
SW-17	Direct Heated	10/16/75	Equilibrium was attained after the fourth start-up, allowing test period calculation. Failures of the first three start-ups were attributed to plugged distributor piping and excessive fines in feed for the fourth start-up.	The off-gas collectors were reinstalled to lower the bed height. An on-line gas chromatograph was installed.
SW-18	Direct Heated	10/25/75	Further success was gained in the start-up procedure.	None
SW-19	Direct Heated	10/27/75	Operation after start-up two was stable enough to allow test period calculation. Increasing orifice sizes in the top distributor was significant on operations.	Orifice holes in the top air/gas distributors were enlarged to that size used in SW-10. Smaller holes existed during SW-12-18.
SW-20	Direct Heated	11/4/75	High oil recovery and trouble free operation were demonstrated for nearly 26 days. Consecutive test periods were obtained at identical operating conditions. Special tests were performed to determine basic design data. Brief power failure interrupted run requiring stand-by occasionally.	None

unclassified document and not

document not

page 1

document

100

none

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

100

Document

100

none

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

100

Document

100

none

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

100

Document

100

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

100

Document

100

none

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

100

Document

100

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

100

Document

100

none

State has not yet received a
copy of documents of which we have
not to destroy it. Should not have not
to the ultimate level was even not destroyed
-perhaps perhaps 110-111

100

Document

100

<u>Run No.</u>	<u>Process Operated</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
SW-21	Indirect Heated	12/10/75	Start-up procedure for the Indirect mode was established. Moisture content in the recycle gas was controlled by cooling with the coalescer. Hot gas was injected only at the top distributor. Continuous problems were experienced with maintaining heater firing. Problems were encountered with holding retort positive pressure.	A packed section in the coalescer, with oil circulation system for cooling the off-gas and condensing water was installed. Stainless steel distributors reinstalled with larger orifice holes. Lowered bed height.
SW-22	Indirect Heated	12/18/75	Further experience was gained in the Indirect operations. Incomplete retorting was experienced. Retort pressure control continued to be a problem. The retort was shutdown after an ignition occurred in the top gas line as a result of air being drawn into the retort during a negative pressure condition.	Further improvement was made in heater operation by various modifications. Six vane rotary seal replaced four vane in the retort top to minimize gas leakage.
SW-23	Indirect Heated	1/10/76	This run demonstrated operability of the indirect heated process. Considerable progress in improving thermal efficiency was made through the run. Heater outages were experienced frequently.	Heater repairs were performed as necessary. An air filter was installed on the primary air blower of the heater to prevent dust intake. Orifice holes in the bottom gas distributor were reduced for lower rates. A stand-by was taken during the run to install the bottom gas cooler.
SW-24	Indirect Heated	2/13/76	Heater problems affected process conditions.	Oil recovery system was modified for combined rundown of oil production.

unintentionally increasing our...

at the same time, we have a
relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

at the same time, we have a
relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

because of the fact that
higher level
relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

the same

because of the fact that
higher level
relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

because of the fact that
higher level
relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

because of the fact that
higher level
relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

relationship to the, especially
and the other public not only
new target personnel has
least satisfied. Bell's
this relationship is not
because of the fact that
higher level

Date

Received

File

12/10/52

Letter to...

11-11

11/18/52

Letter to...

11-11

11/10/52

Letter to...

11-11

11/10/52

Letter to...

11-11

<u>Run No.</u>	<u>Process Operated</u>	<u>Start Date</u>	<u>Key Results</u>	<u>Pre-Run Equipment Modifications</u>
SW-25	Indirect Heated	2/18/76	Particle agglomeration and pluggage of the off-gas piping required shutdown.	Repair of recycle gas heater.
SW-26	Indirect Heated	2/28/76	Special water samples were taken. Bed restrictions and pluggage of off-gas piping caused unstable operation. These plus a power outage necessitated a shutdown.	Number of orifice holes in the bottom gas distributor were increased to handle greater gas rates. Orifice holes in the top gas distributor were enlarged to reduce shale abrasion.
SW-27	Indirect Heated	3/6/76	Leakage in the recycle gas heater delayed start-up. Grate electrical problems resulted in bridging which terminated operations shortly after start-up.	An increase in bed height was made to prevent refluxing and consequent bridging. Modifications were made to the blower to prevent gas leakage.
SW-28	Indirect Heated	3/12/76	Several equilibrium test periods were obtained at conditions of high thermal efficiency. Oil viscosities were lower than normal. During a transition to higher thermal efficiency, bed pressure drop requiring shutdown.	None
SW-29	Combination Mode	3/25/76	Initial results of the combination heated process were obtained. Equilibrium test periods were derived. Discharge grate control malfunctioned causing loss of shale discharge.	None
SW-30	Combination Mode	3/31/76	Start-up was unsuccessful.	None
SW-31	Combination and Indirect Heated	4/2/76	Oil viscosities were particularly lower than previous indirect operation. Indirect operation was made to duplicate past operating results and conditions. This run was hindered by severe leakage in the recycle gas heater. Top pressure was difficult to control positive. Retort was shutdown as scheduled to complete project program.	None

APPENDIX D

TEST DATA

The test data tabulations in this section account for only those periods of retort operation that have been used to calculate complete operational and product data. A complete accounting of all operational time will be found in Appendix Section A for the Pilot Plant and Section B for the Semi-Works.

BASIS

The technique of obtaining laboratory and operating data and methods of processing this data have improved throughout this project. A common basis was chosen for presenting the data from all test periods for each mode of operation. Average values were calculated from most recent and reliable data. These values were used for the earlier runs where such information was not previously available or was considered to be unreliable. These values and the runs in which they were used are shown on Table D-1.

A light naphtha content of 0.62 Vol% in the gas stream for Indirect Heated operations was averaged from data collected during Semi-Works Run SW-23 and SW-28. This value was used for all Indirect Heated Mode data presented.

Retorted shale rates were calculated using an ash balance for those periods showing a deviation of more than $\pm 1\%$ from measured values.

APPENDIX D

TEST DATA

The test data tabulations in this section account for only those periods of retrofit operation that have been used to calculate complete operational and product data. A complete accounting of all operational time will be found in Appendix Section A for the Pilot Plant and Section B for the Semi-Works.

BASIS

The technique of obtaining laboratory and operating data and methods of processing this data have improved throughout this project. A common basis was chosen for presenting the data from all test periods for each mode of operation. Average values were calculated from most recent and reliable data. These values were used for the earlier runs where such information was not previously available or was considered to be unreliable. These values and the runs in which they were used are shown on Table D-1.

A light naphtha content of 0.62 Vol% in the gas stream for Indirect Heated operations was averaged from data collected during Semi-Works Run SW-23 and SW-18. This value was used for all Indirect Heated Mode data presented.

Retrofited shaft rates were calculated using an ash balance for those periods showing a deviation of more than $\pm 1\%$ from measured values.



The column shown as Hot Gas for the Indirect Heated data reflects the heat content of the hot gas entering the top distributors as calculated from the 77°F Datum.

WESTON BOND

FLUORESCENT

25% COTTON FIBER

WESTON BOND

FLUORESCENT

EXCITATION FIBER

TEST DATA VALUES

TABLE D - 1

Item	Value	Plant	From Run	To Run
Raw Shale Moisture Wt%	1.00	Pilot Plant	PP-1	PP-16
Raw Shale Moisture Wt%	1.00	Semi-Works	SW-5	SW-7 (PC-1)
Raw Shale Lab Moist. Wt%	0.66	Pilot Plant	PP-1	PP-16
Raw Shale Lab Moist. Wt%	0.66	Semi-Works	SW-5	SW-20
Raw Shale Wt% C	17.09	Pilot Plant	PP-1	PP-16
Raw Shale Wt% C	17.09	Semi-Works	SW-5	SW-7
Raw Shale Wt% H	1.85	Pilot Plant	PP-1	PP-16
Raw Shale Wt% H	1.85	Semi-Works	SW-5	SW-7
Raw Shale Wt% N	0.51	Pilot Plant	PP-1	PP-16
Raw Shale Wt% N	0.51	Semi-Works	SW-5	SW-7
Manometer Fluid No. 1	1.07	Pilot Plant	PP-9	PP-16
Manometer Fluid No. 1	1.07	Semi-Works	SW-5	SW-20
Run Down Tank Gal/In.	29.65	Semi-Works	SW-5	SW-20
Cooling Water Gal/Min	17	Pilot Plant	PP-1	PP-9
Cooling Water Δ Temp, $^{\circ}$ F	20	Pilot Plant	PP-1	PP-9
Cooling Water, Gal/Min	80	Semi-Works	SW-5	SW-7
Cooling Water Δ Temp $^{\circ}$ F	20	Semi-Works	SW-5	SW-7
Retorted Shale Wt% C	6.24	Pilot Plant	PP-1	PP-16
Retorted Shale Wt% C	6.24	Semi-Works	SW-5	SW-7
Retorted Shale Wt% H	0.16	Pilot Plant	PP-1	PP-16
Retorted Shale Wt% H	0.16	Semi-Works	SW-5	SW-7
Retorted Shale Wt% N	0.20	Pilot Plant	PP-1	PP-16
Retorted Shale Wt% N	0.20	Semi-Works	SW-5	SW-7
Oil Wt% C	84.65	Pilot Plant	PP-1	PP-19
Oil Wt% C	84.65	Semi-Works	SW-5	SW-7
Oil Wt% H	11.49	Pilot Plant	PP-1	PP-19
Oil Wt% H	11.49	Semi-Works	SW-5	SW-7
Oil Wt% N	2.02	Pilot Plant	PP-1	PP-19
Oil Wt% N	2.02	Semi-Works	SW-5	SW-7
Product Gas (Wet) Vol% C ₅ +	0.34	Pilot Plant	PP-1	PP-19
Product Gas (Wet) Vol% C ₅ +	0.34	Semi-Works	SW-5	SW-21
Product Gas (Wet) Vol% C ₅ +	0.62	Semi-Works	SW-21	SW-31
Product Gas (Wet) Tot. Anal.		Pilot Plant	PP-1	PP-9
SW-20' As				
Product Gas (Wet) Vol% H ₂ O	20	Pilot Plant	PP-1	PP-19
Product Gas (Wet) Vol% H ₂ O	20	Semi-Works	SW-5	SW-17

TEST DATA VALUES

TABLE D - 1

Item	Value	Plant	From Run	To Run
Raw Shale Moisture Wt	1.00	Pilot Plant	PP-1	PP-16
Raw Shale Moisture Wt	1.00	Semi-Works	SW-2	SW-7 (PC-1)
Raw Shale Lab Moist. Wt	0.66	Pilot Plant	PP-1	PP-16
Raw Shale Lab Moist. Wt	0.66	Semi-Works	SW-2	SW-20
Raw Shale Wt C	17.09	Pilot Plant	PP-1	PP-16
Raw Shale Wt C	17.09	Semi-Works	SW-2	SW-7
Raw Shale Wt N	1.82	Pilot Plant	PP-1	PP-16
Raw Shale Wt N	1.82	Semi-Works	SW-2	SW-7
Raw Shale Wt N	0.21	Pilot Plant	PP-1	PP-16
Raw Shale Wt N	0.21	Semi-Works	SW-2	SW-7
Manometer Fluid No. 1	1.07	Pilot Plant	PP-9	PP-16
Manometer Fluid No. 1	1.07	Semi-Works	SW-2	SW-20
Run Down Tank Gal/Tn	29.62	Semi-Works	SW-2	SW-20
Cooling Water Gal/Tn	17	Pilot Plant	PP-1	PP-9
Cooling Water A Temp, °F	30	Pilot Plant	PP-1	PP-9
Cooling Water, Gal/Mn	80	Semi-Works	SW-2	SW-7
Cooling Water A Temp, °F	30	Semi-Works	SW-2	SW-7
Reformed Shale Wt C	6.24	Pilot Plant	PP-1	PP-16
Reformed Shale Wt C	6.24	Semi-Works	SW-2	SW-7
Reformed Shale Wt N	0.16	Pilot Plant	PP-1	PP-16
Reformed Shale Wt N	0.16	Semi-Works	SW-2	SW-7
Reformed Shale Wt W	0.20	Pilot Plant	PP-1	PP-16
Reformed Shale Wt W	0.20	Semi-Works	SW-2	SW-7
Oil Wt C	84.62	Pilot Plant	PP-1	PP-19
Oil Wt C	84.62	Semi-Works	SW-2	SW-7
Oil Wt N	11.42	Pilot Plant	PP-1	PP-19
Oil Wt N	11.42	Semi-Works	SW-2	SW-7
Oil Wt N	2.02	Pilot Plant	PP-1	PP-19
Oil Wt N	2.02	Semi-Works	SW-2	SW-7
Product Gas (Wet) Vol/C +	0.34	Pilot Plant	PP-1	PP-19
Product Gas (Wet) Vol/C +	0.34	Semi-Works	SW-2	SW-21
Product Gas (Wet) Vol/C +	0.62	Semi-Works	SW-21	SW-31
Product Gas (Wet) Vol/C +	0.62	Pilot Plant	PP-1	PP-9
Product Gas (Wet) Vol/C +	20	Pilot Plant	PP-1	PP-19
Product Gas (Wet) Vol/C +	20	Semi-Works	SW-2	SW-17

TEST DATA FROM PILOT PLANT --- DIRECT HEATED

TABLE D-2

GENERAL: RUN NUMBER TEST NUMBER	PP-1 A	PP-1 B	PP-1 C	PP-5 A	PP-5 B	PP-5 C	PP-5 D	PP-5 E	PP-5 F	PP-6 A	PP-6 B	PP-6 C	PP-6 D	PP-6 E-1
DATE	5/29/74	6/4/74	6/6/74	7/25/74	7/26/74	7/27/74	7/28/74	7/30/74	8/10/74	8/11/74	8/12/74	8/13/74	8/14/74	
START TIME	0800	0800	0800	2400	1600	1600	1600	0800	0800	0800	0800	0800	0500	
LENGTH OF TEST hrs.	48	24	5	16	16	16	24	8	16	16	16	11	8	
RATES AND QUANTITIES:														
TOP DISTRIBUTOR GAS SCF/T	1277	1350	1359	2960	1099	2549	1478	1527	1552	1582	1453	1449	1324	
MID DISTRIBUTOR GAS SCF/T	1393	1512	1620	942	6620	2230	1478	1527	1851	1808	1688	1705	1785	
BTM DISTRIBUTOR GAS SCF/T	10793	12043	11812	13453	6620	12637	9829	10944	13313	13898	12703	12230	13244	
TOTAL GAS SCF/T	13462	14905	14791	17355	16339	17416	12785	13998	16716	17288	15844	15384	16353	
TOP DISTRIBUTOR AIR SCF/T	3191	3294	3449	6726	7183	5310	3276	3245	3881	4124	3797	3622	3628	
MID DISTRIBUTOR AIR SCF/T	1509	1242	1098	0	141	1062	964	1336	1910	1921	1781	1705	1843	
BTM DISTRIBUTOR AIR SCF/T	0	0	0	0	0	0	0	0	0	0	0	0	0	
TOTAL AIR SCF/T	4700	4536	4547	6726	7324	6372	4240	4581	5791	6045	5578	5327	5471	
SHALE THROUGHPUT lb/hr/ft ²	420	451	466	181	173	229	379	383	408	431	520	572	423	
TEMPERATURES:														
PRODUCT OIL °F	126	133	129	140	133	139	125	127	153	161	139	138	133	
RETORTED SHALE OUT °F	305	339	335	302	352	374	404	367	358	352	444	462	416	
RAW SHALE IN °F	80	82	67	113	105	103	89	90	86	67	82	79	87	
RECYCLE GAS IN °F	239	247	244	250	246	254	239	242	260	272	254	226	246	
OFF-GAS °F	150	150	150	197	178	195	135	145	197	200	160	146	154	
AIR IN °F	233	229	216	250	250	247	247	247	245	240	232	235	233	
YIELDS:														
OIL COLLECTED wt%F.A.	83.4	91.3	126.4	89.2	95.4	93.2	92.6	82.8	84.6	88.6	86.3	90.1	96.1	
PRODUCT GAS (WET) SCF/T	6383	6859	6429	10897	11127	9770	5717	5917	8119	8079	7359	6690	6622	
RETORTED SHALE wt%R.S.	84	84	86	74	75	76	85	83	81	80	82	82	83	
LIQUID WATER lb/ton	8.87	0.54	9.45	5.61	5.87	5.76	5.89	5.22	0.17	0	0.72	0.77	0.56	
ASH BALANCE wt%	101	100	100	100	100	100	100	99	100	100	100	100	100	
ATM N ₂ BALANCE wt%	86	96	90	102	96	97	85	81	89	85	84	80	77	
WATER BALANCE wt%	77	78	73	72	69	73	87	67	68	58	68	56	57	
KEROGEN BALANCE wt%	99	106	166	92	105	98	101	91	100	96	99	102	106	
ORG. CARBON BALANCE wt%	86	90	115	102	107	100	89	82	94	92	92	91	96	
TOT. H ₂ BALANCE wt%	89	91	115	110	115	107	91	85	97	95	94	92	96	
ORG. N ₂ BALANCE wt%	65	66	82	63	66	65	69	64	66	64	66	67	70	
MATERIAL RECOVERY wt%	99	101	104	99	99	99	99	96	98	96	97	97	97	
RAW SHALE PROPERTIES:														
MOISTURE wt%	+	+	+	+	+	+	+	+	1.00 **	+	+	+	+	
FISCHER ASSAY gal/ton	26.0	24.7	25.4	25.5	25.4	26.9	25.7	25.4	26.8	25.0	26.4	25.9	26.2	
FISCHER ASSAY OIL wt%	9.90	9.40	9.70	9.70	9.70	9.50	9.80	9.70	10.20	9.50	10.10	9.90	10.00	
FISCHER ASSAY WATER wt%	1.34	1.35	1.60	1.30	1.30	1.30	1.30	1.50	1.30	1.40	1.40	1.40	1.50	
FISCHER ASSAY GAS LOSS wt%	2.24	2.20	2.30	3.90	3.90	2.70	3.40	3.80	2.50	3.20	2.00	2.40	2.40	
MINERAL CO ₂ wt%	17.71	18.18	18.08	17.69	17.69	16.95	16.98	17.08	17.83	17.91	17.57	17.68	17.68	
IGNITION LOSS wt%	31.17	31.30	28.83	32.02	32.02	32.02	32.54	33.04	33.55	32.87	32.16	32.25	32.47	
CARBON wt%	+	+	+	+	+	+	+	+	17.09 **	+	+	+	+	
HYDROGEN wt%	+	+	+	+	+	+	+	+	1.85 **	+	+	+	+	
NITROGEN wt%	+	+	+	+	+	+	+	+	0.51 **	+	+	+	+	
NOMINAL PART SIZE in.	3/8X2	3/8X2	3/8X2	3/8X2	3/8X2	3/8X2	3/8X2	2X3/8	1.75X3/8	1.75X3/8	1.75X3/8	1.75X3/8	1.75X3/8	
COLLECTED OIL PROPERTIES:														
GRAVITY DEGREE API	21.4	22.1	22.1	19.6	19.4	19.4	21.6	21.4	22.3	21.5	21.1	20.9	21.6	
VISCOSITY SUS@ 130°F	80.2	73.0	69.4	144.6	144.2	148.2	85.8	94.1	73.8	94.0	99.4	107.5	83.8	
VISCOSITY SUS@ 210°F	40.1	39.2	40.0	52.9	52.9	50.6	42.6	42.8	39.8	43.0	43.3	44.9	43.8	
RAMSBOTTOM CARBON wt%	1.15	1.01	0.72	N/A	2.25	2.10	1.56	1.72	1.11	1.33	1.16	1.67	1.43	
WATER CONTENT vol%	4.72	0.30	3.40	2.9	2.90	2.90	2.90	2.90	0.10	0	0.40	0.40	0.30	
SOLIDS BOTTOM SED. wt%	0.11	0	0	Trace	Trace	Trace	0.09	Trace	Trace	Trace	0.30	0.40	Trace	
CARBON wt%	+	+	+	+	+	+	+	+	84.65 **	+	+	+	+	
HYDROGEN wt%	+	+	+	+	+	+	+	+	11.49 **	+	+	+	+	
NITROGEN wt%	+	+	+	+	+	+	+	+	2.02 **	+	+	+	+	
PRODUCT GAS PROPERTIES:														
MOISTURE vol%	+	+	+	+	+	+	+	+	20 **	+	+	+	+	
ANALYSIS (DRY BASIS)														
H ₂ vol%	+	+	+	+	+	+	3.17 **	+	+	+	+	+	+	
N ₂ vol%	+	+	+	+	+	+	52.57 **	+	+	+	+	+	+	
O ₂ vol%	+	+	+	+	+	+	0.05 **	+	+	+	+	+	+	
CO vol%	+	+	+	+	+	+	2.80 **	+	+	+	+	+	+	
CH ₄ vol%	+	+	+	+	+	+	1.31 **	+	+	+	+	+	+	
CO ₂ vol%	+	+	+	+	+	+	28.56 **	+	+	+	+	+	+	
C ₂ H ₄ vol%	+	+	+	+	+	+	0.45 **	+	+	+	+	+	+	
C ₂ H ₆ vol%	+	+	+	+	+	+	0.29 **	+	+	+	+	+	+	
C ₃ 's vol%	+	+	+	+	+	+	0.27 **	+	+	+	+	+	+	
C ₄ 's vol%	+	+	+	+	+	+	0.07 **	+	+	+	+	+	+	
C ₅ +s vol%	+	+	+	+	+	+	0.43 **	+	+	+	+	+	+	
GROSS HEAT VALUE BTU/SCF	+	+	+	+	+	+	83 **	+	+	+	+	+	+	
SPECIFIC GRAVITY	+	+	+	+	+	+	1.117 **	+	+	+	+	+	+	
RETORTED SHALE PROPERTIES:														
FISCHER ASSAY gal/ton	0.12	N/A	N/A	1.20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
FISCHER ASSAY OIL wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
FISCHER ASSAY WATER wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
FISCHER ASSAY GAS LOSS wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
MINERAL CO ₂ wt%	15.23	15.28	14.97	7.02	6.48	8.50	16.16	15.56	12.91	12.33	14.13	14.14	14.92	
ORGANIC CARBON wt%	2.09	2.07	2.16	4.33	4.47	3.92	1.83	2.00	2.72	2.88	2.39	3.50	2.17	
IGNITION LOSS wt%	17.00	12.17	15.90	7.58	8.46	11.01	19.90	19.18	15.62	15.04	16.33	16.99	17.52	
CARBON wt%	+	+	+	+	+	+	+	+	6.24 **	+	+	+	+	
HYDROGEN wt%	+	+	+	+	+	+	+	+	0.16 **	+	+	+	+	
NITROGEN wt%	+	+	+	+	+	+	+	+	0.20 **	+	+	+	+	
MISCELLANEOUS:														
RETORT DROP in.H ₂ O/ft	0.79	0.94	1.06	0.16	0.12	0.33	0.51	0.61	1.42	1.42	1.63	1.81	1.05	
CARBONATE DECOMP wt%	28	30	29	71	73	61	19	25	42	45	34	34	30	
RED HEIGHT ft	24.54	24.54	24.54	23.5	23.5	23.5	23.5	23.5	23.5	23.5	23.5	23.5	23.5	

* DESIGNATED VALUES SEE TABLE D-1

TABLE D-2 (CONT.)

* DESIGNATED VALUES SEE TABLE D-1

TEST DATA FROM PILOT PLANT — DIRECT HEATED
TABLE D-2 (CONT.)

GENERAL: RUN NUMBER TEST NUMBER	PP-10 D	PP-10 D-2	PP-16 A-1	PP-16 A-2	PP-16 A-3	PP-16 A-4	PP-16 A-5	PP-16 A-6	PP-16 A-7	PP-16 B-1	PP-16 B-2	PP-16 B-3	PP-16 C-1
DATE	12/10/74	12/11/74	12/13/74	12/24/75	12/25/75	12/26/75	12/27/75	12/28/75	12/29/75	1/02/76	1/03/76	1/04/76	1/05/76
START TIME	1900	1000	0800	0800	0800	0800	0800	0800	0800	0800	0800	0800	0800
LENGTH OF TEST	hr	15	23	24	24	24	24	24	24	24	24	24	24
RATES AND QUANTITIES:													
TOP DISTRIBUTOR GAS SCF/T	991	1022	1596	1537	1537	1537	1521	1526	1515	1468	1437	1402	1738
MID DISTRIBUTOR GAS SCF/T	1445	1521	1513	1506	1519	1518	1509	1532	1479	1957	1940	1915	1645
BTM DISTRIBUTOR GAS SCF/T	12668	13191	14327	14170	13988	13949	13859	13812	13959	14257	13713	13527	14740
TOTAL GAS SCF/T	15104	15734	17436	17213	17044	17004	16889	16870	16953	17682	17090	16844	18123
TOP DISTRIBUTOR AIR SCF/T	1239	3332	4673	4512	4345	4334	4286	4395	4430	4165	4024	4002	4880
MID DISTRIBUTOR AIR SCF/T	2706	1573	1115	971	1031	1051	1014	1021	1022	1884	1838	1843	680
BTM DISTRIBUTOR AIR SCF/T	0	0	0	0	0	0	0	0	0	0	0	0	0
TOTAL AIR SCF/T	2945	4905	5788	5483	5376	5385	5300	5416	5452	6049	5862	5845	5560
SHALE THROUGHPUT lb/hr/ft ²	622	605	380	396	395	396	404	401	400	398	407	409	394
TEMPERATURES:													
PRODUCT OIL °F	144	129	154	164	160	159	141	149	147	141	145	151	167
RETORTED SHALE OUT °F	412	425	367	376	394	390	397	402	393	408	425	433	393
RAW SHALE IN °F	25	49	83	81	76	81	81	75	78	43	66	66	57
RECYCLE GAS IN °F	160	242	319	321	320	320	313	318	317	291	295	294	294
OFF-GAS °F	161	140	154	160	147	152	144	148	146	145	157	156	154
AIR IN °F	180	179	191	195	199	194	189	187	188	173	181	182	185
YIELDS:													
OIL COLLECTED wt% A.	78.7	85.8	85.6	82.5	86.3	90.6	95.4	95.5	90.8	103.3	83.7	88.9	81.7
PRODUCT GAS (WET) SCF/T	5620	5191	8654	8238	8086	8053	7968	8146	8154	9052	8802	8767	8351
RETORTED SHALE wt% S.	84	84	80	76	77	78	78	79	78	78	79	78	77
LIQUID WATER lb/ton	15.74	5.65	0.62	0.94	0.69	0.86	1.09	1.01	0.93	1.87	2.58	2.99	20.29
ASH BALANCE wt%	100	101	100	100	100	100	100	101	100	100	100	100	100
ATM. N ₂ BALANCE wt%	76	70	96	94	94	95	96	94	96	97	96	96	95
WATER BALANCE wt%	56	36	90	69	75	71	69	79	76	78	81	70	71
KEROGEN BALANCE wt%	96	102	91	81	88	93	90	92	90	101	85	94	86
ORG. CARBON BALANCE wt%	82	86	92	81	90	93	90	100	98	106	89	95	88
TOT. H ₂ BALANCE wt%	93	93	99	94	102	103	100	110	110	118	103	108	116
ORG. N ₂ BALANCE wt%	66	69	57	55	58	60	62	59	59	89	65	60	57
MATERIAL RECOVERY wt%	96	94	99	97	98	98	98	99	98	100	98	98	97
RAW SHALE PROPERTIES:													
MOISTURE wt%	1.00 *	→	0.55	0.99	0.95	0.91	0.91	1.01	1.11	1.16	1.10	1.19	1.31
FISCHER ASSAY gal/ton	27.70	28.10	29.60	28.80	29.10	28.0	27.0	27.7	27.4	28.0	26.0	28.1	27.70
FISCHER ASSAY OIL wt%	10.58	10.72	11.31	11.00	11.11	10.71	10.30	10.56	10.47	10.68	9.91	10.72	10.58
FISCHER ASSAY WATER wt%	1.54	1.96	1.63	1.60	1.42	1.44	1.49	1.51	1.48	1.15	1.54	1.70	2.01
FISCHER ASSAY GAS & LOSS wt%	2.36	2.89	2.07	1.95	2.79	2.32	1.80	2.18	1.98	2.04	2.26	1.88	1.96
MINERAL CO ₂ wt%	17.34	17.47	17.61	17.42	17.58	17.90	17.85	17.42	17.59	17.80	17.56	17.66	17.53
IGNITION LOSS wt%	32.12	32.23	33.77	34.25	33.54	33.54	33.88	33.29	33.08	33.10	33.03	33.72	33.56
CARBON wt%	17.09 *	→	17.44	18.00	17.30	17.43	17.61	16.90	16.36	16.79	16.63	17.08	17.06
HYDROGEN wt%	1.85 *	→	1.82	1.89	1.80	1.83	1.85	1.75	1.67	1.79	1.73	1.80	1.72
NITROGEN wt%	0.51 *	→	0.54	0.54	0.54	0.54	0.53	0.54	0.53	0.51	0.53	0.54	0.52
NOMINAL PART. SIZE in.	½X2	½X2	½X2	½X2	½X2	½X2	½X2	½X2	½X2	½X2	½X2	½X2	½X2
COLLECTED OIL PROPERTIES:													
GRAVITY DEGREE API	20.7	21.2	20.4	20.2	20.2	20.3	20.5	20.5	20.3	20.4	20.9	20.9	20.9
VISCOSITY SUS @ 130°F	111.5	97.5	113.6	119.4	115.9	110.1	104.2	108.3	102.4	104.5	99.7	99.7	103.1
VISCOSITY SUS @ 210°F	44.7	43.1	50.9	51.7	51.5	50.7	49.8	53.7	50.9	50.8	50.6	50.6	50.6
RAMSBOTTOM CARBON wt%	1.83	1.81	1.88	1.72	1.79	1.67	1.55	1.50	1.72	1.91	1.76	1.74	1.99
WATER CONTENT vol%	7.77	2.63	0.32	0.46	0.32	0.42	0.51	0.44	0.46	0.78	1.49	1.40	9.78
SOLIDS BOTTOM SED. wt%	1.98	0.66	0.32	0.10	0.10	0.10	0.10	0.10	Trace	Trace	0.14	0.14	0.28
CARBON wt%	→	→	→	→	→	→	→	→	→	→	→	→	→
HYDROGEN wt%	→	→	→	→	→	→	→	→	→	→	→	→	→
NITROGEN wt%	→	→	→	→	→	→	→	→	→	→	→	→	→
PRODUCT GAS PROPERTIES:													
MOISTURE vol%	→	→	→	→	→	→	→	→	→	→	→	→	→
ANALYSIS (DRY BASIS)													
H ₂ vol%	5.01	4.70	0	2.95	2.99	2.76	2.76	2.99	1.85	2.61	3.10	3.14	3.53
N ₂ vol%	63.94	65.29	63.32	62.02	61.60	63.02	63.02	6.20	63.54	63.97	63.36	63.00	62.66
O ₂ vol%	0	0	0	0	0	0	0	0	0	0.31	0	0	0
CO vol%	2.30	2.49	3.24	2.72	2.72	2.37	2.36	2.76	3.02	2.44	2.33	2.46	2.92
CH ₄ vol%	2.25	2.41	1.05	1.06	1.04	1.13	1.12	1.18	1.26	1.35	1.46	1.59	1.37
CO ₂ vol%	24.16	22.47	31.21	29.97	30.34	29.32	29.33	29.37	28.77	27.68	28.14	28.01	27.94
C ₂ H ₆ vol%	0.61	0.68	0.32	0.36	0.36	0.37	0.37	0.40	0.43	0.48	0.53	0.56	0.49
C ₃ H ₈ vol%	0.54	0.65	0.23	0.24	0.24	0.26	0.26	0.27	0.30	0.30	0.30	0.38	0.28
C ₄ 's vol%	0.62	0.73	0.20	0.21	0.20	0.25	0.24	0.24	0.29	0.29	0.28	0.30	0.28
C ₅ 's vol%	0.15	0.15	0	0.05	0.09	0.07	0.07	0.09	0.11	0.13	0.08	0.12	0.11
C ₆ +s vol%	→	→	→	→	→	→	→	→	→	→	→	→	→
GROSS HEAT. VALUE BTU/SCF	114	121	62	73	74	76	76	78	79	82	83	90	86
SPECIFIC GRAVITY	1.074	1.068	1.159	1.126	1.129	1.125	1.125	1.123	1.130	1.117	1.114	1.113	1.110
RETORTED SHALE PROPERTIES:													
FISCHER ASSAY gal/ton	N/A	N/A	0.30	0.20	0.30	0.30	0.30	0.30	0.30	0.20	0.20	0.30	0.50
FISCHER ASSAY OIL wt%	N/A	N/A	0.10	0.08	0.10	0.10	0.10	0.11	0.10	0.08	0.09	0.11	0.20
FISCHER ASSAY WATER wt%	N/A	N/A	0.16	0.17	0.13	0.21	0.03	0.04	0.10	0	0	0.04	0.32
FISCHER ASSAY GAS & LOSS wt%	N/A	N/A	0.03	0.11	0.07	0.10	0.09	0.03	0.08	0.12	0.12	0.15	0
MINERAL CO ₂ wt%	15.57	15.63	12.41	12.20	12.64	13.03	13.03	13.22	13.46	12.65	13.21	12.78	12.20
ORGANIC CARBON wt%	1.99	1.98	1.52	1.43	1.58	2.10	1.80	1.90	1.50	1.42	1.46	1.76	2.12
IGNITION LOSS wt%	18.34	18.00	13.40	13.19	13.54	14.44	14.13	13.81	14.02	13.22	13.97	14.14	13.42
CARBON wt%	6.24 *	→	4.91	4.76	5.03	5.65	5.35	5.50	5.17	4.87	5.06	5.23	5.45
HYDROGEN wt%	0.16 *	→	0.09	0.09	0.12	0.14	0.10	0.11	0.11	0.11	0.11	0.12	0.12
NITROGEN wt%	0.20 *	→	0.15	0.15	0.16	0.17	0.17	0.15	0.16	0.30	0.23	0.17	0.16
MISCELLANEOUS:													
RETORT DROP in. H ₂ O/ft	1.29	1.33	N/A	0.68	1.06	N/A	N/A	N/A	0.62	0.65	0.67	0.68	0.65
CARBONATE DECOMP. wt%	25	25	46	47	44	43	44	40	40	45	41	44	46
RFD HEIGHT ft	23.5	23.5	24.08	24.08	24.08	24.08	24.08	24.08	24.08	24.08	24.08	24.08	24.08

* DESIGNATED VALUES SEE TABLE D-1

TEST DATA FROM PILOT PLANT --- DIRECT HEATED
TABLE D-2 (CONT.)

GENERAL: RUN NUMBER TEST NUMBER	PP-16 C-3	PP-16 C-4	PP-16 D-1	PP-16 A-8	PP-16 A-9	PP-19 J	PP-19 K	PP-19 J											
DATE	1/7/76	1/8/76	1/11/76	1/27/76	1/30/76	4/9/76	4/10/76	4/11/76											
START TIME	0800	0800	2400	0800	0800	2000	1800	1000											
LENGTH OF TEST hrs	24	24	28	48	72	14	14	24											
RATES AND QUANTITIES:																			
TOP DISTRIBUTOR GAS SCF/T	1827	1757	1515	1653	1412	1415	757	641											
MID DISTRIBUTOR GAS SCF/T	1682	1616	1480	1575	1354	1616	1386	1484											
BTM DISTRIBUTOR GAS SCF/T	15016	14590	13497	14677	12270	14994	14555	13599											
TOTAL GAS SCF/T	18528	17963	16492	17905	15536	18025	16698	15724											
TOP DISTRIBUTOR AIR SCF/T	5216	5014	4190	4281	3812	4843	3360	2871											
MID DISTRIBUTOR AIR SCF/T	601	576	1323	1006	876	849	2494	2299											
BTM DISTRIBUTOR AIR SCF/T	0	0	0	0	0	0	272	0											
TOTAL AIR SCF/T	5817	5590	5513	5287	4688	5694	6126	5170											
SHALE THROUGHPUT lb/hr/ft ²	385	398	420	407	459	387	402	425											
TEMPERATURES:																			
PRODUCT OIL °F	77	171	175	170	160	105	140	140											
RETORTED SHALE OUT °F	401	379	443	365	440	369	454	435											
RAW SHALE IN °F	33	71	76	60	60	70	70	70											
RECYCLE GAS IN °F	295	296	296	272	270	256	260	260											
OFF-GAS °F	153	158	145	155	130	169	156	143											
AIR IN °F	182	185	191	190	193	206	210	220											
YIELDS:																			
OIL COLLECTED wt% A.	87.7	87.1	90.5	98.2	80.6	86.1	86.8	90.2											
PRODUCT GAS (WET) SCF/T	8725	8388	8298	7904	7009	8553	9203	7736											
RETORTED SHALE wt% S.	75	77	77	82	81	74	76	74											
LIQUID WATER lb/ton	22.50	15.49	2.34	15.40	16.90	11.28	8.16	0.40											
ASH BALANCE wt%	100	100	100	101	100	100	101	100											
ATM N ₂ BALANCE wt%	95	94	98	89	94	93	94	90											
WATER BALANCE wt%	70	74	54	108	84	68	77	41											
KEROGEN BALANCE wt%	81	87	95	101	85	87	91	88											
ORG. CARBON BALANCE wt%	84	89	95	101	84	83	88	80											
TOT. H ₂ BALANCE wt%	113	107	108	118	101	103	109	105											
ORG. N ₂ BALANCE wt%	51	52	59	68	65	59	71	62											
MATERIAL RECOVERY wt%	96	97	97	101	98	97	99	94											
RAW SHALE PROPERTIES:																			
MOISTURE wt%	0.96	1.30	1.51	1.06	0.88	1.04	0.80	1.29											
FISCHER ASSAY gal/ton	26.40	26.8	26.7	27.3	28.3	31.65	31.8	31.6											
FISCHER ASSAY OIL wt%	10.06	10.24	10.20	10.41	10.82	12.09	12.15	12.05											
FISCHER ASSAY WATER wt%	1.52	1.29	1.54	1.98	1.56	1.41	1.43	1.40											
FISCHER ASSAY GAS&LOSS wt%	2.03	1.76	1.76	1.95	2.02	1.97	1.60	2.22											
MINERAL CO ₂ wt%	17.92	17.54	17.50	17.70	17.10	17.64	17.25	17.90											
IGNITION LOSS wt%	33.34	32.25	32.29	33.27	33.59	34.52	34.12	34.79											
CARBON wt%	16.60	16.36	16.06	17.06	17.57	18.72	18.32	18.99											
HYDROGEN wt%	1.71	1.72	1.68	1.79	1.88	1.98	1.93	2.01											
NITROGEN wt%	0.51	0.53	0.50	0.55	0.53	0.51	0.51	0.52											
NOMINAL PART. SIZE in.	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2											
COLLECTED OIL PROPERTIES:																			
GRAVITY DEGREE API	19.8	19.8	20.0	19.7	20.5	19.9	19.7	20.2											
VISCOSITY SUS @ 130°F	123.1	122.2	116.3	112.1	98.9	125.9	128.8	112.2											
VISCOSITY SUS @ 210°F	53.5	52.7	51.5	53.6	50.3	52.1	49.7	51.8											
RAMSBOTTOM CARBON wt%	20.50	1.94	2.01	2.01	1.92	2.33	2.29	2.24											
WATER CONTENT vol%	10.60	7.49	1.16	6.50	8.20	4.80	3.47	0.17											
SOLIDS BOTTOM SED. wt%	0.16	0.16	0.15	0.15	0.22	0.23	0.24	0											
CARBON wt%			84.65 *			83.63	83.93	83.93											
HYDROGEN wt%			11.49 *			11.60	11.59	11.59											
NITROGEN wt%			2.02 *			2.27	2.28	2.28											
PRODUCT GAS PROPERTIES:																			
MOISTURE vol%				20 *															
ANALYSIS (DRY BASIS)																			
H ₂ vol%	3.39	2.98	2.80	7.85	4.77	4.28	4.24	6.57											
N ₂ vol%	62.70	62.11	64.10	58.61	62.03	60.80	61.72	59.34											
O ₂ vol%	0.10	0.07	0	0.12	0.39	0	0	0.50											
CO vol%	3.28	3.18	2.11	3.28	2.98	4.08	3.49	3.88											
CH ₄ vol%	1.22	0.99	1.22	1.09	2.68	1.00	1.25	2.49											
CO ₂ vol%	27.73	29.43	28.43	27.85	24.57	28.68	28.06	24.99											
C ₂ H ₄ vol%	0.50	0.32	0.42	0.32	0.79	0.30	0.39	0.62											
C ₂ H ₆ vol%	0.28	0.23	0.27	0.24	0.66	0.23	0.26	0.59											
C ₃ 's vol%	0.28	0.21	0.23	0.21	0.58	0.21	0.12	0.48											
C ₄ 's vol%	0.10	0.05	0	0	0.12	0	0.06	0.13											
C ₅ + 's vol%				0.43 *															
GROSS HEAT. VALUE BTU/SCF	85	74	71	90	123	79	81	124											
SPECIFIC GRAVITY	1.111	1.124	1.118	1.070	1.077	1.107	1.103	1.063											
RETORTED SHALE PROPERTIES:																			
FISCHER ASSAY gal/ton	0.20	0.20	0.20	0.20	0.30	0.24	0.20	0.21											
FISCHER ASSAY OIL wt%	0.06	0.05	0.07	0.09	0.10	0.09	0.08	0.08											
FISCHER ASSAY WATER wt%	0.14	0.25	0.17	0.19	0.23	0.16	0.11	0.11											
FISCHER ASSAY GAS&LOSS wt%	0.02	0.10	0.09	0.09	0.02	0.17	0.16	0.06											
MINERAL CO ₂ wt%	10.43	10.94	10.73	15.80	15.08	10.89	10.80	10.38											
ORGANIC CARBON wt%	1.11	1.34	1.81	1.61	1.67	1.49	1.48	1.44											
IGNITION LOSS wt%	10.53	11.53	12.26	16.68	16.70	11.84	11.92	11.23											
CARBON wt%	3.95	4.32	4.74	5.92	5.78	4.46	4.42	4.27											
HYDROGEN wt%	0.09	0.09	0.10	0.18	0.15	0.11	0.12	0.10											
NITROGEN wt%	0.11	0.13	0.14	0.21	0.21	0.09	0.16	0.10											
MISCELLANEOUS:																			
RETORT DROP in. H ₂ O/ft	0.65	0.57	0.55	0.67	0.60	0.59	0.66	N/A											
CARBONATE DECOMP wt%	56	52	52	27	29	54	52	57											
RED HEIGHT ft	24.08	24.08	24.08	24.08	24.08	24.08	24.08	24.08											

* DESIGNATED VALUES. SEE TABLE D-1

TEST DATA FROM PILOT PLANT — DIRECT HEATED

Run No.	Time, hr	Temp, °F	Flow, gpm	Pressure, psi	Heat, Btu/hr	Efficiency, %	Remarks
1	0.5	100	1.0	100	1000	100	
2	1.0	100	1.0	100	1000	100	
3	1.5	100	1.0	100	1000	100	
4	2.0	100	1.0	100	1000	100	
5	2.5	100	1.0	100	1000	100	
6	3.0	100	1.0	100	1000	100	
7	3.5	100	1.0	100	1000	100	
8	4.0	100	1.0	100	1000	100	
9	4.5	100	1.0	100	1000	100	
10	5.0	100	1.0	100	1000	100	
11	5.5	100	1.0	100	1000	100	
12	6.0	100	1.0	100	1000	100	
13	6.5	100	1.0	100	1000	100	
14	7.0	100	1.0	100	1000	100	
15	7.5	100	1.0	100	1000	100	
16	8.0	100	1.0	100	1000	100	
17	8.5	100	1.0	100	1000	100	
18	9.0	100	1.0	100	1000	100	
19	9.5	100	1.0	100	1000	100	
20	10.0	100	1.0	100	1000	100	
21	10.5	100	1.0	100	1000	100	
22	11.0	100	1.0	100	1000	100	
23	11.5	100	1.0	100	1000	100	
24	12.0	100	1.0	100	1000	100	
25	12.5	100	1.0	100	1000	100	
26	13.0	100	1.0	100	1000	100	
27	13.5	100	1.0	100	1000	100	
28	14.0	100	1.0	100	1000	100	
29	14.5	100	1.0	100	1000	100	
30	15.0	100	1.0	100	1000	100	
31	15.5	100	1.0	100	1000	100	
32	16.0	100	1.0	100	1000	100	
33	16.5	100	1.0	100	1000	100	
34	17.0	100	1.0	100	1000	100	
35	17.5	100	1.0	100	1000	100	
36	18.0	100	1.0	100	1000	100	
37	18.5	100	1.0	100	1000	100	
38	19.0	100	1.0	100	1000	100	
39	19.5	100	1.0	100	1000	100	
40	20.0	100	1.0	100	1000	100	
41	20.5	100	1.0	100	1000	100	
42	21.0	100	1.0	100	1000	100	
43	21.5	100	1.0	100	1000	100	
44	22.0	100	1.0	100	1000	100	
45	22.5	100	1.0	100	1000	100	
46	23.0	100	1.0	100	1000	100	
47	23.5	100	1.0	100	1000	100	
48	24.0	100	1.0	100	1000	100	
49	24.5	100	1.0	100	1000	100	
50	25.0	100	1.0	100	1000	100	
51	25.5	100	1.0	100	1000	100	
52	26.0	100	1.0	100	1000	100	
53	26.5	100	1.0	100	1000	100	
54	27.0	100	1.0	100	1000	100	
55	27.5	100	1.0	100	1000	100	
56	28.0	100	1.0	100	1000	100	
57	28.5	100	1.0	100	1000	100	
58	29.0	100	1.0	100	1000	100	
59	29.5	100	1.0	100	1000	100	
60	30.0	100	1.0	100	1000	100	
61	30.5	100	1.0	100	1000	100	
62	31.0	100	1.0	100	1000	100	
63	31.5	100	1.0	100	1000	100	
64	32.0	100	1.0	100	1000	100	
65	32.5	100	1.0	100	1000	100	
66	33.0	100	1.0	100	1000	100	
67	33.5	100	1.0	100	1000	100	
68	34.0	100	1.0	100	1000	100	
69	34.5	100	1.0	100	1000	100	
70	35.0	100	1.0	100	1000	100	
71	35.5	100	1.0	100	1000	100	
72	36.0	100	1.0	100	1000	100	
73	36.5	100	1.0	100	1000	100	
74	37.0	100	1.0	100	1000	100	
75	37.5	100	1.0	100	1000	100	
76	38.0	100	1.0	100	1000	100	
77	38.5	100	1.0	100	1000	100	
78	39.0	100	1.0	100	1000	100	
79	39.5	100	1.0	100	1000	100	
80	40.0	100	1.0	100	1000	100	
81	40.5	100	1.0	100	1000	100	
82	41.0	100	1.0	100	1000	100	
83	41.5	100	1.0	100	1000	100	
84	42.0	100	1.0	100	1000	100	
85	42.5	100	1.0	100	1000	100	
86	43.0	100	1.0	100	1000	100	
87	43.5	100	1.0	100	1000	100	
88	44.0	100	1.0	100	1000	100	
89	44.5	100	1.0	100	1000	100	
90	45.0	100	1.0	100	1000	100	
91	45.5	100	1.0	100	1000	100	
92	46.0	100	1.0	100	1000	100	
93	46.5	100	1.0	100	1000	100	
94	47.0	100	1.0	100	1000	100	
95	47.5	100	1.0	100	1000	100	
96	48.0	100	1.0	100	1000	100	
97	48.5	100	1.0	100	1000	100	
98	49.0	100	1.0	100	1000	100	
99	49.5	100	1.0	100	1000	100	
100	50.0	100	1.0	100	1000	100	

TEST DATA FROM SEMI-WORKS — DIRECT HEATED

TABLE D-3

GENERAL: RUN NUMBER TEST NUMBER	SW-5 A-1	SW-5 A-2	SW-5 A-3	SW-5 A-4	SW-7 A	SW-7 B	SW-7 D	SW-7 E	SW-7 H-1	SW-7 J	SW-7 K	SW-7 K-1	SW-7 K-2
DATE	12/24/74	12/26/74	12/28/74	12/29/74	1/20/75	1/22/75	1/23/75	1/24/75	1/28/75	1/29/75	1/30/75	2/7/75	2/8/75
START TIME	1600	2400	0800	0800	1600	1600	2400	2400	0800	1600	2400	2400	0800
LENGTH OF TEST HRS.	24	32	8	8	40	16	8	8	24	24	32	8	24
RATES AND QUANTITIES:													
TOP DISTRIBUTOR GAS SCF/T	1458	1218	1276	1250	1818	1911	1583	1357	1844	1374	1181	1307	1283
MID DISTRIBUTOR GAS SCF/T	1646	1709	1806	1782	1938	1837	1561	1375	1742	1575	1491	1500	1498
BTM DISTRIBUTOR GAS SCF/T	13825	15141	15363	15132	13653	14537	13847	12480	13770	14003	14886	13322	13097
TOTAL GAS SCF/T	16929	18068	18445	18164	17409	18285	16991	15212	17356	16952	17558	16129	15878
TOP DISTRIBUTOR AIR SCF/T	2883	3492	3690	3605	5555	5781	4789	3792	5474	4852	4280	4735	4577
MID DISTRIBUTOR AIR SCF/T	1538	1686	1751	1740	0	0	330	373	0	329	408	546	450
BTM DISTRIBUTOR AIR SCF/T	0	0	0	0	0	0	0	0	0	0	0	0	0
TOTAL AIR SCF/T	4421	5178	5441	5345	5555	5781	5119	4165	5474	5181	4688	5281	5027
SHALE THROUGHPUT lb/hr/ft ²	451	422	401	408	343	362	435	549	383	436	502	455	465
TEMPERATURES:													
PRODUCT OIL °F	155	156	155	156	155	155	155	160	185	195	194	174	169
RETORTED SHALE OUT °F	373	349	336	324	325	328	337	376	277	328	302	369	377
RAW SHALE IN °F	30	30	30	30	33	30	30	35	38	37	40	47	42
RECYCLE GAS IN °F	176	176	187	170	281	282	250	267	267	268	271	265	263
OFF-GAS °F	177	184	196	176	174	175	187	174	177	174	193	155	157
AIR IN °F	150	150	150	150	235	231	230	231	223	231	231	231	240
YIELDS:													
OIL COLLECTED wt% A.	93.4	92.0	83.3	93.8	96.1	100.3	90.3	86.2	84.8	81.3	84.4	90.4	83.4
PRODUCT GAS (WET) SCF/T	7331	8001	8396	8191	9641	9375	7861	6054	8309	7627	6481	7467	5912
RETORTED SHALE wt% S.	84	81	82	81	78	79	82	85	78	82	82	80	82
LIQUID WATER lb/ton	0.32	0.51	0.30	0.32	0.39	0.50	4.73	4.45	10.30	2.52	0.99	0.21	0.66
ASH BALANCE wt%	100	99	100	100	100	100	100	100	99	100	100	100	100
ATM. N ₂ BALANCE wt%	107	97	97	97	108	102	99	96	94	91	87	87	74
WATER BALANCE wt%	86	76	74	69	95	85	63	58	67	67	55	48	39
KEROGEN BALANCE wt%	110	102	102	107	106	109	110	104	99	103	95	109	99
ORG. CARBON BALANCE wt%	96	96	92	101	100	107	97	94	100	89	88	91	84
TOTAL H ₂ BALANCE wt%	105	105	99	109	113	125	108	126	109	101	101	101	94
ORG. N ₂ BALANCE wt%	69	67	64	69	60	69	74	73	68	59	65	69	65
MATERIAL RECOVERY wt%	103	100	100	100	103	102	100	99	98	99	97	97	94
RAW SHALE PROPERTIES:													
MOISTURE wt%								1.00 *					
FISCHER ASSAY gal/ton	26.0	25.6	25.4	26.6	28.5	27.7	27.4	27.00	29.8	27.2	27.6	26.0	26.6
FISCHER ASSAY OIL wt%	9.9	9.8	9.7	10.2	10.9	10.56	10.46	10.30	11.36	10.41	10.51	9.94	10.17
FISCHER ASSAY WATER wt%	1.7	1.8	1.75	1.6	1.83	1.79	1.85	1.89	1.75	1.73	1.67	1.69	1.68
FISCHER ASSAY GAS LOSS wt%	2.2	2.5	2.1	2.2	2.55	2.33	2.47	2.36	2.41	1.95	2.39	1.98	2.01
MINERAL CO ₂ wt%	16.87	17.12	17.46	17.25	17.41	13.48	17.58	17.73	17.88	17.63	17.04	18.82	18.34
IGNITION LOSS wt%	31.50	32.48	31.63	31.94	33.44	33.29	32.36	32.76	33.19	31.76	32.74	32.24	32.37
CARBON wt%			17.09 *		17.91	16.97	17.09 *	17.03	17.09 *	16.81	16.51	16.69	16.26
HYDROGEN wt%			1.85 *		1.92	1.75	1.85 *	1.51	1.85 *	1.77	1.74	1.74	1.71
NITROGEN wt%			0.51 *		0.60	0.53	0.51 *	0.56	0.51 *	0.55	0.53	0.50	0.52
NOMINAL PART. SIZE in.	3/8X2	3/8X2	3/8X2	3/8X2	1/2X2	1/2X2	1/2X2	1/2X2	1/2X2	1/2X2	1/2X2	1/2X2	1/2X2
COLLECTED OIL PROPERTIES:													
GRAVITY DEGREE API	20.6	20.4	19.7	19.9	19.6	19.7	19.6	20.0	19.4	19.9	19.3	19.9	20.1
VISCOSITY SUS @ 130°F	115.4	119.6	134.1	130.7	150.5	141.0	144.4	119.2	141.7	126.1	142.3	125.2	124.4
VISCOSITY SUS @ 210°F	44.8	45.4	46.7	46.7	48.5	47.3	47.6	44.8	47.8	45.9	47.6	46.0	43.7
RAMSBOTTOM CARBON wt%	1.78	1.73	1.65	1.97	2.24	N/A	2.30	1.98	2.19	1.83	2.18	1.86	1.75
WATER CONTENT vol%	0.15	0.27	0.18	0.16	0.17	0.21	0.04	0.08	0.29	0.21	0.24	0.12	0.35
SOLIDS BOTTOM SED. wt%	0.29	0.54	0.43	0.30	0.30	0.39	0.48	1.25	0.36	0.30	0.70	0.18	0.16
CARBON wt%				84.65 *			84.84		84.65 *		84.20	84.00	84.34
HYDROGEN wt%				11.49 *			11.36		11.49 *		11.19	11.11	11.19
NITROGEN wt%				2.02 *			2.27		2.02 *		2.21	2.15	2.26
PRODUCT GAS PROPERTIES:													
MOISTURE vol%								20 *					
ANALYSIS (DRY BASIS)													
H ₂ vol%	5.21	5.53	4.60	5.18	5.03	5.04	5.74	5.50	4.99	5.45	5.59	4.88	4.94
N ₂ vol%	63.52	62.11	62.26	62.25	61.33	62.25	63.77	65.16	61.10	61.23	62.35	61.05	62.17
O ₂ vol%	0	0	0	0	0.15	0.13	0.10	0.37	0.24	0.17	0.29	0.03	0.97
CO vol%	2.70	2.18	2.83	3.15	4.04	3.38	3.76	2.83	4.26	4.04	3.53	3.62	3.49
CH ₄ vol%	2.55	2.18	2.07	2.29	1.59	1.64	2.19	2.60	1.53	1.75	2.26	1.56	1.69
CO ₂ vol%	23.21	25.70	26.01	24.71	26.11	25.70	22.02	20.44	26.33	25.51	23.40	27.02	24.79
C ₂ H ₆ vol%	0.77	0.72	0.78	0.76	0.55	0.52	0.73	0.89	0.45	0.55	0.80	0.46	0.52
C ₃ H ₈ vol%	0.64	0.49	0.43	0.51	0.35	0.38	0.52	0.67	0.33	0.38	0.52	0.37	0.40
C ₄ 's vol%	0.68	0.50	0.44	0.53	0.35	0.42	0.52	0.80	0.34	0.44	0.59	0.39	0.44
C ₅ +s vol%	0.29	0.16	0.15	0.21	0.06	0.12	0.21	0.32	0	0.05	0.25	0.21	0.18
C ₅ +s vol%							0.43 *						
CROSS HEAT. VALUE BTU/SCF	129	113	109	119	100	101	122	138	95	105	126	102	104
SPECIFIC GRAVITY	1.068	1.078	1.088	1.076	1.085	1.084	1.056	1.051	1.086	1.078	1.066	1.093	1.081
RETORTED SHALE PROPERTIES:													
FISCHER ASSAY gal/ton	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
FISCHER ASSAY OIL wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
FISCHER ASSAY WATER wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
FISCHER ASSAY GAS LOSS wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
MINERAL CO ₂ wt%	15.64	14.52	13.59	13.56	12.89	13.48	14.42	17.14	12.59	14.16	15.12	13.00	14.81
ORGANIC CARBON wt%	1.98	2.28	2.53	2.54	1.96	1.79	2.31	2.42	2.81	1.73	1.40	1.89	1.49
IGNITION LOSS wt%	17.98	16.82	15.60	15.42	14.51	15.15	16.84	19.90	14.26	16.11	17.56	14.94	17.07
CARBON wt%			6.24 *		5.47	5.47	6.24 *	7.09	6.24 *	5.59	5.52	5.43	5.53
HYDROGEN wt%			0.16 *		0.15	0.15	0.16 *	0.27	0.16 *	0.16	0.14	0.12	0.14
NITROGEN wt%			0.20 *		0.19	0.19	0.20 *	0.27	0.20 *	0.19	0.18	0.19	0.18
MISCELLANEOUS:													
RETORT DROP in. H ₂ O/ft	1.76	1.67	1.46	1.61	0.92	1.02	1.27	1.40	0.65	1.27	1.89	1.34	1.51
CARBONATE DECOMP. wt%	22	31	37	36	42	39	33	18	45	34	27	45	34
BED HEIGHT ft	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58

* DESIGNATED VALUES SEE TABLE D-1

TABLE D-3 (CONT.)

* DESIGNATED VALUE SEE TABLE D-1

TEST DATA FROM SEMI-WORKS — DIRECT HEATED

TABLE D-3 (CONT.)

General: Run Number Test Number	SW-7 PC-2	SW-7 PC-1	SW-7 QC	SW-7 PC-4	SW-7 PC-5	SW-7 PC-6	SW-7 PA-1	SW-7 PA-2	SW-7 PA-3	SW-7 PA-4	SW-7 PA-5	SW-7 PA-6	SW-7 PA-7
Date	2-22-75	2-23-75	2-24-75	2-26-75	2-27-75	2-28-75	3-1-75	3-2-75	3-4-75	3-5-75	3-8-75	3-9-75	1-10-75
Start Time	0800	0800	0800	0800	0800	0800	2400	0800	1600	0800	1600	0800	2400
Length of Test Hrs	8	16	16	24	24	24	8	24	16	24	16	24	6
Rates and Quantities:													
Top Distributor Gas SCF/T	1351	1326	1220	1074	1070	1054	1042	1040	1166	1134	1276	1338	1147
Mid Distributor Gas SCF/T	1524	1513	1533	1469	1501	1469	1440	1456	1076	989	1435	1467	1688
Bot Distributor Gas SCF/T	14414	14217	14225	13903	13973	13593	13429	13603	14489	14593	12895	12420	15376
Total Gas SCF/T	17289	17056	16978	16446	16544	16116	15911	16099	16731	16716	15806	15725	18211
Top Distributor Air SCF/T	3108	3062	3121	2983	3037	2893	2896	2885	3090	3106	987	3290	1688
Mid Distributor Air SCF/T	1536	1544	1544	1480	1473	1424	1434	1434	1172	1055	2793	1433	3297
Bot Distributor Air SCF/T	0	0	0	0	0	0	431	433	463	464	420	435	514
Total Air SCF/T	4644	4616	4665	4463	4510	4317	4761	4752	4725	4625	4200	5158	5499
Shale Throughput lb/hr/ft ²	408	415	443	426	424	435	435	433	405	404	447	437	370
Temperatures:													
Product Oil °F	166	151	162	161	164	171	174	175	173	166	168	162	177
Retorted Shale Out °F	360	359	392	371	375	380	425	431	428	389	339	322	282
Raw Shale In °F	30	30	30	46	60	50	60	50	45	55	45	40	37
Recycle Gas In °F	241	239	248	252	252	248	250	256	242	237	256	251	271
Off-Gas °F	142	144	151	159	161	153	156	163	147	149	176	185	201
Air In °F	246	249	251	258	256	262	254	259	260	259	253	248	249
Yields:													
Oil Collected wt% F.A.	95.3	94.5	86.6	89.4	87.4	84.8	85.4	80.5	92.6	87.6	87.7	82.7	96.5
Product Gas (wet) SCF/T	5062	5001	5275	5154	5097	4778	5300	5331	5092	4794	7227	7461	8802
Retorted Shale wt% R.S.	83	83	83	82	83	83	83	82	83	83	84	85	84
Liquid Water lb/ton	11.25	10.14	7.50	9.10	3.89	5.43	12.90	1.50	2.81	6.25	6.42	5.41	1.91
Ash Balance wt%	100	100	100	100	100	100	100	100	100	100	100	100	100
Atm. N2 Balance wt%	71	71	74	74	73	72	72	76	69	69	111	93	102
Water Balance wt%	42	42	42	41	38	36	44	35	45	38	87	69	85
Kerogen Balance wt%	104	103	105	97	95	92	93	97	99	97	106	114	123
Org. Carbon Balance wt%	96	91	90	85	88	87	88	92	94	87	90	95	108
Tot. H2 Balance wt%	103	103	97	94	95	96	100	101	95	95	103	114	121
Org. N2 Balance wt%	74	77	73	63	70	73	70	78	73	68	58	68	80
Material Recovery wt%	95	95	95	94	94	93	94	94	95	94	102	100	103
Raw Shale Properties:													
Moisture wt%	0.93	1.00	0.95	0.92	1.00	1.07	1.10	1.10	1.00	0.84	1.06	1.35	1.23
Fischer Assay gal/ton	28.7	27.7	30.1	29.0	27.9	27.1	26.6	28.6	29.1	29.0	26.3	26.4	26.4
Fischer Assay Oil wt%	10.98	10.58	11.48	11.07	10.64	10.34	10.18	10.90	11.10	11.10	10.00	10.10	10.10
Fischer Assay Water wt%	1.71	1.52	1.45	1.79	1.80	1.66	1.85	1.50	1.50	1.60	1.60	1.80	2.80
Fischer Assay gas+loss wt%	1.86	2.07	2.38	2.30	2.39	2.49	2.72	1.90	2.60	2.40	2.90	2.50	2.10
Mineral CO ₂ wt%	17.39	17.71	17.45	17.49	17.47	17.78	17.65	17.57	17.02	17.43	17.64	18.12	16.73
Ignition Loss wt%	33.13	32.41	32.49	33.21	33.07	33.01	33.09	33.34	33.26	33.55	32.41	32.13	32.54
Carbon wt%	17.17	17.34	17.89	18.16	17.07	16.76	16.87	17.53	17.77	17.50	17.29	16.59	17.08
Hydrogen wt%	1.83	1.83	1.91	1.93	1.81	1.74	1.76	1.83	1.90	1.83	1.82	1.72	1.79
Nitrogen wt%	0.53	0.55	0.56	0.64	0.54	0.51	0.52	0.53	0.58	0.57	0.59	0.54	0.52
Nominal Part Size in.	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4	3/4x2 3/4
Collected Oil Properties:													
Gravity Degree API	21.6	21.5	21.4	20.7	21.0	21.2	21.2	21.0	21.1	21.1	20.7	20.6	19.9
Viscosity SUS @ 130° F	92.3	95.2	96.2	121.1	106.4	92.4	91.2	99.2	95.1	109.9	105.5	134.5	
Viscosity SUS @ 210° F	42.9	42.3	42.3	44.7	44.7	46.6	47.0	45.6	45.9	46.7	51.0	49.4	52.0
Ramshotton Carbon wt%	1.47	1.60	1.16	1.61	1.41	1.48	1.50	1.52	2.14	2.13	1.73	1.81	1.82
Water Content vol%	0.81	1.48	1.31	0.33	0.65	0.71	0.39	0.40	1.04	1.12	0.39	0.59	0.36
Solids bottom sed. wt%	1.20	1.39	1.23	0.30	0.44	0.78	0.82	0.63	1.34	1.20	0.60	0.52	0.28
Carbon wt%	83.55	84.38	84.19	83.15	83.17	83.96	84.36	83.86	84.12	83.71	84.65	84.33	84.41
Hydrogen wt%	11.24	11.89	11.26	11.15	11.13	11.44	11.59	11.23	11.18	11.22	11.49	11.40	11.40
Nitrogen wt%	2.03	2.26	2.11	2.12	2.03	1.98	1.95	2.07	2.01	2.11	2.02	1.85	2.13
Product Gas Properties:													
Moisture vol%							20						
Analysis (dry basis)													
H ₂ vol%	5.04	5.15	5.41	5.65	5.58	5.43	5.35	4.84	5.19	4.84	5.54	5.58	6.05
N ₂ vol%	64.36	64.55	64.34	62.80	63.42	63.82	63.92	66.53	62.97	65.34	63.67	63.55	62.83
O ₂ vol%	0.14	0.21	0.64	0.10	0.15	0.14	0.20	0.64	0.13	0.22	0.33	0.36	0.33
CO vol%	2.45	2.37	2.38	2.57	2.52	2.42	2.37	2.37	2.88	2.57	2.83	3.04	3.08
CH ₄ vol%	2.46	2.56	2.70	2.72	2.65	2.58	2.52	2.37	2.24	2.29	2.36	2.19	2.35
CO ₂ vol%	22.87	22.40	21.62	23.33	22.87	22.80	22.92	20.70	24.36	22.22	22.88	22.91	22.92
C ₂ H ₄ vol%	0.63	0.64	0.65	0.71	0.72	0.69	0.66	0.60	0.70	0.55	0.68	0.66	0.77
C ₂ H ₆ vol%	0.62	0.65	0.69	0.65	0.64	0.63	0.62	0.59	0.53	0.56	0.55	0.56	0.50
C ₃ 's vol%	0.71	0.76	0.80	0.76	0.74	0.75	0.76	0.68	0.58	0.75	0.57	0.55	0.56
C ₄ 's vol%	0.28	0.29	0.33	0.30	0.29	0.27	0.26	0.24	0	0.23	0.16	0.18	0.19
C ₅ 's vol%							0.43						
Gross Heat Value BTU/SCF	125	129	134	134	132	130	128	120	112	120	120	118	123
Specific Gravity	1.068	1.065	1.059	1.065	1.063	1.064	1.066	1.058	1.072	1.067	1.062	1.063	1.058
Retorted Shale Properties:													
Fischer Assay gal/ton	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	0.40	0.90	N/A
Fischer Assay Oil wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Fischer Assay Water wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Fischer Assay gas+loss wt%	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Mineral CO ₂ wt%	15.70	16.14	15.67	15.48	16.07	16.17	16.08	15.62	16.44	16.30	15.95	16.28	15.55
Organic Carbon wt%	2.40	2.17	2.62	2.44	2.22	2.31	2.45	2.73	2.61	2.21	1.89	2.08	4.57
Ignition Loss wt%	18.40	18.25	18.49	17.53	18.36	18.57	18.47	17.86	19.23	19.18	18.88	19.46	18.74
Carbon wt%	6.68	6.57	6.89	6.66	6.60	6.72	6.83	6.99	7.09	6.65	6.24	6.52	6.84
Hydrogen wt%	0.18	0.17	0.18	0.17	0.17	0.18	0.19	0.22	0.19	0.17	0.16	0.30	0.22
Nitrogen wt%	0.22	0.24	0.24	0.24	0.23	0.24	0.24	0.25	0.26	0.22	0.20	0.25	0.25
Miscellaneous:													
Retort Drop in. H ₂ O/ft	1.32	1.33	1.48	1.21	1.16	1.13	1.21	1.21	1.13	1.12	1.43	1.57	1.55
Carbonate Decomp. wt%	26	24	25	28	24	25	25	27	20	23	24	24	22
Bed Height ft	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58	25.58

DESIGNATED VALUES SEE TABLE D-1

TABLE D-3 (CONT.)

* DESIGNATED VALUES SEE TABLE D-1

TEST DATA FROM SEMI-WORKS — DIRECT HEATED
TABLE D-3 (CONT.)

GENERAL:														
RUN NUMBER TEST NUMBER	SW-8 B-2	SW-8 B-3	SW-8 B-4	SW-9 X	SW-11 A	SW-17 I-1	SW-17 I-2	SW-17 J	SW-19 A	SW-19 A-1	SW-20 11	SW-20 A-1	SW-20 A-2	
DATE	5-12-75	5-13-75	5-15-75	5-30-75	8-21-75	10-20-75	10-21-75	10-22-75	10-31-75	11-1-75	11-6-75	11-7-75	11-8-75	
START TIME	0800	1600	0800	0800	0800	1600	0800	1600	0800	0800	1700	0800	0800	
LENGTH OF TEST HRS.	24	16	16	24	24	16	24	16	24	8	15	24	24	
RATES AND QUANTITIES:														
TOP DISTRIBUTOR GAS SCF/T	856	862	876	717	968	1483	1493	1296	1261	1223	1328	1323	1341	
MID DISTRIBUTOR GAS SCF/T	967	981	967	867	1692	1409	1405	1895	1919	1847	1317	1307	1294	
BTM DISTRIBUTOR GAS SCF/T	13944	12957	13185	12678	12880	12097	12140	13435	11702	11572	11300	11848	11916	
TOTAL GAS SCF/T	15767	14800	15028	14262	15540	14989	15038	16626	14882	14642	13945	14478	14551	
TOP DISTRIBUTOR AIR SCF/T	2891	2796	2815	2592	3126	3359	3436	3130	2943	2869	3664	3622	3686	
MID DISTRIBUTOR AIR SCF/T	962	967	1008	843	1955	1049	1089	1495	1492	1465	815	805	820	
BTM DISTRIBUTOR AIR SCF/T	719	677	684	646	0	0	0	0	0	0	0	0	0	
TOTAL AIR SCF/T	4572	4440	4507	4081	5081	4408	4525	4625	4435	4334	4479	4427	4506	
SHALE THROUGHPUT lb/hr/ft ²	481	489	481	618	501	427	416	402	473	484	466	475	463	
TEMPERATURES:														
PRODUCT OIL °F	185	183	176	181	152	145	143	146	144	142	148	146	141	
RETORTED SHALE OUT °F	365	326	336	422	443	380	373	339	400	413	405	387	386	
RAW SHALE IN °F	50	50	68	60	70	60	60	55	55	45	63	50	53	
RECYCLE GAS IN °F	272	269	265	278	249	269	272	263	247	247	253	246	236	
OFF-GAS °F	190	188	181	200	183	161	170	190	153	146	156	156	148	
AIR IN °F	253	261	271	251	269	235	235	219	221	227	195	206	196	
YIELDS:														
OIL COLLECTED wt% F.A.	80.3	81.9	80.3	76.3	84.7	81.1	74.6	79.2	89.9	94.8	85.4	89.6	92.0	
PRODUCT GAS (WET) SCF/T	7073	6877	6916	6252	7070	6816	6942	7235	7292	7067	7129	7098	6799	
RETORTED SHALE wt% R.S.	83	84	81	84	82	82	81	82	82	82	82	81	81	
LIQUID WATER lb/ton	0.56	0.73	0.65	0.30	0.70	1.96	6.43	5.02	6.72	11.38	4.00	7.42	5.23	
ASH BALANCE wt%	100	100	100	101	100	100	99	100	100	100	100	100	99	
ATM. N ₂ BALANCE wt%	102	104	99	102	88	84	96	97	100	105	100	102	99	
WATER BALANCE wt%	69	73	75	58	62	99	82	71	87	84	77	64	63	
KEROGEN BALANCE wt%	97	99	89	95	97	90	88	91	100	104	98	100	98	
ORG. CARBON BALANCE wt%	91	92	86	89	92	87	83	86	97	104	92	95	95	
TOT. N ₂ BALANCE wt%	103	103	99	96	105	111	98	106	113	114	109	109	100	
ORG. N ₂ BALANCE wt%	70	73	67	77	67	61	51	64	66	60	64	70	69	
MATERIAL RECOVERY wt%	100	100	99	99	98	98	98	98	101	102	100	100	99	
RAW SHALE PROPERTIES:														
MOISTURE wt%	0.84	0.71	0.87	0.89	1.19	0.58	0.82	1.53	1.32	0.75	0.94	1.04	0.97	
FISCHER ASSAY gal/ton	28.5	27.8	29.9	28.8	28.3	28.2	28.0	25.0	26.3	26.0	28.6	27.1	27.0	
FISCHER ASSAY OIL wt%	10.90	10.60	11.40	11.00	10.80	10.80	10.70	9.52	10.04	9.90	10.91	10.36	10.29	
FISCHER ASSAY WATER wt%	1.60	1.60	1.50	1.70	1.60	1.80	1.70	2.10	1.73	1.65	1.54	1.71	1.46	
FISCHER ASSAY gas + loss wt%	2.40	2.40	2.50	2.30	2.40	2.00	1.80	1.60	2.14	1.99	2.17	2.20	2.23	
MINERAL CO ₂ wt%	17.69	17.66	17.32	18.28	17.16	17.95	17.79	17.56	17.42	17.52	17.71	17.84	17.30	
IGNITION LOSS wt%	33.61	33.16	34.58	33.21	33.34	32.90	32.81	32.20	32.76	32.59	33.48	33.24	33.14	
CARBON wt%	17.50	17.14	18.64	17.28	17.25	16.89	16.88	15.96	16.57	16.12	17.45	17.07	17.03	
HYDROGEN wt%	1.84	1.81	1.92	1.84	1.79	1.77	1.77	1.66	1.74	1.75	1.84	1.80	1.90	
NITROGEN wt%	0.57	0.54	0.57	0.50	0.51	0.56	0.64	0.57	0.50	0.53	0.52	0.51	0.49	
NOMINAL PART. SIZE in.	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	5/8x3/4	5/8x3/4	1/2-3/4	1/2-3/4	1/2-3/4	
COLLECTED OIL PROPERTIES:														
GRAVITY DEGREE API	20.5	21.1	21.1	20.5	21.3	20.7	21.0	21.1	21.4	21.5	21.4	21.3	21.4	
VISCOSITY SUS @ 130°F	119.1	104.7	102.8	115.5	99.0	104.6	97.2	92.4	87.0	98.9	92.1	89.9	94.4	
VISCOSITY SUS @ 210°F	47.4	45.3	45.6	51.7	49.4	52.2	50.4	49.9	51.4	55.5	50.5	52.4	50.7	
RAMSBOTTOM CARBON wt%	1.45	1.59	1.67	1.83	1.74	2.02	1.84	1.92	1.89	2.38	1.94	2.18	2.32	
WATER CONTENT vol%	0.17	0.38	0.32	0.17	0.34	1.00	0.91	0.23	3.43	5.15	1.93	3.56	2.48	
SOLIDS BOTTOM SED. wt%	0.41	0.32	0.31	0.27	0.13	1.26	0.37	0.17	0.38	0.07	0.83	0.54	0.50	
CARBON wt%	84.80	84.99	84.76	84.66	84.27	85.03	84.89	84.80	83.79	83.80	84.60	84.77	84.84	
HYDROGEN wt%	11.25	11.50	11.47	11.32	11.53	11.43	11.10	11.61	11.52	11.52	11.52	11.53	11.54	
NITROGEN wt%	2.32	2.07	1.89	2.00	1.70	1.98	2.09	2.48	1.95	1.71	1.94	2.12	1.95	
PRODUCT GAS PROPERTIES:														
MOISTURE vol%			→20 *			33.60	25.22	25.42	23.16	20.28	22.34	20.79	18.53	
ANALYSIS (DRY BASIS)														
H ₂ vol%	5.95	5.40	5.56	5.41	5.19	1.19	0.71	0.83	4.47	4.16	4.87	4.75	4.65	
N ₂ vol%	64.79	66.58	63.43	65.92	62.33	65.96	65.96	65.43	62.19	63.46	63.75	63.27	63.36	
O ₂ vol%	0.16	0.35	0.27	0.17	0.33	0.02	0.01	0.01	0	0.08	0	0	0	
CO vol%	1.75	1.79	2.13	1.93	2.69	2.39	1.99	2.68	2.12	1.98	2.31	2.42	2.52	
CH ₄ vol%	2.38	2.49	2.42	2.46	2.29	2.29	2.30	2.18	2.18	2.28	2.43	2.29	2.31	
CO ₂ vol%	21.23	20.53	23.43	21.18	24.70	26.28	26.28	26.17	25.83	24.69	23.46	24.29	24.38	
C ₂ H ₄ vol%	0.57	0.56	0.63	0.58	0.80	0.71	0.68	0.70	0.91	0.88	0.75	0.76	0.67	
C ₂ H ₆ vol%	1.00	0.69	0.62	0.70	0.47	0.57	0.56	0.54	0.61	0.66	0.70	0.62	0.56	
C ₃ H ₈ vol%	1.11	0.79	0.70	0.79	0.58	0.74	0.72	0.68	0.75	0.90	0.90	0.78	0.75	
C ₄ H ₁₀ vol%	0.63	0.40	0.39	0.44	0.19	0.35	0.33	0.32	0.30	0.50	0.46	0.39	0.37	
C ₅ + ¹ s vol%			→0.43 *			0.51 *	0.45 *	0.46 *	0.44 *	0.43 *	0.37 *	0.43 *	0.42 *	
GROSS HEAT. VALUE BTU/SCF	152	131	129	133	119	118	111	111	127	135	132	130	126	
SPECIFIC GRAVITY	1.059	1.054	1.068	1.058	1.076	1.127	1.129	1.127	1.092	1.091	1.071	1.081	1.081	
RETORTED SHALE PROPERTIES:														
FISCHER ASSAY gal/ton	0.30	0.20	0.80	0.40	0.30	0.20	0.30	0	0.40	0.40	0.20	0.40	0.41	
FISCHER ASSAY OIL wt%	0.10	0.10	0.30	0.10	0.10	0.10	0.10	0	0.14	0.14	0.10	0.16	0.16	
FISCHER ASSAY WATER wt%	0.10	0.30	0.10	0.30	0.40	0.20	0.50	0.20	0.31	0.31	0.10	0.23	0.20	
FISCHER ASSAY gas + loss wt%	0.50	0.10	0.30	0.20	0.40	0.10	0.00	0.10	0.00	0.00	0.10	0.15	0.37	
MINERAL CO ₂ wt%	16.86	17.12	16.49	17.46	15.12	16.12	15.48	14.63	15.35	15.14	15.89	14.74	15.58	
ORGANIC CARBON wt%	2.02	2.17	2.51	2.32	2.18	1.67	1.70	1.61	2.00	2.06	1.98	2.37	1.93	
IGNITION LOSS wt%	19.32	19.89	19.02	19.52	17.93	17.10	17.03	16.33	17.60	17.36	18.21	17.16	17.49	
CARBON wt%	6.62	6.84	7.01	7.08	6.30	6.07	5.92	5.60	6.19	6.19	6.31	6.39	6.18	
HYDROGEN wt%	0.16	0.18	0.18	0.21	0.18	0.14	0.13	0.15	0.15	0.15	0.18	0.18	0.16	
NITROGEN wt%	0.24	0.26	0.26	0.26	0.23	0.21	0.20	0.22	0.19	0.19	0.19	0.20	0.19	
MISCELLANEOUS:														
RETORT DROP in. H ₂ O/ft	1.64	1.62	1.76	2.37	1.52	1.00	0.91	1.09	1.30	1.31	0.96	1.05	1.05	
CARBONATE DECOMP. wt%	21	19	23	20	28	27	30	32	28	29	27	33	29	
BED HEIGHT ft	25.58	25.58	25.58	25.58	26	25.5	25.5	25.5	25.5	25.5	25.5	25.5	25.5	
* DESIGNATED VALUES SEE TABLE D-1														

TEST DATA FROM SEMI-WORKS — DIRECT HEATED

TABLE D-3 (CONT.)

GENERAL:	SW-20 A-3	SW-20 A-4	SW-20 A-5	SW-20 B	SW-20 B-2	SW-20 A-6	SW-20 A-7										
RUN NUMBER																	
TEST NUMBER																	
DATE	11-9-75	11-10-75	11-11-75	11-12-75	11-13-75	11-13-75	11-14-75										
START TIME	0800	0800	0800	2400	0800	2400	0800										
LENGTH OF TEST HRS.	24	24	24	8	8	8	24										
RATES AND QUANTITIES:																	
TOP DISTRIBUTOR GAS SCF/T	1342	1302	1334	1302	1195	1325	1334										
MID DISTRIBUTOR GAS SCF/T	1300	1249	1285	1770	1635	1276	1281										
BTM DISTRIBUTOR GAS SCF/T	11936	11556	11860	12462	11575	11779	11821										
TOTAL GAS	14578	14107	14479	15534	14405	14380	14436										
TOP DISTRIBUTOR AIR SCF/T	3745	3730	3867	3724	3488	3856	3717										
MID DISTRIBUTOR AIR SCF/T	833	831	864	1686	1593	1155	1112										
BTM DISTRIBUTOR AIR SCF/T	0	0	0	0	0	0	0										
TOTAL AIR SCF/T	4578	4561	4731	5410	5081	5014	4829										
SHALE THROUGHPUT lb/hr/ft ²	459	461	451	438	459	452	462										
TEMPERATURES:																	
PRODUCT OIL °F	140	139	142	154	145	130	144										
RETORTED SHALE OUT °F	402	377	382	378	381	387	385										
RAW SHALE IN °F	45	38	39	22	33	39	42										
RECYCLE GAS IN °F	235	233	248	254	257	256	257										
OFF-GAS °F	147	146	149	164	154	154	152										
AIR IN °F	187	189	183	180	195	185	195										
YIELDS:																	
OIL COLLECTED wt% F.A.	87.5	93.4	89.0	82.2	82.4	83.6	89.6										
PRODUCT GAS (WET) SCF/T	7082	6963	7194	8215	7519	7492	7666										
RETORTED SHALE wt% R.S.	82	82	81	81	80	81	81										
LIQUOR WATER lb/ton	8.59	9.56	9.01	11.92	3.56	5.99	6.49										
ASH BALANCE wt%	100	100	99	100	100	99	99										
ATM. N ₂ BALANCE wt%	103	107	103	94	114	101	103										
WATER BALANCE wt%	77	69	74	95	34	60	80										
KEROGEN BALANCE wt%	93	107	100	98	94	97	101										
ORG. CARBON BALANCE wt%	94	100	96	95	90	96	98										
TOT. H ₂ BALANCE wt%	99	99	98	111	95	99	109										
ORG. N ₂ BALANCE wt%	68	66	67	63	63	62	69										
MATERIAL RECOVERY wt%	100	102	100	100	98	99	101										
RAW SHALE PROPERTIES:																	
MOISTURE wt%	0.91	0.77	1.16	0.68	1.04	1.29	0.77										
FISCHER ASSAY gal/ton	27.6	26.8	27.8	28.1	28.0	28.9	28.8										
FISCHER ASSAY OIL wt%	10.53	10.22	10.58	10.74	10.67	11.04	11.03										
FISCHER ASSAY WATER wt%	1.53	1.58	1.70	1.78	1.72	1.58	1.60										
FISCHER ASSAY gas + loss wt%	2.18	2.18	2.25	1.68	1.92	2.06	2.20										
MINERAL CO ₂ wt%	17.72	18.00	17.65	17.58	17.95	17.41	17.40										
IGNITION LOSS wt%	33.26	32.68	32.95	33.12	33.20	33.30	33.54										
CARBON wt%	17.12	16.86	17.20	16.91	16.91	17.03	17.41										
HYDROGEN wt%	1.92	1.89	1.94	1.81	1.81	1.84	1.86										
NITROGEN wt%	0.50	0.53	0.49	0.50	0.50	0.50	0.52										
NOMINAL PART. SIZE in.	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4	1/2-3/4										
COLLECTED OIL PROPERTIES:																	
GRAVITY DEGREE API	21.4	21.3	21.3	21.1	21.1	21.1	21.4										
VISCOSITY SUS @ 150°F	89.6	90.3	91.2	94.9	93.1	92.2	91.2										
VISCOSITY SUS @ 210°F	50.3	52.1	51.3	47.4	55.5	52.5	48.7										
RAMSBOTTOM CARBON wt%	2.23	2.35	2.01	2.18	2.24	1.99	2.07										
WATER CONTENT vol%	4.07	4.93	4.22	5.85	1.83	3.89	2.93										
SOLIDS BOTTOM SED. wt%	0.53	0.35	0.41	0.47	0.19	0.32	0.63										
CARBON wt%	84.82	84.84	85.27	84.55	84.48	83.99	84.26										
HYDROGEN wt%	11.51	11.55	11.54	11.40	11.40	11.33	11.40										
NITROGEN wt%	2.21	2.06	2.09	2.05	2.05	1.95	2.08										
PRODUCT GAS PROPERTIES:																	
MOISTURE vol%	17.60	16.41	18.97	21.49	12.60	14.50	19.17										
ANALYSIS (DRY BASIS)																	
H ₂ vol%	4.65	1.23	1.48	4.68	2.20	4.67	4.97										
N ₂ vol%	63.85	66.28	65.95	62.27	69.63	62.41	63.32										
O ₂ vol%	0	0	0	0	0.15	0	0										
CO vol%	2.48	2.49	2.54	2.78	2.89	2.74	2.62										
CH ₄ vol%	2.25	2.34	2.38	2.19	2.39	2.24	2.32										
CO ₂ vol%	24.09	24.73	24.86	25.56	20.13	25.36	23.98										
C ₂ H ₄ vol%	0.63	0.67	0.62	0.67	0.67	0.67	0.70										
C ₂ H ₆ vol%	0.56	0.62	0.62	0.51	0.55	0.53	0.58										
C ₃ H ₈ vol%	0.73	0.84	0.76	0.64	0.70	0.68	0.72										
C ₄ H ₁₀ vol%	0.35	0.39	0.38	0.27	0.31	0.32	0.37										
C ₅ H ₁₂ vol%	0.41	0.41	0.42	0.43	0.39	0.40	0.42										
GROSS HEAT. VALUE BTU/SCF	123	117	116	119	114	120	127										
SPECIFIC GRAVITY	1.080	1.115	1.113	1.087	1.078	1.085	1.076										
RETORTED SHALE PROPERTIES:																	
FISCHER ASSAY gal/ton	0.22	0.32	0.12	0.82	0.26	0.10	0.22										
FISCHER ASSAY OIL wt%	0.09	0.12	0.04	0.31	0.10	0.05	0.08										
FISCHER ASSAY WATER wt%	0.10	0.14	0.12	0.10	0.05	0.23	0.07										
FISCHER ASSAY gas + loss wt%	0.42	0.15	0.26	0	0.16	0.27	0.09										
MINERAL CO ₂	16.29	15.75	15.98	14.76	14.36	15.17	15.17										
ORGANIC CARBON wt%	1.71	1.86	1.80	1.99	1.98	1.86	2.07										
IGNITION LOSS wt%	17.49	17.73	17.50	16.50	15.97	17.00	17.43										
CARBON wt%	6.15	6.15	6.16	6.01	5.90	6.00	6.21										
HYDROGEN wt%	0.16	0.16	0.15	0.15	0.15	0.14	0.15										
NITROGEN wt%	0.17	0.19	0.16	0.17	0.17	0.16	0.19										
MISCELLANEOUS:																	
RETORT DROP in. H ₂ O/ft	1.04	1.02	0.99	1.03	1.04	0.98	0.99										
CARBONATE DECOMP. wt%	25	28	26	32	36	30	30										
BED HEIGHT ft	25.5	25.5	25.5	25.5	25.5	25.5	25.5										

* DESIGNATED VALUE SEE TABLE D-1

SECTION 101

SECTION 101

MESLON BOND

TABLE D-3 (CONT.)

* DESIGNATED VALUES SEE TABLE D-1

TABLE D-4

General:		SW-21	SW-22	SW-22	SW-23	SW-23	SW-23	SW-23	SW-23	SW-23	SW-23	SW-23	SW-23	SW-23	SW-23
Run Number		A	A-1	A-2	A-1	A-2	A-3	A-4	A-5	A-6	A-7	B-1	B-2	A-8	
Test Number															
Date		12-13-75	12-19-75	12-20-75	1-16-76	1-17-76	1-18-76	1-19-76	1-20-76	1-21-76	1-22-76	1-23-76	1-24-76	1-25-76	
Start Time		0000	2400	0800	0800	0800	0800	0800	0800	2400	1600	1600	0800	1600	
Length of Test	Hrs	24	8	24	24	24	24	24	24	8	16	12	16		
Rates and Quantities:															
Top Distributor Gas	SCF/T	12350	16523	15804	18540	18251	19046	18763	18721	18252	16791	17576	17722	19541	
Mid Distributor Gas	SCF/T	0	0	0	0	0	0	0	0	0	0	0	0	0	
Btm Distributor Gas	SCF/T	3300	4271	3750	5037	4886	5119	5043	4962	4809	8395	6818	6811	5217	
Total Gas	SCF/T	15650	20794	19554	23577	23127	24165	23806	23683	23061	25186	24394	24555	24778	
Shale Throughput	lb/hr/ft ²	438	348	364	344	339	324	329	324	329	316	322	324	310	
Hot Gas Above 77°F	MBTU/T	488	549	478	588	532	611	595	584	566	541	578	564	629	
Temperatures:															
Product Oil	°F	158	171	176	175	175	175	172	174	170	170	140	160	150	
Retorted Shale Out	°F	550	NA	NA	545	550	555	559	528	561	439	475	490	499	
Raw Shale In	°F	30	25	25	26	36	35	40	40	40	60	60	50	50	
Product Gas	°F	241	213	222	222	224	224	219	216	216	211	214	205	235	
Off Gas	°F	225	277	294	305	292	297	302	299	295	301	305	293	286	
Top Heater Out	°F	1110	1110	1080	1190	1190	1190	1190	1180	1190	1190	1200	1200	1200	
Top Distributor In	°F	1080	1084	1040	1142	1148	1148	1151	1143	1148	1136	1146	1141	1133	
Btm Distributor In	°F	241	213	222	222	224	224	219	216	216	211	214	205	235	
Yields:															
Oil Collected	wt%	71.0	86.5	78.9	91.7	90.8	81.7	79.1	91.2	91.1	106.8	88.4	90.9	92.4	
Total Oil C ₉ wt% F.A.		72.3	88.7	80.1	98.1	83.6	84.8	81.8	93.3	92.6	109.6	91.7	94.0	95.5	
Product Gas (wet)	SCF/T	884	1140	1130	1440	1260	1690	1720	1370	1380	1560	1650	1690	1660	
Retorted Shale wt% R.S.		86	87	89	84	86	85	85	85	84	86	86	86	86	
Liquid Water	lb/ton	4.95	45.4	14.0	42.6	33.9	29.7	45.1	25.3	21.2	4.4	23.7	7.8	22.8	
Ash Balance	wt%	99	100	100	101	101	100	100	100	99	100	100	100	100	
Water Balance	wt%	39	147	73	157	145	105	133	108	89	55	86	76	95	
Kerogen Balance	wt%	87	94	107	78	89	95	95	96	88	109	106	101	101	
Org. Carbon Balance	wt%	87	90	102	88	85	88	86	93	88	105	95	96	97	
Org. H ₂ Balance	wt%	95	102	111	104	94	99	96	99	100	122	105	104	108	
Org. N ₂ Balance	wt%	84	74	90	97	95	92	93	93	102	101	102	103	101	
Material Recovery	wt%	96	100	100	99	100	100	100	100	98	100	101	100	100	
Raw Shale Properties:															
Moisture	wt%	1.12	1.03	1.02	1.12	0.94	1.17	1.13	1.03	1.15	1.43	1.38	1.25	1.40	
Fischer Assay	gal/ton	30.1	26.9	28.8	27.4	28.3	27.3	28.3	28.6	27.	27.5	27.9	27.9	27.1	
Fischer Assay Oil	wt%	11.51	10.28	10.97	10.46	10.81	10.67	10.79	10.90	10.32	10.50	10.63	10.66	10.33	
Fischer Assay Water	wt%	1.55	1.38	1.39	1.82	1.42	1.81	1.94	1.69	1.92	2.17	1.81	1.64	1.91	
Fischer Assay, gas/loss	wt%	2.15	1.88	1.98	1.53	1.94	1.78	1.84	1.18	1.97	1.85	1.99	2.08	2.37	
Mineral CO ₂	wt%	17.25	17.60	17.58	18.26	18.1	17.23	17.05	17.51	17.74	16.48	17.16	17.30	17.42	
Ignition Loss	wt%	34.20	33.25	33.78	33.01	32.95	32.88	33.38	33.27	32.89	33.54	33.05	33.02	33.62	
Carbon	wt%	17.98	17.66	17.64	16.85	17.17	16.96	17.45	17.27	16.80	17.08	17.30	17.08	17.05	
Hydrogen	wt%	1.91	1.79	1.82	1.73	1.81	1.78	1.84	1.82	1.76	1.75	1.80	1.73	1.78	
Nitrogen	wt%	0.55	0.57	0.56	0.45	0.48	0.49	0.5	0.51	0.45	0.51	0.49	0.48	0.50	
Nominal Part Size	in.	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	
Collected Oil Properties:															
Gravity Degree	API	23.5	23.0	21.1	20.3	20.2	19.8	19.9	20.3	21.0	20.1	19.7	20.1	20.4	
Viscosity SUS @ 130°F		62.0	105.1	92.8	105.9	106.0	112.8	94.9	111.9	112.4	112.9	106.6	115.4	102.4	
Viscosity SUS @ 210°F		42.5	46.7	47.4	50.4	52.1	53.0	49.1	53.1	53.0	53.4	51.7	56.5	50.5	
Kerosbottom Carbon	wt%	1.40	1.25	1.27	1.77	1.81	2.00	2.24	2.26	2.44	2.41	2.42	2.59	1.71	
Water Content	vol%	2.67	13.0	6.15	15.53	14.55	12.89	18.58	9.56	8.15	0.18	10.28	3.57	9.27	
Solids Bottom Sed.	wt%	0.25	0.91	0.94	1.62	1.72	1.47	3.04	2.14	1.31	0.13	2.01	2.36	0.85	
Carbon	wt%	84.66	84.82	84.22	83	84.47	84.68	84.39	84.51	84.56	84.35	84.23	83.87	84.65	
Hydrogen	wt%	11.56	11.66	11.47	11.38	11.45	11.48	11.48	11.50	11.47	11.49	11.28	11.33	11.36	
Nitrogen	wt%	1.74	1.66	1.76	1.98	2.04	2.01	1.97	1.95	1.97	1.98	1.89	1.84	1.88	
Product Gas Properties:															
Moisture	vol%	30.63	23.50	28.50	31.34	29.85	27.30	25.80	32.00	32.00	31.10	26.50	32.00	30.00	
Analysis (dry basis)															
H ₂	vol%	25.00	24.48	24.61	25.54	26.73	27.16	26.87	26.10	26.23	27.47	26.68	26.68	26.18	
N ₂	vol%	2.04	6.96	9.78	1.69	1.66	1.17	1.11	10.33	0.80	0.75	0.79	0.68	0.96	
O ₂	vol%	0	0.01	0.01	0.01	0.01	0	0.05	0	0.01	0	0	0	0	
CO	vol%	2.15	2.72	2.58	4.63	4.13	3.91	4.09	3.75	4.24	3.24	3.81	3.88	4.14	
CH ₄	vol%	25.54	21.47	19.37	19.26	19.15	18.72	18.30	19.08	19.13	20.72	20.20	19.67	19.92	
CO ₂	vol%	13.78	16.22	15.91	28.69	28.63	29.68	30.68	29.62	28.98	25.49	27.63	27.81	27.34	
C ₂ H ₆	vol%	8.93	4.13	3.76	4.33	4.38	4.02	3.90	4.64	4.36	4.84	4.76	4.73	4.61	
C ₃ H ₈	vol%	7.96	7.66	6.72	5.32	5.09	5.07	4.93	5.03	5.16	5.71	5.25	5.29	5.46	
C ₄	vol%	7.45	7.25	6.52	4.08	3.88	3.90	3.81	4.02	4.02	4.56	4.00	4.16	4.24	
C ₄ 's	vol%	3.00	4.13	3.76	1.60	1.50	1.57	1.44	1.51	1.61	1.81	1.44	1.70	1.73	
H ₂ S	vol%	4.16	5.18	6.98	1.95	1.94	1.93	1.92	1.97	1.71	1.69	1.70	1.68	1.70	
NH ₃	vol%	N/A	N/A	N/A	2.90	2.91	2.87	2.87	2.94	3.75	3.72	3.73	3.72	3.73	
Gross Heat Value	BTU/SCF	951	862	803	846	823	827	812	837	842	697	655	663	669	
Specific Gravity		0.808	0.857	0.857	0.859	0.846	0.851	0.864	0.858	0.851	0.820	0.833	0.840	0.842	
Retorted Shale Properties:															
Fischer Assay	gal/ton	3.2	1.0	5.3	0.25	0.30	0.40	0.40	0.30	0.30	0.20	0.40	0.30	0.50	
Fischer Assay Oil	wt%	1.24	0.37	2.01	0.08	0.11	0.15	0.14	0.12	0.11	0.09	0.13	0.11	0.19	
Fischer Assay Water	wt%	0.41	0.36	0.51	0.40	0.32	0.30	0.28	0.28	0.28	0.41	0.36	0.34	0.34	
Fischer Assay, gas/loss	wt%	0.22	0.38	0.53	0.02	0.33	0.10	0.09	0.17	0.14	0.14	0.10	0.14	0.20	
Mineral CO ₂	wt%	18.54	19.30	18.87	15.42	18.39	18.58	19.01	18.54	18.11	18.51	18.39	19.02	18.99	
Organic Carbon	wt%	4.35	3.14	5.34	2.75	2.43	2.36	2.62	2.74	2.38	2.69	2.94	2.69	2.76	
Ignition Loss	wt%	23.90	22.46	25.23	28.4	20.83	20.84	21.25	21.28	20.29	21.32	21.79	21.31	21.77	
Carbon	wt%	9.41	8.41	10.49	6.96	7.45	7.43	7.80	7.80	7.32	7.74	8.01	7.88	7.94	
Hydrogen	wt%	0.47	0.32	0.60	0.19	0.22	0.20	0.21	0.21	0.20	0.20	0.22	0.21	0.24	
Nitrogen	wt%	0.37	0.32	0.40	0.23	0.26	0.25	0.27	0.27	0.25	0.26	0.28	0.28	0.29	
Miscellaneous:															
Retort Drop	in. H ₂ O/ft	0.50	0.46	0.38	0.56	0.57	0.6	0.57	0.57	0.60	0.79	0.58	0.63	0.53	
Carbonate Decomp.	wt%	8	6	5	30	14	9	6	10	15	5	7	6	7	
Red Height	ft	24	24	24	24	24	24	24	24	24	24	24	24	24	

TEST DATA FROM DEPT. OF AGRICULTURE

1917-18

Year	1917	1918	1919	1920	1921	1922	1923	1924	1925	1926	1927	1928	1929	1930	1931	1932	1933	1934	1935	1936	1937	1938	1939	1940	1941	1942	1943	1944	1945	1946	1947	1948	1949	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2423	2424	2425	2426	2427	2428	2429	2430	2431	2432	2433	2434	2435	2436	2437	2438	2439	2440	2441	2442	2443	2444	2445	2446	2447	2448	2449	2450	2451	2452	2453	2454	2455	2456	2457	2458	2459	2460	2461	2462	2463	2464	2465	2466	2467	2468	2469	2470	2471	2472	2473	2474	2475	2476	2477	2478	2479	2480	2481	2482	2483	2484	2485	2486	2487	2488	2489	2490	2491	2492	2493	2494	2495	2496	2497	2498	2499	2500	2501	2502	2503	2504	2505	2506	2507	2508	2509	2510	2511	2512	2513	2514	2515	2516	2517	2518	2519	2520	2521	2522	2523	2524	2525	2526	2527	2528	2529	2530	2531	2532	2533	2534	2535	2536	2537	2538	2539	2540	2541	2542	2543	2544	2545	2546	2547	2548	2549	2550	2551	2552	2553	2554	2555	2556	2557	2558	2559	2560	2561	2562	2563	2564	2565	2566	2567	2568	2569	2570	2571	2572	2573	2574	2575	2576	2577	2578	2579	2580	2581	2582	2583	2584	2585	2586	2587	2588	2589	2590	2591	2592	2593	2594	2595	2596	2597	2598	2599	2600	2601	2602	2603	2604	2605	2606	2607	2608	2609	2610	2611	2612	2613	2614	2615	2616	2617	2618	2619	2620	2621	2622	2623	2624	2625	2626	2627	2628	2629	2630	2631	2632	2633	2634	2635	2636	2637	2638	2639	2640	2641	2642	2643	2644	2645	2646	2647	2648	2649	2650	2651	2652	2653	2654	2655	2656	2657	2658	2659	2660	2661	2662	2663	2664	2665	2666	2667	2668	2669	2670	2671	2672	2673	2674	2675	2676	2677	2678	2679	2680	2681	2682	2683	2684	2685	2686	2687	2688	2689	2690	2691	2692	2693	2694	2695	2696	2697	2698	2699	2700	2701	2702	2703	2704	2705	2706	2707	2708	2709	2710	2711	2712	2713	2714	2715	2716	2717	2718	2719	2720	2721	2722	2723	2724	2725	2726	2727	2728	2729	2730	2731	2732	2733	2734	2735	2736	2737	2738	2739	2740	2741	2742	2743	2744	2745	2746	2747	2748	2749	2750	2751	2752	2753	2754	2755	2756	2757	2758	2759	2760	2761	2762	2763	2764	2765	2766	2767	2768	2769	2770	2771	2772	2773	2774	2775	2776	2777	2778	2779	2780	2781	2782	2783	2784	2785	2786	2787	2788	2789	2790	2791	2792	2793	2794	2795	2796	2797	2798	2799	2800	2801	2802	2803	2804	2805	2806	2807	2808	2809	2810	2811	2812	2813	2814	2815	2816	2817	2818	2819	2820	2821	2822	2823	2824	2825	2826	2827	2828	2829	2830	2831	2832	2833	2834	2835	2836	2837	2838	2839	2840	2841	2842	2843	2844	2845	2846	2847	2848	2849	2850	2851	2852	2853	2854	2855	2856	2857	2858	2859	2860	2861	2862	2863	2864	2865	2866	2867	2868	2869	2870	2871	2872	2873	2874	2875	2876	2877	2878	2879	2880	2881	2882	2883	2884	2885	2886	2887	2888	2889	2890	2891	2892	2893	2894	2895	2896	2897	2898	2899	2900	2901	2902	2903	2904	2905	2906	2907	2908	2909	2910	2911	2912	2913	2914	2915	2916	2917	2918	2919	2920	2921	2922	2923	2924	2925	2926	2927	2928	2929	2930	2931	2932	2933	2934	2935	2936	2937	2938	2939	2940	2941	2942	2943	2944	2945	2946	2947	2948	2949	2950	2951	2952	2953	2954	2955	2956	2957	2958	2959	2960	2961	2962	2963	2964	2965	2966	2967	2968	2969	2970	2971	2972	2973	2974	2975	2976	2977	2978	2979	2980	2981	2982	2983	2984	2985	2986	2987	2988	2989	2990	2991	2992	2993	2994	2995	2996	2997	2998	2999	3000	3001	3002	3003	3004	3005	3006	3007	3008	3009	3010	3011	3012	3013	3014	3015	3016	3017	3018	3019	3020	3021	3022	3023	3024	3025	3026	3027	3028	3029	3030	3031	3032	3033	3034	3035	3036	3037	3038	3039	3040	3041	3042	3043	3044	3045	3046	3047	3048	3049	3050	3051	3052	3053	3054	3055	3056	3057	3058	3059	3060	3061	3062	3063	3064	3065	3066	3067	3068	3069	3070	3071	3072	3073	3074	3075	3076	3077	3078	3079	3080	3081	3082	3083	3084	3085	3086	3087	3088	3089	3090	3091	3092	3093	3094	3095	3096	3097	3098	3099	3100	3101	3102	3103	3104	3105	3106	3107	3108	3109	3110	3111	3112	3113	3114	3115	3116	3117	3118	3119	3120	3121	3122	3123	3124	3125	3126	3127	3128	3129	3130	3131	3132	3133	3134	3135	3136	3137	3138	3139	3140	3141	3142	3143	3144	3145	3146	3147	3148	3149	3150	3151	3152	3153	3154	3155	3156	3157	3158	3159	3160	3161	3162	3163	3164	3165	3166	3167	3168	3169	3170	3171	3172	3173	3174	3175	3176	3177	3178	3179	3180	3181	3182	3183	3184	3185	3186	3187	3188	3189	3190	3191	3192	3193	3194	3195	3196	3197	3198	3199	3200	3201	3202	3203	3204	3205	3206	3207	3208	3209	3210	3211	3212	3213	3214	3215	3216	3217	3218	3219	3220	3221	3222	3223	3224	3225	3226	3227	3228	3229	3230	3231	3232	3233	3234	3235	3236	3237	3238	3239	3240	3241	3242	3243	3244	3245	3246	3247	3248	3249	3250	3251	3252	3253	3254	3255	3256	3257	3258	3259	3260	3261	3262	3263	3264	3265	3266	3267	3268	3269	3270	3271	3272	3273	3274	3275	3276	3277	327
------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	-----

TABLE D-4 (CONT.)

TABLE D-4 (CONT.)							
General:		SW-23	SW-23	SW-22	SW-23	SW-23	SW-23
Run Number		B-5	C-1	C-2.1	C-2.2	C-2.3	C-5
Test Number							
Date		2-1-76	2-2-76	2-3-76	2-4-76	2-5-76	2-7-76
Start Time		1600	1600	2400	0800	1600	1600
Length of Test Hrs		24	16	8	24	15	16
Rates and Quantities:							
Top Distributor Gas SCF/T		14913	14065	12783	12115	12544	11751
Mid Distributor Gas SCF/T		0	0	0	0	0	0
Btm Distributor Gas SCF/T		7671	7870	8671	8332	8558	8433
Total Gas SCF/T		22584	21935	21454	20447	21102	20184
Shale Throughput lb/hr/ft ²		408	436	492	509	501	529
Hot Gas Above 77°F MBU/T		508	496	465	429	466	442
Temperatures:							
Product Oil °F		187	150	195	160	189	182
Retorted Shale Out °F		452	450	398	411	396	414
Raw Shale In °F		40	40	50	40	50	40
Product Gas °F		221	220	200	209	205	215
Off Gas °F		339	332	326	303	322	308
Top Heater Out °F		1200	1230	1260	1200	1242	1250
Top Distributor In °F		1151	1183	1206	1153	1198	1206
Btm Distributor In °F		150	150	150	150	150	152
Yields:							
Oil Collected wt%		81.8	86.0	88.0	87.3	93.5	85.8
Total Oil C ₅ +wt% F.A.		84.1	88.0	89.6	88.9	95.3	88.3
Product Gas (wet) SCF/T		1081	1070	890	940	950	1175
Retorted Shale wt% R.S		86	86	85	86	88	87
Liquid Water lb/ton		34.4	28.9	32.4	27.8	37.8	32.2
Ash Balance wt%		100	100	99	100	100	101
Water Balance wt%		137	91	106	118	124	101
Kerogen Balance wt%		89	92	82	94	101	103
Org. Carbon Balance wt%		86	90	83	90	93	97
Org. H ₂ Balance wt%		93	96	92	96	102	107
Org. N ₂ Balance wt%		93	88	92	92	97	100
Material Recovery wt%		99	99	98	100	101	101
Raw Shale Properties:							
Moisture wt%		0.90	1.05	0.94	0.78	0.84	1.19
Fischer Assay gal/ton		29.8	28.6	27.5	28.7	26.1	29.65
Fischer Assay Oil wt%		11.36	10.93	10.48	10.97	9.94	11.33
Fischer Assay Water wt%		1.39	1.59	1.81	1.68	1.88	1.67
Fischer Assay gas loss wt%		1.90	2.07	2.10	2.22	1.78	2.27
Mineral CO ₂ wt%		16.39	17.13	18.41	17.62	17.65	16.95
Ignition Loss wt%		33.85	33.41	33.06	33.77	33.25	33.75
Carbon wt%		17.82	17.41	17.35	17.75	17.44	17.64
Hydrogen wt%		1.87	1.84	1.82	1.87	1.83	1.85
Nitrogen wt%		0.50	0.49	0.48	0.49	0.48	0.51
Nominal Part. Size wt%		½ x 2	½ x 2	½ x 2	½ x 2	½ x 2	½ x 2
Collected Oil Properties:							
Gravity Degree API		19.8	19.9	19.0*	20.2	21.0	20.5
Viscosity SUS @ 130°F		111.0	117.4	105.0	88.5	85.4	89.5
Viscosity SUS @ 210°F		53.9	51.1	58.0	51.4	49.1	48.9
Rambottom Carbon wt%		2.16	1.98	2.21	1.61	1.52	1.34
Water Content vol%		7.10	4.65	2.16	4.16	2.77	1.75
Solids Bottom Sed. wt%		3.35	3.40	2.30	2.61	1.27	0.95
Carbon wt%		84.65	84.99	84.58	84.88	85.15	85.17
Hydrogen wt%		11.34	11.41	11.31	11.42	11.42	11.44
Nitrogen wt%		2.02	1.88	2.00	1.92	1.99	1.98
Product Gas Properties:							
Moisture vol%		29.10	27.00	29.30	28.10	29.90	29.40
Analysis (dry basis)							
H ₂ vol%		27.91	27.33	25.14	27.06	25.53	25.58
N ₂ vol%		0.80	0.57	1.34	0.91	0.55	0.61
O ₂ vol%		0	0	0	0	0	0
CO vol%		3.26	3.21	3.24	2.94	2.44	2.78
CH ₄ vol%		23.80	24.51	26.19	25.40	25.92	26.60
C ₂ H ₆ vol%		20.92	20.32	18.96	16.96	16.73	17.11
C ₃ H ₈ vol%		5.95	7.00	7.99	7.45	9.58	9.24
C ₄ 's vol%		6.62	6.61	6.67	7.16	7.34	7.11
C ₅ 's vol%		5.38	5.25	5.13	6.18	6.27	5.69
C ₆ 's vol%		2.12	1.94	1.82	2.65	2.34	2.00
H ₂ S vol%		2.30	2.32	2.32	2.33	2.33	2.33
NH ₃ vol%		0.94	0.96	1.21	0.96	0.96	0.96
Gross Heat. Value BTU/SCF		786	799	819	870	898	870
Specific Gravity		0.798	0.795	0.797	0.788	0.796	0.787
Retorted Shale Properties:							
Fischer Assay gal/ton		0.27	0.30	0.30	0.20	0.60	0.40
Fischer Assay Oil wt%		0.10	0.12	0.12	0.09	0.25	0.17
Fischer Assay Water wt%		0.50	0.27	0.63	0.74	0.63	0.69
Fischer Assay gas loss wt%		0	0.05	0.14	0.22	0.49	0.27
Mineral CO ₂ wt%		18.94	19.67	19.07	19.25	19.82	20.03
Organic Carbon wt%		2.84	2.55	2.38	2.99	3.14	3.16
Ignition Loss wt%		22.22	22.02	21.07	22.72	23.19	23.20
Carbon wt%		8.01	7.91	7.58	8.24	8.55	8.62
Hydrogen wt%		0.27	0.25	0.23	0.27	0.34	0.34
Nitrogen wt%		0.31	0.28	0.29	0.30	0.31	0.35
Miscellaneous:							
Retort Drop in. H ₂ O/ft		0.99	1.08	1.24	1.21	1.42	1.27
Carbonate Decomp. wt%		2	2	13	6	2	2
Bed Height ft		24	24	24	24	24	24

TEST DATA FROM SEMI-WORKS — INDIRECT HEATED

TABLE D-4 (CONT.)

GENERAL: RUN NUMBER TEST NUMBER	SW-28 C-1	SW-28 C-2	SW-28 STEP3	SW-28 A-3	SW-28 A-4	SW-28 A-4.1	SW-28 A-4.2	SW-28 A-4.3	SW-28 A-4.4	SW-31 B	SW-31 D				
DATE	3/14/76	3/15/76	3/16/76	3/17/76	3/18/76	3/19/76	3/20/76	3/21/76	3/22/76	4/3/76	4/4/76				
START TIME	0800	0800	1600	1200	1600	2000	0800	0800	0800	2000	1800				
LENGTH OF TEST	hrs. 24	22	14	24	16	12	24	24	8	12	14				
RATES AND QUANTITIES:															
TOP DISTRIBUTOR GAS SCF/T	12181	11467	8693	8463	9524	11058	10270	9659	9541	10887	10187				
MID DISTRIBUTOR GAS SCF/T	0	0	0	0	2076	0	0	0	0	0	0				
BTM DISTRIBUTOR GAS SCF/T	8011	7700	9973	11051	8923	12572	11647	10998	10850	8766	9807				
TOTAL GAS SCF/T	20192	19167	18666	19514	20503	23630	21917	20657	20301	19653	19994				
SHALE THROUGHPUT lb/hr/ft ²	433	461	480	465	458	401	421	448	460	464	456				
HOT GAS ABOVE 77°F MBTU/T	451	429	326	318	358	415	393	369	359	405	382				
TEMPERATURES:															
PRODUCT OIL °F	147	170	153	150	175	149	147	147	152	158	158				
RETORTED SHALE OUT °F	355	380	337	295	336	308	312	349	361	362	336				
RAW SHALE IN °F	40	40	41	41	52	40	40	40	40	50	50				
PRODUCT GAS °F	217	217	228	220	209	212	214	215	217	221	219				
OFF-GAS °F	311	302	256	250	294	333	322	294	325	277	281				
TOP HEATER OUT °F	1264	1245	1341	1370	1380	1378	1380	1388	1380	1300	1370				
TOP DISTRIBUTOR IN °F	1197	1197	1268	1280	1300	1298	1298	1301	1301	1222	1285				
BTM DISTRIBUTOR IN °F	150	150	150	150	150	150	150	150	150	152	151				
YIELDS:															
OIL COLLECTED wt%	89.3	87.0	59.9	58.9	83.9	94.2	93.2	78.2	68.3	77.2	78.1				
TOTAL OIL C ₂ + wt% A ₁	91.3	88.4	60.4	60.1	85.4	94.9	94.0	79.7	69.5	80.2	79.3				
PRODUCT GAS (WET) SCF/T	1072	887	203	586	751	566	516	616	610	1344	567				
RETORTED SHALE wt% S ₂	87	87	88	89	91	90	89	88	89	88	89				
LIQUID WATER lb/ton	43.5	22.5	23.4	18.3	18.5	29.2	30.2	30.0	17.6	20.2	20.6				
ASH BALANCE wt%	100	100	100	100	100	100	100	100	100	100	100				
WATER BALANCE wt%	93	61	59	56	57	74	81	97	67	117	75				
KEROGEN BALANCE wt%	106	96	72	84	108	111	104	89	94	100	90				
ORG. CARBON BALANCE wt%	96	90	74	82	96	103	96	84	89	97	87				
ORG. H ₂ BALANCE wt%	105	96	83	91	106	103	99	87	93	107	92				
ORG. N ₂ BALANCE wt%	103	88	87	109	98	112	111	98	98	89	91				
MATERIAL RECOVERY wt%	101	99	95	97	100	101	100	98	99	100	98				
RAW SHALE PROPERTIES:															
MOISTURE wt%	1.35	1.24	1.05	1.24	1.09	1.05	1.32	1.25	1.19	0.89	0.87				
FISCHER ASSAY gal/ton	27.9	28.7	27.1	27.2	25.3	25.7	26.6	27.3	28.2	26.7	27.0				
FISCHER ASSAY OIL wt%	10.63	10.75	10.36	10.39	9.65	9.78	10.14	10.44	11.28	10.14	10.29				
FISCHER ASSAY WATER wt%	2.02	1.83	1.88	1.44	1.78	1.96	1.54	1.33	1.26	1.24	1.46				
FISCHER ASSAY GAS+LOSS wt%	2.04	2.10	1.86	2.14	1.90	1.96	2.07	2.13	1.84	1.96	1.87				
MINERAL CO ₂ wt%	17.81	17.29	17.89	18.15	17.92	17.93	17.59	17.44	17.54	17.31	17.67				
IGNITION LOSS wt%	33.81	34.61	34.74	34.02	33.11	31.76	32.15	33.12	33.65	31.92	32.53				
CARBON wt%	17.66	18.26	18.26	17.89	16.60	15.68	16.40	17.64	18.31	16.42	16.68				
HYDROGEN wt%	1.87	1.97	1.89	1.91	1.72	1.70	1.70	1.85	1.93	1.72	1.74				
NITROGEN wt%	0.50	0.58	0.56	0.51	0.48	0.45	0.45	0.48	0.53	0.56	0.54				
NOMINAL PART. SIZE in. +4"X2"	++"X2"	++"X2"	++"X2"	++"X2"	++"X2"	++"X2"	++"X2"	++"X2"	++"X2"	++"X2"	++"X2"				
COLLECTED OIL PROPERTIES:															
GRAVITY DEGREE API	21.7	22.0	21.9	21.8	21.8	20.6	20.0	21.2	20.9	22.0	21.7				
VISCOSITY SUS @ 130°F	68.4	66.8	63.4	63.5	64.6	82.9	86.1	72.2	71.5	67.0	68.2				
VISCOSITY SUS @ 210°F	42.2	41.6	41.4	42.5	41.8	45.0	46.1	44.1	44.7	41.9	42.1				
RAMSBOTTOM CARBON wt%	1.33	1.28	1.16	0.95	1.11	1.60	2.10	1.34	1.74	1.11	1.41				
WATER CONTENT vol%	1.42	1.92	8.74	1.52	4.76	1.34	0.93	1.06	0.74	0.97	0.39				
SOLIDS BOTTOM SED. wt%	0.65	0.54	1.49	0.75	0.83	1.27	1.70	1.43	0.94	0.18	0.09				
CARBON wt%	84.70	84.67	84.67	84.61	84.65	85.00	84.84	84.82	84.69	83.62	84.12				
HYDROGEN wt%	11.51	11.47	11.44	11.46	11.59	11.45	11.44	11.48	11.53	11.63	11.66				
NITROGEN wt%	2.13	2.08	2.06	1.95	1.91	2.07	2.01	1.90	2.08	1.99	2.13				
PRODUCT GAS PROPERTIES:															
MOISTURE vol%	21.98	19.01	35.28	31.17	34.05	28.85	28.80	33.20	32.60	33.25	31.25				
ANALYSIS (DRY BASIS)															
H ₂ vol%	25.31	24.35	24.02	24.13	24.76	25.49	24.92	24.66	24.16	25.11	25.22				
N ₂ vol%	0.76	1.98	0.74	0.96	0.40	0.61	0.53	0.76	1.14	0.37	0.61				
O ₂ vol%	0.04	0.14	0.09	0.01	0	0	0	0	0	0	0				
CO vol%	2.40	2.45	2.34	2.67	2.97	2.76	2.72	2.62	2.60	2.69	3.17				
CH ₄ vol%	25.94	26.43	29.34	31.40	31.06	32.52	31.94	33.49	33.85	27.75	29.63				
CO ₂ vol%	16.36	15.48	16.14	15.22	14.76	15.46	15.13	13.88	13.79	17.46	19.12				
C ₂ H ₆ vol%	9.47	9.25	13.05	12.79	13.20	12.80	12.70	12.81	12.97	10.00	11.15				
C ₂ H ₄ vol%	7.37	7.36	4.97	4.65	4.85	4.41	4.58	4.27	4.20	7.46	4.76				
C ₃ 's vol%	5.68	5.85	3.71	2.88	2.70	2.18	2.38	2.35	2.29	5.63	2.79				
C ₄ 's vol%	2.20	2.27	1.01	0.74	0.78	0.58	0.61	0.61	0.48	1.84	0.92				
H ₂ S vol%	3.26	3.22	3.37	3.30	3.30	1.94	3.26	3.31	3.29	1.16	1.83				
NH ₃ vol%	1.22	1.21	1.25	1.24	1.24	1.24	1.22	1.24	1.23	0.54	0.79				
GROSS HEAT. VALUE BTU/SCF	884	888	881	823	820	803	811	822	819	833	778				
SPECIFIC GRAVITY	0.792	0.796	0.762	0.739	0.732	0.71	0.725	0.713	0.714	0.786	0.758				
RETORTED SHALE PROPERTIES:															
FISCHER ASSAY gal/ton	0.43	1.27	7.60	7.20	5.30	0.52	0.49	1.71	5.90	2.30	2.55				
FISCHER ASSAY OIL wt%	0.16	0.49	2.92	2.74	2.07	0.70	0.19	0.65	2.26	0.88	0.97				
FISCHER ASSAY WATER wt%	0.77	0.56	0.72	0.66	0.61	0.84	0.69	0.80	0.69	0.54	0.67				
FISCHER ASSAY GAS+LOSS wt%	0.06	0.25	0.38	1.11	0.61	0.64	0.61	0.40	0.59	0.52	0.49				
MINERAL CO ₂ wt%	20.23	19.62	18.71	18.43	19.43	19.55	19.43	19.74	19.35	18.12	19.05				
ORGANIC CARBON wt%	3.30	3.79	5.52	5.93	4.16	3.10	3.04	3.74	5.51	3.76	3.63				
IGNITION LOSS wt%	23.77	24.04	25.27	24.85	25.50	23.32	23.32	23.84	25.45	22.72	23.31				
CARBON wt%	8.82	9.14	10.62	10.96	9.46	8.43	8.34	9.12	10.79	8.87	8.83				
HYDROGEN wt%	0.33	0.38	0.72	0.82	0.53	0.34	0.32	0.42	0.68	0.45	0.42				
NITROGEN wt%	0.34	0.35	0.41	0.48	0.34	0.34	0.34	0.35	0.39	0.36	0.36				
MISCELLANEOUS:															
RETORT DROP in. H ₂ O/ft	1.09	1.04	0.94	0.94	1.08	1.42	1.43	1.41	1.10	0.78	0.79				
CARBONATE DECOMP wt%	1.35	2.26	8.64	9.67	2.68	2.96	2.29	0.60	1.31	4.75	5.11				
BED HEIGHT ft	24.5	24.5	24.5	24.5	24.5	24.5	24.5	24.5	24.5	24.5	24.5				

APPENDIX E

EQUIPMENT SUMMARY LIST

Feed Preparation

Primary Crusher

36" x 42" Traylor Bulldog, Blake-Type
Jaw Crusher, 100 HP, -5" setting
40 TPH capacity

Secondary Crusher

Allis-Chalmers Toothed Double Roll
Crusher, 25 HP each roll, 1 3/4" Tooth
to roll setting, 38 TPH capacity

Pilot Plant Retort System

Raw Shale Weighbelt

Ramsey Model 10-11" Vey-R-Weigh" Conveyor
Scale System for 24" wide conveyor to handle
4 TPH of shale weighing 85-90 lbs per cu. ft.
at a speed of 8.5 fpm (15.7 lbs per foot)

Retort

Vertical cylindrical vessel, 4'-6" O.D., 2'-6" I.D.
approximately 33' high with 1/4" carbon steel shell,
design pressure 10 psig. Retort lining consists of
one layer of 1/8" Kaiser Fiberfrac insulating felt,
7 1/2" of Kaiser Celocast 20 insulating castable
and 4 1/2" vertical course of Kaiser Aztex fire
clay brick. One top and two bottom Salina Model
MFS 1716 rotary gas seals.

Coalescer

Vertical cylindrical vessel approximately 7'
high, 30" O.D. with internal pipes of 20" and
10" for gas flow directional changes and optional
oil sprays in inlet pipe (field fabricated)

Electrostatic Precipitator

Research - Cottrell Tar precipitator, 6" ϕ by
6'0" long collecting pipe type, 2 1/2 KVA
220 Volt - 35000 volt - half wave rectifier.

Recycle Gas Blower

Hoffman centrifugal blower with 75 HP motor,
 ΔP of 5 psig and estimated capacity of 2500 SCFM

Air Blower

Spencer Turbine blower with 40 HP motor,
 ΔP of 80 oz. and estimated capacity of 800 CFM

APPENDIX E

EQUIPMENT SUMMARY LIST

Feed Preparation

Primary Crusher
36" x 42" Traylor Bulldog, Blake-Type
Jaw Crusher, 100 HP, -5" setting
40 TPH capacity

Secondary Crusher
Allis-Chalmers Toothed Double Roll
Crusher, 25 HP each roll, 1 3/4" Tooth
to roll setting, 38 TPH capacity

Pilot Plant Retort System

Raw Shale Weighbridge
Ramsey Model 10-11" Vey-R-Weigh" Conveyor
Scale System for 34" wide conveyor to handle
4 TPH of shale weighing 85-90 lbs per cu. ft.
at a speed of 8.5 fpm (15.7 lbs per foot)

Retort

Vertical cylindrical vessel, 4'-6" O.D., 2'-6" I.D.,
approximately 33' high with 1/4" carbon steel shell,
design pressure 10 psig. Retort lining consists of
one layer of 1/2" Kaiser Fiberflex insulating felt,
1 1/2" of Kaiser Celocast 50 insulating castable
and 4 1/2" vertical course of Kaiser Artek fire
clay brick. One top and two bottom Salina Model
M25 life rotary gas seals.

Condenser

Vertical cylindrical vessel approximately 7'
high, 30" O.D. with internal pipes of 20" and
10" for gas flow directional changes and optional
oil sprays in inlet pipe (field fabricated)

Electrostatic Precipitator

Research - Cottrell Tar precipitator, 6" x 6" by
6'0" long collecting pipe type, 1 1/2 KVA
250 Volt - 35000 volt - half wave rectifier.

Recycle Gas Blower

Holman centrifugal blower with 75 HP motor,
A P of 2 psig and estimated capacity of 3500 SCFM

Air Blower

Spencer Turbine blower with 40 HP motor,
A P of 80 ps. and estimated capacity of 800 CFM

External Fired Heaters

Brown Fintube Type 102 indirect fired heaters with 20 foot section of HK40 firetube, duty 600 M BTU/h at 406-635 SCFM of gas up to gas outlet temperature of 1300°F

Retorted Shale Weighbelt

Ramsey Model 10-11 "Vey-R-Weigh" conveyor Scale System for 24" wide conveyor to handle 4 TPH of shale weighing 85-90 lbs per cu. ft. at a speed of 8.5 fpm (15.7 lbs per foot)

Semi-Works Retort System

Raw Shale Weighbelt

Ramsey Model 10-11 "Vey-R-Weigh" Conveyor Shale System for 24" wide conveyor to handle 43 TPH of shale weighing 85-90 lbs per cu. ft. at a speed of 89 fpm (15.7 per foot)

Retort

Vertical cylindrical vessel 10'-6" O.D., 8'-6" I.D. approximately 49' high with 1/4" carbon steel shell design pressure 10 psig. Retort lining consists of two layers of 1/8" Kaiser Fiberfrax insulating felt, 2 3/4" of Kaiser Celocast -20 insulating castable and two vertical courses of 4 1/2" Kaiser Jaybee SM fire clay brick. One top and two bottom Salina Model MFS 1716 rotary gas seals.

Coalescer

Vertical cylindrical vessel, 5'-0" O.D. approximately 14' high with an internal pipe 32" O.D., 5 1/2 feet packed section and oil wash sprays

Electrostatic Precipitator

Koppers concentric ring type precipitator 10' Ø by 27' high, 35 KVA silicon rectifier control console

Recycle Gas Blower

Spencer Turbine Turbo Blower with 700 HP motor, 120 oz. Δ P and estimated capacity of 14,000 CFM

Air Blower

Spencer Turbine Blower with 150 HP motor, 80 oz. Δ P and estimated capacity of 3600 SCFM

Bottom Gas Cooler

Horizontal unit, gas on shell side, water on tube side, 784 Ft², duty approximately, 1MM BTU/h

Bottom Gas Cooler
Horizontal unit, gas on shell side, water on
tube side, 784 Ft², duty approximately, 1MM BTU/H

Air Blower
Spencer Turbine Blower with 150 HP motor, 80 oz.
A.P. and estimated capacity of 3600 SCFM

Recycle Gas Blower
Spencer Turbine Turbo Blower with 700 HP
motor, 120 oz. A.P. and estimated capacity of 14,000
CFM

Electrostatic Precipitator
Nepco's concentric ring type precipitator
16' 9" by 27' high, 35 KVA silicon rectifier
control console

Condenser
Vertical cylindrical vessel, 5'-0" O.D., approximately
14' high with an internal pipe 32" O.D., 5 1/2
feet packed section and oil wash sprays

Reform
Vertical cylindrical vessel 10'-6" O.D., 8'-8" I.D.,
approximately 43' high with 1/4" carbon steel shell
design pressure 10 psig. Reform lining consists
of two layers of 1/8" Kaiser Fibertrax insulating
felt, 2 3/4" of Kaiser Celocast - 30 insulating
castable and two vertical courses of 4 1/2" Kaiser
Jaymac SM fire clay brick. One top and two bottom
Kaiser Model MPS 1716 rotary gas seals.

Raw Shale Weighbelt
Ramsey Model 10-11 "Vey-R-Weigh" Conveyor
Scale System for 24" wide conveyor to handle
4 TPH of shale weighing 85-90 lbs per cu. ft.
at a speed of 8.2 fpm (15.7 lbs per foot)

Semi-Works Reform System

External Fired Heater
Brown Fintube Type 102 indirect fired
heaters with 20 foot section of HR40 firetube,
duty 600 M BTU/H at 400-600 SCFM of gas up to
gas outlet temperature of 1300° F

External Fired Heaters

Smalling Engineering and Equipment Co., indirect fired heaters with stainless steel tubes and tubesheets, duty 7 MM BTU/hr at 3,500 to 5,000 SCMF gas rate up to gas exit temperature of 1400°F

Retorted Shale Weighbelt

Ramsey Model 10-11 "Vey-R-Weigh" Conveyor Scale system for 24" wide conveyor to handle 43 TPH of shale weighing 85-90 lbs per cu. ft. at a speed of 89 fpm (15.7 lbs per foot)

Miscellaneous

Thermal Oxidizer

Gas Combustion Retort #3 fire box 30 feet high with 60 sq. ft. cross section area, a checker brick system in bottom and John Zink burner and controls, unit to handle 4100 SCFM of excess gas at 2000°F operating temperature of oxidizer

Steam Generators

2 Cleaver Brooks package boilers complete with boiler feed system each capable of generating 1725 #/hr of steam of 50 psig

Instrument Air

Ingersoll-Rand package air compressor complete with dryer capable of producing 125 SCFM of air at 100 psig

External Fired Heaters
Smalley Engineering and Equipment Co., indirect
fired heaters with stainless steel tubes and
superheaters, duty 7 MM BTU/hr at 3,500 to 5,000
SCFM gas rate up to gas exit temperature of 1400°F


Reformed Shale Weighbelt
Ramsey Model 10-11 "Vey-R-Weigh" Conveyor
Scale system for 34" wide conveyor to handle
43 TPD of shale weighing 85-90 lbs per cu. ft.
at a speed of 89 fpm (15.7 lbs per foot)

Miscellaneous

Thermal Oxidizer
Gas Combustion Refractor #3 fire box 30 feet high
with 60 sq. ft. cross section area, a checker
brick system in bottom and John Erik burner
and controls, unit to handle 4100 SCFM of excess
gas at 1800°F operating temperature of oxidizer

Steam Generators
3 Cleaver Brooks package boilers complete with
boiler feed system each capable of generating
1725 #/hr of steam at 20 psig

Instrument Air
Ingersoll-Rand package air compressor complete
with dryer capable of producing 125 SCFM of air
at 100 psig



NOTE: This Print is the property of
PARAHO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
furnished by us.


PARAHO OIL SHALE
DEMONSTRATION


TITLE
RAW OIL SHALE
FEED PREPARATION
FACILITIES

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

DWG. 1









NOTE: This Pilot is the property of PARAHU OIL SHALE CORPORATION. It shall not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.

PARAHU OIL SHALE DEMONSTRATION		McKEE ENGINEERS AND CONSTRUCTORS CLEVELAND, OHIO
SOLIDS HANDLING SYSTEMS PILOT-SEMI-WORKS PLANTS		
DWG. 2	SCALE: 1" = 10'	REVISION: 1




000000-000




NOTE: This Pilot is the property of PARAGO DEVELOPMENT CORPORATION. It must not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.

PARAGO OIL SHALE
DEMONSTRATION
ENGINEERING FLOW DIAGRAM
PILOT PLANT
DIRECT & INDIRECT HEATED MODES
SCALE: 1/8" = 1'-0"

McKEE
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO
DWG. 3






NOTE: This Print is the property of PARAH OIL SHALE DEMONSTRATION CORPORATION. It must not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.

PARAH OIL SHALE
DEMONSTRATION
ENGINEERING FLOW DIAGRAM
SEMI-WORKS PLANT
(DIRECT HEATED MODE)

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO


DWG. 4

REVISION
1



WEST


SHALE OIL STORAGE SYSTEMS



COMPRESSOR AIR
SYSTEM



EXHAUSTION OF
SYSTEM

COOLING WATER
SYSTEM




DUST COLLECTION SYSTEMS

STEAM SYSTEM



THERMAL OXIDIZER SYSTEM



NOTE: This Print is the property of
PARAHQ DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
performed by this organization.

PARAHO OIL SHALE DEMONSTRATION


TITLE
AUXILIARY SYSTEMS
STEAM, DUST COLLECTION
& THERMAL OXIDIZER




McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

DWG 7



STEAM SYSTEM






NOTE: This Print is the property of PARAH OIL SHALE DEVELOPMENT CORPORATION. It must not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.

CLIENT
PARAH OIL SHALE
DEMONSTRATION
TITLE
PILOT PLANT
RETORT ASSEMBLY
SCALE
R. M. NO.

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO




DWG.8





NOTE: This drawing is for information only. It is not to be used for construction purposes. The design is subject to change without notice. The manufacturer is not responsible for any errors or omissions in this drawing. The manufacturer is not responsible for any damage or injury resulting from the use of this drawing.

NOTE: RETORT CROSS
SECTIONAL AREA
49.251 SQ. FT. INSIDE
REFRACTORY.



NOTE: This Print is the property of
PARAHO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
furnished by us.

CLIENT
PARAHO OIL SHALE
DEMONSTRATION



TITLE
SEMI-WORKS RETORT
ASSEMBLY

SCALE
AS SHOWN

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

DWG. 9





NOTE: This Print is the property of PARAH O DEVELOPMENT CORPORATION. It must not be traced nor reproduced in any manner nor shall it be submitted to outside parties for examination without our consent. It shall be used only as a means of reference to work designed or furnished by us.

PARAH O OIL SHALE
DEMONSTRATION


SEMI-WORKS RETORT
DIRECT & INDIRECT
PROCESS COALESCERS

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO


DWG.10

REVISION





NOTE: This type of separator is used for separating oil and water from gas. The gas enters from the top and passes through a series of saffles which cause the gas to change direction and the oil and water to settle. The oil and water then pass through a series of horizontal plates which further separate the oil and water from the gas. The gas then exits from the top and the oil and water exit from the bottom.



NOTE: This Print is the property of
PARAHO DEVELOPMENT CORPORATION. It
must not be traced nor reproduced in any manner
nor shall it be submitted to outside parties for
examination without our consent. It shall be used
only as a means of reference to work designed or
furnished by us.

CLIENT

PARAHO OIL SHALE
DEMONSTRATION

TITLE

PILOT PLANT
COALESCER ASSEMBLY

SCALE


S. M. NO.

McKee
ENGINEERS AND CONSTRUCTORS
CLEVELAND, OHIO

DWG.11

REVISION





APPENDIX G

GLOSSARY

Bed height	-	The vertical thickness of the shale bed in the retort measured between the grate retarder plate and the bottom of the off gas collector.
Bottom gas (air)-		Gas (air) quantity to the bottom distributor located in the grate structure at the bottom of the retort.
BTU	-	British thermal unit heating value. The heat needed to raise the temperature of one pound of water one degree Fahrenheit.
Carbon residue (residual carbon)	-	The carbonaceous solid organic residue from pyrolysis of oil shale intimately dispersed in the retorted shale particles.
Clinkers	-	Fused inorganic matter of oil shale owing to excessive temperature level.
Coalescer	-	Part of the oil recovery system wherein an oil spray contacts the retort off-gas and a portion of the contained oil mist is agglomerated to a liquid oil stream.
Commercial Evaluation	-	An investment and operating cost study of a commercial oil shale processing facility including mining, shale preparation, retorting, pre-refining shale oil (up-grading) retorted shale disposal, and supporting facilities.
Conveyor scales	-	A device on a belt conveyor which senses continuously the weight of material being carried by the belt. The instrumentation converts the weight sensor signal and a belt speed signal to a weight rate and accumulative counter.
Dilution Gas	-	Clean retort gas which is mixed with air to moderate the combustion zone temperature.
Direct Heated Mode	-	Oil shale processing where heat is released inside the retort by combustion of fuel with injected air.
Distributor (Top)-		(Gas) and/or (Air) The quantity of gas and/or air entering the top distribution level in the retort.

APPENDIX G

GLOSSARY

Bed height	-	The vertical thickness of the shale bed in the retort measured between the grate and the bottom of the off-gas collector.
Bottom gas (air)-	-	Gas (air) quantity to the bottom distributor located in the grate structure at the bottom of the retort.
Btu	-	British thermal unit heating value. The heat needed to raise the temperature of one pound of water one degree Fahrenheit.
Carbon residue (residual carbon)	-	The carbonaceous solid organic residue from pyrolysis of oil shale intimately dispersed in the retorted shale particles.
Clinkers	-	Fused inorganic matter of oil shale owing to excessive temperature level.
Coalescer	-	Part of the oil recovery system wherein an oil spray contacts the retort off-gas and a portion of the contained oil mist is agglomerated to a liquid oil stream.
Commercial Evaluation	-	An investment and operating cost study of a commercial oil shale processing facility including mining, shale preparation, retorting, pre-refining shale oil (up-grading) retorted shale disposal, and supporting facilities.
Conveyor scales	-	A device on a belt conveyor which senses continuously the weight of material being carried by the belt. The instrumentation converts the weight sensor signal and a belt speed signal to a weight rate and accumulative counter.
Dilution Gas	-	Clean retort gas which is mixed with air to moderate the combustion zone temperature.
Direct Heated Mode	-	Oil shale processing where heat is released inside the retort by combustion of fuel with injected air.
Distributor (Top)-	-	(Gas) and/or (Air) The quantity of gas and/or air entering the top distribution level in the retort.

Distributor (Mid) -	(gas) and/or (Air) The quantity of gas and/or air entering the middle distribution level in the retort
Distributor (Btm) -	(Gas and/or (Air) The quantity of gas and/or air entering the bottom distribution level at the grate.
Dolomite	- A predominate mineral of oil shale containing equal quantities of calcium and magnesium carbonate.
ESP (Electrostatic-Precipitator)	Part of the oil recovery system wherein oil droplets are subjected to a high voltage electrostatic field. The oil droplets are impelled by the field to contact a surface to form a film of oil which drains continuously.
Fischer Assay -	A laboratory method for determining the potential oil yield from a sample of oil shale. Described in detail in Volume 4.
Full Size Module -	A large oil shale processing plant which would be one section (or module) of a commercial oil shale processing plant.
Gas Chromatograph-(GC)	Equipment for determining the composition of a gas mixture.
Grate -	A device in the bottom of a retort for controlling the descent of shale through the retort.
Gross Heating Value	- Equal to the higher heating value. The heat of combustion determined in a calorimeter and is based on the recovery of water (from combustion) as a liquid.
Heat Inventory -	Total sensible heat of the retort equipment and its contents.
Indirect Heated Mode	- Oil shale processing using hot gas heated in an external heater to supply the process heat requirements.
Kerogen -	A solid organic material containing all of the energy values in oil shale.
Marlstone	- A geological classification for oil shale. A sedimentary rock containing mixtures of Dolomite limestones and argillaceous materials.

<p>(gas) and/or (Air) The quantity of gas and/or air entering the middle distribution level in the retort</p>	-	Distributor (Mid)
<p>(Gas and/or (Air) The quantity of gas and/or air entering the bottom distribution level at the grate.</p>	-	Distributor (Btm)
<p>A predominance mineral of oil shale containing equal quantities of calcium and magnesium carbonate.</p>	-	Dolomite
<p>Part of the oil recovery system wherein oil droplets are subjected to a high voltage electrostatic field. The oil droplets are impelled by the field to contact a surface to form a film of oil which drains continuously.</p>	-	ESP (Electrostatic Precipitator)
<p>A laboratory method for determining the potential oil yield from a sample of oil shale. Described in detail in Volume 4.</p>	-	Fischer Assay
<p>A large oil shale processing plant which would be one section (or module) of a commercial oil shale processing plant.</p>	-	Full Size Module
<p>Equipment for determining the composition of a gas mixture.</p>	-	Gas Chromatograph (GC)
<p>A device in the bottom of a retort for controlling the descent of shale through the retort.</p>	-	Grate
<p>Equal to the higher heating value. The heat of combustion determined in a calorimeter and is based on the recovery of water (from combustion) as a liquid.</p>	-	Gross Heating Value
<p>Total sensible heat of the retort equipment and its contents.</p>	-	Heat Inventory
<p>Oil shale processing using hot gas heated in an external heater to supply the process heat requirements.</p>	-	Indirect Heated Mode
<p>A solid organic material containing all of the energy values in oil shale.</p>	-	Kerogen
<p>A geological classification for oil shale. A sedimentary rock containing mixtures of dolomite, limestone and crystalline materials.</p>	-	Limestone

Mass Rate	-	Shale processing rate usually expressed as pounds of raw shale per hour per square foot of retort cross-sectional area.
Mid Gas (Air)	-	Gas (air) quantity to the middle distributor.
Mine Run Shale	-	Oil shale blasted from the oil shale formation in the mine. The largest lumps are usually less than 30 inches in the longest dimension.
Off-gas	-	Retort gas containing oil mist as it leaves the retort bed through the off-gas collectors.
Off-gas Collectors	-	A gas removal device for the top of the shale bed. In the Semi-Works retort, it consists of two inverted transverse channels within the shale bed. The gas emerging from the channels flows to an external manifold.
Oil mist	-	A dispersoid of liquid oil droplets in an entraining gas stream.
Orifice Meter	-	A device for measuring fluid flow rate from the measured loss of pressure when the fluid flows through a restricting orifice of smaller diameter than the pipe. Specifications set by the National Gas Association.
Orsat Apparatus	-	Gas analysis apparatus for determination of CO ₂ , CO and O ₂ in a gas stream.
Pilot Plant	-	Oil shale processing system of a vertical kiln (retort) with associated solids, gas, and liquid oil handling equipment described in detail in Section 5.1. It was used principally for retorting process studies and operation planning for the Semi-Works Plant.
Pour Point	-	The congealing temperature of oil as tested by prescribed ASTM procedure.
Pyrolysis	-	The thermal decomposition of kerogen starting at approximately 500°F and rapidly reaching complete decomposition at 900°F.
Refluxing	-	Condensation of oil vapors on shale descending towards the retorting zone.
Retort	-	A kiln or vessel for heating oil shale to temperatures to form oil and gas products.

Retort	-	A kiln or vessel for heating oil shale to temperatures to form oil and gas products.
Refining	-	Combustion of oil vapors on shale descending towards the retorting zone.
Pyrolysis	-	The thermal decomposition of kerogen starting at approximately 500°F and rapidly reaching complete decomposition at 800°F.
Pour Point	-	The condensing temperature of oil as tested by prescribed ASTM procedure.
Pilot Plant	-	Oil shale processing system of a vertical kiln (retort) with associated solids, gas, and liquid oil handling equipment described in detail in Section 5.1. It was used principally for retorting process studies and operation planning for the Semi-Works Plant.
Orsat Apparatus	-	Gas analysis apparatus for determination of CO ₂ , CO and O ₂ in a gas stream.
Orifice Meter	-	A device for measuring fluid flow rate from the measured loss of pressure when the fluid flows through a restricting orifice of smaller diameter than the pipe. Specifications set by the National Gas Association.
Oil Mist	-	A dispersed oil droplet in an entraining gas stream.
Oil-gas Collectors	-	A gas removal device for the top of the shale bed. In the Semi-Works retort, it consists of two inverted transverse channels within the shale bed. The gas emerging from the channels flows to an external manifold.
Off-gas	-	Retort gas containing oil mist as it leaves the retort bed through the oil-gas collectors.
Mine Run Shale	-	Oil shale blasted from the oil shale formation in the mine. The largest lumps are usually less than 30 inches in the longest dimension.
Mid Gas (Air)	-	Gas (air) quantity to the middle distributor.
Mass Rate	-	Shale processing rate usually expressed as pounds of raw shale per hour per square foot of retort cross-sectional area.

- Retorted Shale - The residue from the retorting of oil shale composed of inorganic minerals and residual carbon from pyrolysis of kerogen.
- Run - An operation or series of operations having the same objective or purpose.
- SCF - Standard cubic feet of gas. The measured volume is converted to the volume at 60 degrees Fahrenheit and 14.7 pounds per square inch absolute pressure.
- Seal (rotary) - A device for passing solid particulate matter and simultaneously preventing the passage of gas into or out of the retort.
- Semi-Works Plant - Oil shale processing system of a vertical kiln (retort) with associated solids, gas and liquids oil handling equipment described in detail in Section 5.2. It is structurally and functionally equivalent to a commercial oil shale processing plant.
- Shale size range - The size range of shale particles, as used in the test data. This is measured by minimum square opening of the top and bottom deck screens in the crushing plant during the preparation of the raw shale in question.
- Standard deviation - A statistical measure of the spread or variability of data. In normally distributed data of an adequate population, two thirds of the data will be included in band plus and minus one standard deviation about the mean.
- Standby Period - A period in retort operations (from minutes to several hours duration) where flows of shale and processing gas and air are stopped. Retained heat in the shale bed permits a resumption of operations by restarting process flows.
- Startup - A planned stepwise procedure for the transition from a cold static bed of shale in the retort to a continuous stable retorting operation.
- Temperature Profile - The vertical temperature gradient through the retort bed as measured by the temperature-pressure probe assembly.

Retorted shale -	The residue from the retorting of oil shale composed of inorganic minerals and residual carbon from pyrolysis of kerogen.
Run -	An operation or series of operations having the same objective or purpose.
SCF -	Standard cubic feet of gas. The measured volume is converted to the volume at 60 degrees Fahrenheit and 14.7 pounds per square inch absolute pressure.
Seal (rotary) -	A device for passing solid particulate matter and simultaneously preventing the passage of gas into or out of the retort.
Semi-Works Plant -	Oil shale processing system of a vertical kiln (retort) with associated solids, gas and liquids oil handling equipment described in detail in Section 5.2. It is structurally and functionally equivalent to a commercial oil shale processing plant.
Shale size range -	The size range of shale particles, as used in the test data. This is measured by minimum aperture opening of the top and bottom deck screens in the crushing plant during the preparation of the raw shale in question.
Standard deviation -	A statistical measure of the spread or variability of data. In normally distributed data of an adequate population, two thirds of the data will be included in band plus and minus one standard deviation about the mean.
Standby Period -	A period in retort operations (from minutes to several hours duration) where flows of shale and processing gas and air are stopped. Retained heat in the shale bed permits a resumption of operations by restarting process flows.
Startup -	A planned stepwise procedure for the transition from a cold static bed of shale in the retort to a continuous stable retorting operation.
Temperature Profile -	The vertical temperature gradient through the retort bed as measured by the temperature-pressure probe assembly.

APPENDIX B

Test Period	-	A continuous period of time of stable operations during a retort run where operating data and laboratory results are obtained and summarized.
Thermal Oxidizer	-	A gas incinerator for the disposal of gas with excess air and supplemental fuel if required.
Top Gas (air)	-	Gas (air) quantity to the top distributor.
Vertical Kiln	-	A vertical vessel for continuous counter-current processing of granular solids with gas.
Void Space	-	In a bulk of crushed and screened solid material, the volume of air space is called the void space. It is about 40% of the entire volume.
Weighbelt	-	Conveyor scales.
°F	-	degrees Fahrenheit
F.A.	-	Fischer Assay
GPM	-	Gallons (U.S.) per minute
GPT	-	Gallons Per Ton
lbs/hr/ft ²	-	Pounds of raw shale per square foot of the vessel inside diameter per hour
lbs/MSCF	-	Pounds per thousand standard cubic foot
mid	-	middle
O.D.	-	Outside Diameter
VR	-	Pilot Plant
raw shale	-	Mined oil shale which has been crushed and screened. Retort feed is a synonym
SS	-	Saw shale
SCF/T	-	Standard cubic foot per ton of raw shale
SUF	-	Saybolt Universal Seconds. A test for viscosity.
SW	-	Semi-Works
Ton (T)	-	short ton 2000 pounds

Test Period

A continuous period of time of stable operations during a test run where operating data and laboratory results are obtained and summarized.

Thermal Oxidizer -

A gas incinerator for the disposal of gas with excess air and supplemental fuel if required.

Top Gas (air) -

Gas (air) quantity to the top distributor.

Vertical Kilo -

A vertical vessel for continuous counter-current processing of granular solids with gas.

Void Space -

In a bulk of crushed and screened solid material, the volume of air space is called the void space. It is about 40% of the entire volume.

Weightbelt -

Conveyor scales.

APPENDIX H
LIST OF ABBREVIATIONS

°API	-	(degrees API) Specific Gravity of oil measured on the scale defined by the American Petroleum Institute
Ar	-	Argon
BS	-	Bottom sediment
Btm	-	Bottom
BTU	-	British Thermal Unit
C5+	-	Liquid hydrocarbon mixtures with components having 5 or more carbon atoms
dist	-	(distri) distributor
Dmmd	-	mean particle size of mist (in microns) See Laboratory Report, Volume 4
°F	-	degrees Fahrenheit
F.A.	-	Fischer Assay
GPM	-	Gallons (U.S.) per minute
GPT	-	Gallons Per Ton
lbs/hr/ft ²	-	Pounds of raw shale per square foot of the vessel inside diameter per hour
lbs/MSCF	-	Pounds per thousand standard cubic foot
mid	-	middle
O.D.	-	Outside diameter
PP	-	Pilot Plant
raw shale	-	Mined oil shale which has been crushed and screened. Retort feed is a synonym
RS	-	Raw shale
SCF/T	-	Standard cubic feet per ton of raw shale
SUS	-	Saybolt Universal Seconds. A test for viscosity.
SW	-	Semi-Works
Ton (T)	-	short ton : 2000 pounds

Baran

APPENDIX B
LIST OF ABBREVIATIONS

°API	-	(degrees API) Specific Gravity of oil measured on the scale defined by the American Petroleum Institute
Ar	-	Argon
BS	-	Bottom sediment
Bm	-	Bottom
BTU	-	British Thermal Unit
C ₅ +	-	liquid hydrocarbon mixtures with components having 5 or more carbon atoms
Dist	-	(distill) distributor
D ₄₀	-	mean particle size of mist (in microns) See Laboratory Report, Volume 4
°F	-	degrees Fahrenheit
F.A.	-	Fischer Assay
GPM	-	Gallons (U.S.) per minute
GPT	-	Gallons per Ton
lbs/ft ²	-	Pounds of raw shale per square foot of the vessel inside diameter per hour
lbs/MSCF	-	Pounds per thousand standard cubic foot
Mid	-	Middle
O.D.	-	Outside diameter
PP	-	Pilot Plant
raw shale	-	Mined oil shale which has been crushed and screened. Retort feed is a synonym
RS	-	Raw shale
SCF/T	-	Standard cubic feet per ton of raw shale
SUS	-	Saybolt Universal Seconds. A test for viscosity.
SW	-	Semi-Works
Ton (T)	-	short ton 2000 pounds

TPH - Tons per hour
wt.% - Weight percent

Barab

W.C. 9 - Weight percent
T.M. 9 - Tons per hour

